



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

February 17, 2020

CALL NO. 312
CONTRACT ID NO. 202054
ADDENDUM # 2

Subject: WARREN COUNTY FD05 114 1402 000-003
Letting February 21, 2020

- (1) Revised - Special Note - Page 9 of 50
- (2) Revised - Proposal Bid Item - Page 50 of 50

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mw
Enclosures

DEFERRED PAYMENT

The successful bidder on this project may request a work order with an effective date prior to June 15, 2020. The successful bidder must make the request in writing to the Department. The Department will issue a work at the request of the Contractor with the distinct understanding that payment for any Work Performed Estimates may be delayed until July 15, 2020. Unless the successful bidder requests an earlier work order date, the Department will issue a work order on June 15, 2020 for this project.

SURFACING AREAS

The Department estimates the mainline surfacing width to be 24 feet.

The Department estimates the total mainline area to be surfaced to be 46,277 square yards.

The Department estimates the shoulder width to be 1.5 foot on each side.

The Department estimates the total shoulder area to be surfaced to be 5,104 square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

DGA BASE FOR SHOULDERS

Unless otherwise noted, the Department estimates the rate of application for DGA Base for Shoulders to be 115 lbs/sy per inch of depth. The Department will not measure necessary grading and/or shaping of existing shoulders prior to placing of DGA Base, but shall be incidental to the Contract unit price per ton for DGA Base.

Accept payment at the Contract unit price per ton as full compensation for all labor, materials, equipment, and incidentals for grading and/or shaping of existing shoulders and furnishing, placing, and compacting the DGA Base.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

PROPOSAL BID ITEMS

Report Date 2/17/20

Section: 0001 - MICROSURFACE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	21652EN		MICROSURFACING-LEVELING COURSE (REVISED: 2-17-20)	48,877.00	SQYD		\$	
0020	24958EC		MICROSURFACING-SURFACE COURSE - TYPE D (REVISED: 2-17-20)	46,277.00	SQYD		\$	

Section: 0002 - THINLAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0030	00190		LEVELING & WEDGING PG64-22	108.00	TON		\$	
0040	02676		MOBILIZATION FOR MILL & TEXT (REVISED: 2-10-20)	1.00	LS		\$	
0050	21653ES403		CL2 ASPH SURF NO.4D PG64-22 (REVISED: 2-17-20)	1,910.00	TON		\$	
0060	24964EC		FINE MILLING	1,820.00	SQYD		\$	
0070	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING (REVISED: 2-17-20)	13.00	TON		\$	

Section: 0003 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	00001		DGA BASE	450.00	TON		\$	
0090	02562		TEMPORARY SIGNS	470.00	SQFT		\$	
0100	02650		MAINTAIN & CONTROL TRAFFIC (ADDED: 2-10-20)	1.00	LS		\$	
0110	02697		EDGE LINE RUMBLE STRIPS	14,785.00	LF		\$	
0120	06510		PAVE STRIPING-TEMP PAINT-4 IN	30,625.00	LF		\$	
0130	06514		PAVE STRIPING-PERM PAINT-4 IN	61,250.00	LF		\$	
0140	06568		PAVE MARKING-THERMO STOP BAR-24IN	30.00	LF		\$	
0150	06574		PAVE MARKING-THERMO CURV ARROW	4.00	EACH		\$	
0160	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0170	23260EC		PAVE MARK-THERMO-24 IN Y	180.00	LF		\$	

Section: 0004 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0180	02569		DEMOBILIZATION	1.00	LS		\$	