

Andy Beshear Governor

Jim Gray Secretary

February 21, 2022

CALL NO. 315

CONTRACT ID NO. 222080

ADDENDUM # 1

Subject: Jefferson County, FD05 056 031E 015-017 Letting February 24, 2022

- (1) Added Special Notes Pages 17(a)-17(c) of 60
- (2) Revised Thermoplastic Summary Page 38 of 60
- (3) Revised Proposal Bid Items Page 60 of 60

Proposal revisions are available at $\frac{\text{http://transportation.ky.gov/Construction-Procurement/.}}{\text{Procurement/.}}$

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

Rachel Mills, P.E.

Director

Division of Construction Procurement

Kachel Mille

RM:mr

Enclosures

COORDINATION OF WORK WITH OTHERS

Be advised, there are active project(s) adjacent to or within this project. These may be KYTC administered contracts or work being performed as part of a KYTC issued encroachment permit. The Engineer will help coordinate the work of any other Contractors or permit holders within the limits of this project. See Sections 105.06, 107.06 and 107.14 of the Standard Specifications.

Adjacent to this project, starting at the southern limit (approximate milepoint 15.895), will be a separate, KYTC resurfacing project, planned to occur later in 2022. The contractor is advised that coordination will be required between these two projects and minor, temporary striping may need to be installed based on the sequence of the resurfacing. The contractor shall inform the Engineer as soon as practical of the anticipated resurfacing schedule to prevent any conflicts.

Coordination with Others D-5/US 31E 2/14/2022

SPECIAL NOTE FOR PAVEMENT MARKING MODIFICATIONS

This Proposal may include drawings depicting anticipated pavement marking modifications along the route to be resurfaced. However, per Section 713.03.01 of the Standard Specifications, the Contractor shall still be required to submit a record of existing pavement markings prior to beginning resurfacing activities. The Department requests these records be submitted at least two weeks prior to milling or paving in order to coordinate all desired changes between the District Traffic Engineer and the Contractor. All changes will be returned to the Contractor to ensure the desired modifications can be performed during final surfacing. As the Contractor is responsible for implementing any pavement marking changes, it is highly recommended any questions are addressed to the Project Engineer prior to striping. Any incorrect markings will be removed and replaced with the proper markings at the Contractor's expense and in a manner approved by the Engineer.


SPECIAL NOTE FOR ON-STREET PARKING RESTRICTIONS

On routes which contain areas with on-street parking, advance warning shall be given to residents and businesses prior to resurfacing activities commencing. Signage advertising the dates and times when parking will be restricted shall be purchased and installed by the Contractor, at no expense to the Department and shall be considered incidental to the bid item for MAINTAIN AND CONTROL TRAFFIC. The "NO STOPPING" signs shall be installed a minimum of two business days (48 hours) prior to any parking restrictions and shall be removed as soon as the restrictions are no longer applicable.

Signs shall be installed along the side(s) of the route where stopping will be restricted, at a maximum spacing of 80 feet between signs. At intersecting side streets and/or alleys, place signs a maximum of 30 feet in each direction from the approach, along the route to be resurfaced.

No Stopping signs shall be purchased from Louisville Metro Public Works in order to utilize towing services provided by the Louisville Metro Police Department. The Contractor shall contact Tonya Richardson at LMPW at (502) 574-3121 or Tonya.Richardson@louisvilleky.gov to place their sign order. LMPW will need a minimum of two weeks notice of the sign needs to ensure they have adequate quantity in stock. The Contractor will need to specify the quantity of signs needed, the dates and times restrictions will be in place and the day the signs will need to be acquired.

The cost is anticipated to be \$6.75 per sign. The Contractor shall remit payment and obtain signs at the LMPW office at 444 South 5th Street, 4th Floor in Downtown Louisville. Signs may be re-used, on this project, as long as they are in like-new and legible condition and date and time restrictions still apply.



THERMOPLASTIC INTERSECTION PAVEMENT MARKINGS SUMMARY FD05 056 031E 015-017 **JEFFERSON COUNTY**

| MILE | | X-WALKS | STOP BARS | ARR | ARROWS | ONLY | TRACKING | CROSS | TAPERS & TRANSVERSE STRIPES |
|--------|-------------------------|---------|-----------|-------|--------|------|----------|-------|--------------------------------|
| POINT | INIERSECTION | 6 INCH | 24 INCH | CURVE | COMBO | | 6 INCH | НАТСН | 6 INCH |
| | | LF | LF | EACH | EACH | EACH | LF | SQFT | LF |
| 15.901 | US 150/Broadway | 260 | 40 | 3 | | | 09 | 80 | 190 |
| 16.037 | Rogers St | | | | | | | 110 | 240 |
| 16.137 | Payne Street | 400 | 72 | | | | | 120 | 320 |
| 16.200 | Hull St | | | | | | | 120 | 420 |
| 16.298 | Lexington Road | 490 | 08 | 3 | 4 | 2 | | 105 | 250 |
| 16.422 | Liberty Street | 620 | 09 | | | | | | |
| 16.541 | KY 864/Jefferson Street | 300 | 106 | 11 | င | - | 100 | | |
| 16.635 | US 31E/Market Street | 550 | 32 | | 2 | | | | |
| | PROJECT TOTALS | 2620 | 390 | 17 | 6 | 3 | 150 | 535 | 1420 |

PROPOSAL BID ITEMS

REVISED ADDENDUM #1 2/21/2022 Contract ID: 222080 Page 60 of 60

Page 1 of 1

Report Date 2/21/22

Section: 0001 - PAVING

| LINE | BID CODE | ALT DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|------------|---|-----------|------|-----------|----|--------|
| 0010 | 00190 | LEVELING & WEDGING PG64-22 | 168.00 | TON | | \$ | |
| 0020 | 00307 | CL2 ASPH SURF 0.38B PG64-22 | 1,675.00 | TON | | \$ | |
| 0030 | 02562 | TEMPORARY SIGNS | 310.00 | SQFT | | \$ | |
| 0040 | 02650 | MAINTAIN & CONTROL TRAFFIC | 1.00 | LS | | \$ | |
| 0050 | 02671 | PORTABLE CHANGEABLE MESSAGE SIGN | 2.00 | EACH | | \$ | |
| 0060 | 02676 | MOBILIZATION FOR MILL & TEXT | 1.00 | LS | | \$ | |
| 0070 | 02677 | ASPHALT PAVE MILLING & TEXTURING | 1,675.00 | TON | | \$ | |
| 080 | 02720 | SIDEWALK-4 IN CONCRETE | 120.00 | SQYD | | \$ | |
| 0090 | 02775 | ARROW PANEL | 2.00 | EACH | | \$ | |
| 0100 | 04792 | CONDUIT-1 IN | 130.00 | LF | | \$ | |
| 0110 | 04811 | ELECTRICAL JUNCTION BOX TYPE B | 18.00 | EACH | | \$ | |
| 0120 | 04820 | TRENCHING AND BACKFILLING | 152.00 | LF | | \$ | |
| 0130 | 04830 | LOOP WIRE | 11,025.00 | LF | | \$ | |
| 0140 | 04850 | CABLE-NO. 14/1 PAIR | 3,205.00 | LF | | \$ | |
| 0150 | 04895 | LOOP SAW SLOT AND FILL | 4,465.00 | LF | | \$ | |
| 0160 | 04960 | REMOVE AND REPLACE SIDEWALK (TRAFFIC LOOPS) | 11.00 | SQYD | | \$ | |
| 0170 | 06510 | PAVE STRIPING-TEMP PAINT-4 IN (REVISED 2-21-2022) | 12,000.00 | LF | | \$ | |
| 0175 | 06514 | PAVE STRIPING-PERM PAINT-4 IN (ADDED 2-21-2022) | 400.00 | LF | | \$ | |
| 0180 | 06542 | PAVE STRIPING-THERMO-6 IN W (REVISED 2-21-2022) | 6,100.00 | LF | | \$ | |
| 190 | 06543 | PAVE STRIPING-THERMO-6 IN Y (REVISED 2-21-2022) | 7,050.00 | LF | | \$ | |
| 195 | 06546 | PAVE STRIPING-THERMO-12 IN W (ADDED 2-21-2022) | 700.00 | LF | | \$ | |
| 200 | 06565 | PAVE MARKING-THERMO X-WALK-6 IN (REVISED 2-21-2022) | 2,620.00 | LF | | \$ | |
| 0210 | 06568 | PAVE MARKING-THERMO STOP BAR-24IN (REVISED 2-21-2022) | 390.00 | LF | | \$ | |
|)215 | 06569 | PAVE MARKING-THERMO CROSS-HATCH (ADDED 2-21-2022) | 535.00 | SQFT | | \$ | |
| 0220 | 06574 | PAVE MARKING-THERMO CURV ARROW (REVISED 2-21-2022) | 17.00 | EACH | | \$ | |
| 230 | 06575 | PAVE MARKING-THERMO COMB ARROW (REVISED 2-21-2022) | 9.00 | EACH | | \$ | |
| 0240 | 23158ES505 | DETECTABLE WARNINGS (NEW) | 240.00 | SQFT | | \$ | |
| 250 | 24900EC | PVC CONDUIT-1 1/4 IN-SCHEDULE 80 | 100.00 | | | \$ | |
| 0260 | 24963ED | LOOP TEST | 33.00 | EACH | | \$ | |
| 270 | 24970EC | ASPHALT MATERIAL FOR TACK NON- TRACKING | 10.00 | TON | | \$ | |
| | | | | | | | |

Section: 0002 - DEMOBILIZATION

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | | NIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|----------------|----------|---|-----|-----------|----|--------|
| 0280 | 02569 | | DEMOBILIZATION | 1.00 |) | L | S | \$ | |