



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Acting Secretary

June 18, 2010

CALL NO. 316  
CONTRACT ID NO. 102940  
ADDENDUM # 1

Subject: Carroll County, FE02 021 0042 B00043  
Letting June 25, 2010

- (1) Revised - Special Note for Traffic Control - Pages 15-16 of 49
- (2) Revised - Bid Items - Page 49 of 49

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Ryan Griffith".

Ryan Griffith, P.E.  
Director  
Division of Construction Procurement

Enclosures  
RG:ks



An Equal Opportunity Employer M/F/D

## **SPECIAL NOTE FOR TRAFFIC CONTROL ON BRIDGE REPAIR CONTRACTS**

### **I. TRAFFIC CONTROL GENERAL**

Except as provided herein, traffic shall be maintained in accordance with the 2008 Standard Specifications, Section 112. Except for the roadway and traffic control bid items listed, all items of work necessary to maintain and control traffic will be paid at the lump sum bid price to "Maintain and Control Traffic".

Contrary to Section 106.01, traffic control devices used on this project may be new or used in new condition, at the beginning of the work and maintained in like new condition until completion of the work.

### **II. TRAFFIC COORDINATOR**

Furnish a Traffic Coordinator as per Section 112. The Traffic Coordinator shall inspect the project maintenance of traffic, at least three times daily, or as directed by the Engineer, during the Contractor's operations and at any time a lane closure is in place. The personnel shall have access on the project to a radio or telephone to be used in case of emergencies or accidents.

The Traffic Coordinator shall report all incidents throughout the work zone to the Engineer on the project. The Contractor shall furnish the name and telephone number where the Traffic Coordinator can be contacted at all times.

### **III. SIGNS**

Contrary to Section 112.04.02 , signs will be measured once only regardless of how many times set up, moved, or relocated.

The contractor is to install warning signs for wide loads in advance of the bridge under the direction of the Engineer. This shall be paid under the contract price for signs. The Department will not measure installation, maintenance, or removal for payment, and will consider these incidentals to Maintain and Control Traffic. This shall be paid under the contract price for signs.

### **IV. Lane Closures**

Lane closures will only be paid once. If lane closures are left in place continuously over three days it is the contractors responsibility to install striping meeting MUTCD STANDARDS.

Lane closures will not be permitted on these days:

Easter Weekend (Thursday-Sunday)

Memorial Day Weekend (Friday-Monday)

Independence Day Weekend, Labor Day Weekend (Friday-Monday)

Thanksgiving Day Weekend (Thursday-Sunday)

Christmas/New Years (December 24-January 2)

## **VI. PROJECT PHASING & CONSTRUCTION PROCEDURES**

Lane closures are to be in place when during the construction process to move loading to the opposite side of the retrofit being installed. Retrofits are to be placed one at a time. Length of lane closure will be span 6 plus tapers.

Maintain one lane of traffic during construction in accordance with Standard Drawing No. TTC-100 for lane closures. The minimum clear lane width required is 11'-0". Flagging shall be used during peak traffic (6:30am to 8:30am and 3:00pm to 5:00pm).

## **VII. VARIABLE MESSAGE SIGNS**

If deemed necessary by the Engineer, variable message signs will be installed, operated, and maintained by the Department.

## **XIII. TEMPORARY SIGNAL**

Provide, install, and maintain a temporary multi phase traffic signal in accordance with Standard Drawing No. TTC-110-01. The Contractor must provide a 24-hour contact person and number available to maintain the temporary signals as needed. The signal may be used in lieu of flagging for all hours other than those mentioned in paragraph VI.

CONTRACT ID: 102940  
COUNTY: CARROLL  
PROPOSAL: FE02 021 0042 B00043

PAGE: 1  
LETTING: 06/25/10  
CALL NO: 316

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 BRIDGE						
0010	02014	BARRICADE-TYPE III	4.000	EACH		
0020	02562	SIGNS (REVISED: 6-18-10)	300.000	SQFT		
0030	02650	MAINTAIN & CONTROL TRAFFIC	( 1.00)	LS		
0040	02653	LANE CLOSURE	2.000	EACH		
0050	02654	TRUCK MOUNTED ATTENUATOR	1.000	EACH		
0060	04935	TEMP SIGNAL (ADDED: 6-18-10)	( 1.00)	LS		
0070	06550	PAVE STRIPING-TEMP REM TAPE-W (ADDED: 6-18-10)	900.000	LF		
0080	06551	PAVE STRIPING-TEMP REM TAPE-Y (ADDED: 6-18-10)	2,000.000	LF		
0090	23290EC	GUSSET PLATE RETROFIT INSIDE	2.000	EACH		
0100	23290EC	GUSSET PLATE RETROFIT OUTSIDE	2.000	EACH		
SECTION 0002 DEMOBILIZATION & MOBILIZATION						
0110	02568	MOBILIZATION (NO MORE THAN 5%)		LUMP		
0120	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				