



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

May 17, 2011

CALL NO. 317
CONTRACT ID NO. 112922
ADDENDUM # 2

Subject: Hopkins County, FE02 054 9001 B00144
Letting May 20, 2011

- (1) Revised - Traffic Control Plan - Page 48 of 106
- (2) Revised - Bid Items - Pages 105-106 of 106

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

V. PROJECT PHASING & CONSTRUCTION PROCEDURES

The Contractor shall maintain one lane of traffic on the Parkway at all times in accordance with Standard Drawing No. TTC-120 and the attached detail drawings. The clear lane width required is:

<u>Structure</u>	<u>Clear Lane Width</u>
054B00144L	<u>12</u> feet
054B00144R	<u>12</u> feet

The Contractor shall phase the work so that the joint between concrete pours is located on the centerline of the Parkway.

Parkway lane closures will not be permitted on these days:

Easter Weekend (Thursday-Sunday)

Memorial Day Weekend (Friday-Monday)

Independence Day, when July 4th is on Tuesday, Wednesday, or Thursday; or

Independence Day Weekend, when July 4th is on Monday (Saturday-Monday) or Friday (Friday-Sunday)

Labor Day Weekend (Friday-Monday)

VI. BARRIER WALL

Payment of the contract unit price per linear foot for "CONCRETE BARRIER WALL TYPE 9T" shall be full compensation for furnishing, installing, maintaining, adjusting alignment as needed, removing the barrier when no longer needed, and all incidental items necessary to complete the work.

Provide one side mounted barrier wall delineator per each section of barrier. See Standard Drawing RBM-020 for types. No direct payment allowed for delineators.

VII. CRASH CUSHION / END TREATMENTS

To the satisfaction of the Engineer extend Barrier wall out of the clear zone. If Barrier wall is not extended out of the clear zone to the satisfaction of the engineer provide crash cushions / end treatments for the barrier wall.

Provide Barrier end treatments that comply with NCHRP 350 LEVEL 3.

CONTRACT ID: 112922
COUNTY: HOPKINS
PROPOSAL: FE02 054 9001 B00144PAGE: 1
LETTING: 05/20/11
CALL NO: 317

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
SECTION 0001 BRIDGE					
0010	00071	CRUSHED AGGREGATE SIZE NO 57	37.000 TON		
0020	02003	RELOCATE TEMP CONC BARRIER	1,660.000 LF		
0030	24094EC	PARTIAL DEPTH PATCHING (REVISED: 5-17-11)	72.600 CUYD		
0040	02562	SIGNS	298.000 SQFT		
0050	02650	MAINTAIN & CONTROL TRAFFIC B00144L	(1.00) LS		
0060	02650	MAINTAIN & CONTROL TRAFFIC B00144R	(1.00) LS		
0070	02653	LANE CLOSURE	4.000 EACH		
0080	03171	CONCRETE BARRIER WALL TYPE 9T	1,660.000 LF		
0090	03295	EXPAN JOINT REPLACE 2 IN	166.800 LF		
0100	03298	EXPAN JOINT REPLACE 4 IN	83.000 LF		
0110	03299	ARMORED EDGE FOR CONCRETE	166.800 LF		
0120	03304	BRIDGE OVERLAY APPROACH PAVEMENT	666.000 SQYD		
0130	06515	PAVE STRIPING-PERM PAINT-6 IN	2,552.000 LF		
0140	06549	PAVE STRIPING-TEMP REM TAPE-B	1,300.000 LF		
0150	06550	PAVE STRIPING-TEMP REM TAPE-W	4,400.000 LF		
0160	06551	PAVE STRIPING-TEMP REM TAPE-Y	4,400.000 LF		
0170	08100	CONCRETE-CLASS A	5.000 CUYD		
0180	08150	STEEL REINFORCEMENT	800.000 LB		
0190	08504	EPOXY SAND SLURRY	232.000 SQYD		
0200	08510	REM EPOXY BIT FOREIGN OVERLAY	2,986.000 SQYD		

CONTRACT ID: 112922
COUNTY: HOPKINS
PROPOSAL: FE02 054 9001 B00144

PAGE: 2
LETTING: 05/20/11
CALL NO: 317

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
0210	08526	CONC CLASS M FULL DEPTH PATCH	4.000 CUYD		
0220	08534	CONCRETE OVERLAY-LATEX	124.400 CUYD		
0230	08549	BLAST CLEANING	3,218.000 SQYD		
0240	23032EN	BRIDGE BARRIER RETROFIT APPLIES TO B00144L (ADDED: 5-9-11)	928.000 LF		
SECTION 0002 DEMOBILIZATION					
0250	02569	DEMOBILIZATION (AT LEAST 1.5%)	LUMP		
		TOTAL BID			