



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

May 17, 2011

CALL NO. 321  
CONTRACT ID NO. 112939  
ADDENDUM # 1

Subject: Knox County, FE02 061 0930 B00036  
Letting May 20, 2011

(1) Revised - Traffic Control - Page 23 of 70

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:ks  
Enclosures



An Equal Opportunity Employer M/F/D

## V. PROJECT PHASING & CONSTRUCTION PROCEDURES

**For either alternate, all work must be completed between May 24, 2011 and August 1, 2011 and no work shall be performed during Independence Day holiday.**

### **ALTERNATE #1 –**

Contractor shall complete all work in 105 hours beginning on a Friday at 8:00pm and ending on the following Wednesday at 5:00am.

The bridge shall be shut down completely during this time and traffic shall be detoured according to the attached Detour Plan. Contractor shall give Engineer 14 day written notice of the chosen 105 hour time period.

### **ALTERNATE #2**

Contractor shall complete all work in 20 calendar days, closing the bridge from 10:00pm-5:30am each night, beginning on a Friday at 8:00pm and ending on a Thursday at 8:00pm. In addition, the bridge may be closed one day **per lane** (24 hours maximum for each lane) during the Friday night 8:00 PM through Monday morning 5:30am time period for overlay pour. This closure will be to accommodate extra width of finishing machine encroaching into adjacent lane during set up, dry run, and actual pour. Otherwise, maintain one lane of traffic during construction in accordance with Standard Drawing No. TTC-110 for lane closures, and the attached detail drawing. The minimum clear lane width required is 9'-0". Channelization devices must be placed in work area to maintain 9'-0" clear lane width. At the direction of the Engineer, steel plates shall be secured over open areas of construction and uncured concrete pours (joint areas and full depth areas).

If the Contractor chooses to work during hours other than 10:00pm-5:30am each night, construction activities shall be limited to a 6'-6" wide zone as measured from the curb of the work zone, thus leaving an additional 2'-6" wide clear zone in addition to the 9'-0" clear zone specified above. This additional 2'-6" wide clear zone shall be maintained throughout the work area and buffer area. Each approach has guardrail on either side of the roadway, thus vehicles and equipment greater than 6'6" in width will not be allowed.

Traffic shall be detoured according to the attached Detour Plan. Each morning at 5:30am, all detour signs shall be covered and the temporary signal shall be initialized. Contractor shall give Engineer 14 day written notice of the chosen 20 calendar day time period.

## VI. TEMPORARY SIGNAL (ALTERNATE 2)

Provide, install, and maintain a temporary two phase traffic signal. The Contractor must provide a 24-hour contact person and number available to maintain the temporary signals as needed.