



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

March 12, 2024

CALL NO. 322
CONTRACT ID NO. 242114
ADDENDUM # 2

Subject: Carroll County, CPTL 021 8013 000-003
Letting March 21, 2024

- (1) Added - Special Note - Page 11 of 52
- (2) Added - Proposal Bid Items - Page 52 of 52

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

CPTL 021 8013 000-003 Intermediate Pipe Anchor



Prior to Leveling and Wedging and placing Asphalt Surface, excavate and expose the disjointed cross drain pipe. Protect pipe from concrete infiltration. Modify pipe anchor shown on Standard Drawing RDX-060-04 and obtain the Engineer's approval. Place Class A Concrete. Backfill the excavated hole with DGA and top with 3" Class 2 Asphalt Base 0.75D PG64-22. Seal the area with Leveling and Wedging. Do this work as one of the Contractor's first operations in order to allow further compaction by traffic. Prior to placing the new asphalt surface, level and wedge any settlement of the repair areas.

Accept payment at the Contract unit price for CONCRETE-CLASS A (FOR INTERMEDIATE PIPE ANCHOR) as full compensation for all materials, labor, equipment, and incidentals for excavation, modifying Standard Drawing RDX-060, forms, pipe protection, Concrete-Class A, DGA backfill, and asphalt base for pavement restoration.

PROPOSAL BID ITEMS

Report Date 3/12/24

Section: 0001 - RESURFACING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	500.00	TON		\$	
0020	00190		LEVELING & WEDGING PG64-22	250.00	TON		\$	
0030	00301		CL2 ASPH SURF 0.38D PG64-22	2,500.00	TON		\$	
0035	02237		DITCHING (ADDED 3/12/2024)	250.00	LF		\$	
0040	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0050	02483		CHANNEL LINING CLASS II	100.00	TON		\$	
0060	02562		TEMPORARY SIGNS	300.00	SQFT		\$	
0065	02585		EDGE KEY ADDED (3-8-24)	300.00	LF		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0080	03240		BASE FAILURE REPAIR	200.00	SQYD		\$	
0090	06510		PAVE STRIPING-TEMP PAINT-4 IN	5,000.00	LF		\$	
0100	06514		PAVE STRIPING-PERM PAINT-4 IN	10,700.00	LF		\$	
0110	06568		PAVE MARKING-THERMO STOP BAR-24IN	176.00	LF		\$	
0120	06573		PAVE MARKING-THERMO STR ARROW	8.00	EACH		\$	
0130	08100		CONCRETE-CLASS A (FOR INTERMEDIATE PIPE ANCHOR)	2.00	CUYD		\$	
0140	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	15.00	TON		\$	

Section: 0002 - GUARDRAIL

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0150	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	7.00	EACH		\$	
0160	20060ES719		GUARDRAIL STEEL W BEAM-S FACE CR	300.00	LF		\$	
0170	20061ES719		G/R END TREATMENT TY 7 CR	2.00	EACH		\$	

Section: 0003 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0180	02569		DEMOBILIZATION	1.00	LS		\$	