



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

April 21, 2011

CALL NO. 328
CONTRACT ID NO. 112929
ADDENDUM # 1

Subject: Bullitt County, FE02 015 0061 B00016N
Letting April 29, 2011

- (1) Revised - Project Identification & Description - Page 4 of 90
- (2) Revised - Special Note - Page 20 of 90
- (3) Revised - Bid Items - Pages 89-90 of 90

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

CONTRACT ID - 112929

ADMINISTRATIVE DISTRICT - 05

PROJECT(S) IDENTIFICATION AND DESCRIPTION:

COUNTY - BULLITT PCN - MB01500611101
FE02 015 0061 B00016N
PRESTON HIGHWAY (KY 61) BRIDGE OVER SALT RIVER (MP 14.083). BRIDGE DECK RESTORATION &
WATERPROOFING.
GEOGRAPHIC COORDINATES LATITUDE 37^59'05" LONGITUDE 85^43'02"

COMPLETION DATE(S):

COMPLETION DATE - November 15, 2011
APPLIES TO ENTIRE CONTRACT

45 WORKING DAYS
APPLIES TO B00016N

**SPECIAL NOTE FOR CONTRACT COMPLETION DATE AND
LIQUIDATED DAMAGES ON BRIDGE REPAIR CONTRACTS**

- I. COMPLETION DATE.** The Contractor has the option of selecting the starting date for this Contract. Once selected, notify the Department in writing of the date selected at least two weeks prior to beginning work. All work is to be completed in the 2011 construction season by November 15, 2011. An allotted number of Working days are assigned to this structure in this contract as shown below.

<u>STRUCTURE</u>	<u>NUMBER OF WORKING DAYS</u>
B00016N	45

Contrary to Section 108.07.02, the Engineer will begin charging working days and hours for a structure on the day and the hour the Contractor starts work (Traffic inhibiting work) or sets up traffic control on the structure, and count will continue until, at minimum, a phase of the work is completed, accepted and Traffic Control Devices are removed.

- II. LIQUIDATED DAMAGES.** In addition to the liquidated damages specified in the Transportation Cabinet, Department of Highway's 2008 Standard Specifications for Road and Bridge Construction, Section 108.09, liquidated damages in the amount of \$1500 per day will be assessed for each day, or fraction of a day, that a lane closure remains in place when either the allotted number of working days or the November 15, 2011 date is exceeded. All construction must be completed in accordance with the weather limitations specified in Section 606 and/or Section 601 as applicable. No extension of Contract time will be granted due to inclement weather or temperature limitations that occur due to starting work on the Contract late in the construction season. Liquidated damages of \$5,000 per hour will be assessed if all traffic lanes closed for more than 1 hour.

CONTRACT ID: 112929
COUNTY: BULLITT
PROPOSAL: FE02 015 0061 B00016N

PAGE: 1
LETTING: 04/29/11
CALL NO: 328

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 BRIDGE						
0010	02004	RELOCATE WATER-FILLED BARRIERS	960.000	LF		
0020	02005	WATER-FILLED BARRIERS	960.000	LF		
0030	02562	SIGNS	149.000	SQFT		
0040	02650	MAINTAIN & CONTROL TRAFFIC	(1.00)	LS		
0050	02653	LANE CLOSURE	2.000	EACH		
0060	03298	EXPAN JOINT REPLACE 4 IN	93.200	LF		
0070	03299	ARMORED EDGE FOR CONCRETE	62.100	LF		
0080	03300	ELIMINATE TRANSVERSE JOINT	31.050	LF		
0090	03303	REPAIR CONCRETE SIDEWALK	730.000	SQYD		
0100	03304	BRIDGE OVERLAY APPROACH PAVEMENT	905.000	SQYD		
0110	04934	TEMP SIGNAL MULTI PHASE	1.000	EACH		
0120	06514	PAVE STRIPING-PERM PAINT-4 IN	600.000	LF		
0130	06530	PAVE STRIPING REMOVAL-4 IN	580.000	LF		
0140	06549	PAVE STRIPING-TEMP REM TAPE-B	560.000	LF		
0150	06550	PAVE STRIPING-TEMP REM TAPE-W	2,500.000	LF		
0160	06551	PAVE STRIPING-TEMP REM TAPE-Y	2,000.000	LF		
0170	06554	PAVE STRIPING-DUR TY 1-4 IN W	1,160.000	LF		
0180	06555	PAVE STRIPING-DUR TY 1-4 IN Y	1,160.000	LF		
0190	08150	STEEL REINFORCEMENT	1,765.800	LB		
0200	08504	EPOXY SAND SLURRY	665.900	SQYD		

CONTRACT ID: 112929
COUNTY: BULLITT
PROPOSAL: FE02 015 0061 B00016N

PAGE: 2
LETTING: 04/29/11
CALL NO: 328

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0210	08510	REM EPOXY BIT FOREIGN OVERLAY	1,933.000	SQYD		
0220	08526	CONC CLASS M FULL DEPTH PATCH	38.000	CUYD		
0230	08534	CONCRETE OVERLAY-LATEX	139.600	CUYD		
0240	08549	BLAST CLEANING	2,599.000	SQYD		
0241	22146EN	CONCRETE PATCHING REPAIR (ADDED: 4-21-11)	240.000	SQFT		
0250	24094EC	PARTIAL DEPTH PATCHING	50.000	CUYD		
SECTION 0002 DEMOBILIZATION						
0260	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				