



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

August 7, 2025

CALL NO. 328
CONTRACT ID NO. 251320
ADDENDUM # 1

Subject: Kenton County, FD06 059 0536 002-005
Letting August 21, 2025

(1) Revised - Proposal Bid Items - Pages 223-228 of 228

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

251320

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	32,059.00	TON		\$	
0020	00013		LIME STABILIZED ROADBED	74,312.00	SQYD		\$	
0030	00014		LIME	1,404.00	TON		\$	
0040	00018		DRAINAGE BLANKET-TYPE II-ASPH	14,862.00	TON		\$	
0050	00020		TRAFFIC BOUND BASE	17.00	TON		\$	
0060	00100		ASPHALT SEAL AGGREGATE	24.00	TON		\$	
0070	00103		ASPHALT SEAL COAT	3.00	TON		\$	
0080	00190		LEVELING & WEDGING PG64-22	83.00	TON		\$	
0090	00214		CL3 ASPH BASE 1.00D PG64-22	24,436.00	TON		\$	
0100	00216		CL3 ASPH BASE 1.00D PG76-22	1,993.00	TON		\$	
0110	00221		CL2 ASPH BASE 0.75D PG64-22	3,085.00	TON		\$	
0120	00301		CL2 ASPH SURF 0.38D PG64-22	1,784.00	TON		\$	
0130	00356		ASPHALT MATERIAL FOR TACK	82.00	TON		\$	
0140	00358		ASPHALT CURING SEAL	133.00	TON		\$	
0150	00387		CL3 ASPH SURF 0.38B PG76-22	997.00	TON		\$	
0160	00388		CL3 ASPH SURF 0.38B PG64-22	6,372.00	TON		\$	
0170	02084		JPC PAVEMENT-8 IN	1,487.00	SQYD		\$	
0180	02677		ASPHALT PAVE MILLING & TEXTURING	1,594.00	TON		\$	
0190	02702		SAND FOR BLOTTER	186.00	TON		\$	
0200	23379EC		STAMPED CONCRETE	952.00	SQYD		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0210	00078		CRUSHED AGGREGATE SIZE NO 2	12.00	TON		\$	
0220	00440		ENTRANCE PIPE-15 IN	45.00	LF		\$	
0230	01000		PERFORATED PIPE-4 IN	19,588.00	LF		\$	
0240	01001		PERFORATED PIPE-6 IN	5,899.00	LF		\$	
0250	01010		NON-PERFORATED PIPE-4 IN	120.00	LF		\$	
0260	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM	1.00	LS		\$	
0270	01020		PERF PIPE HEADWALL TY 1-4 IN	9.00	EACH		\$	
0280	01028		PERF PIPE HEADWALL TY 3-4 IN	2.00	EACH		\$	
0290	01032		PERF PIPE HEADWALL TY 4-4 IN	1.00	EACH		\$	
0300	01310		REMOVE PIPE	190.00	LF		\$	
0310	01740		CORED HOLE DRAINAGE BOX CON-4 IN	168.00	EACH		\$	
0320	01741		CORED HOLE DRAINAGE BOX CON-6 IN	19.00	EACH		\$	
0330	01810		STANDARD CURB AND GUTTER	37,382.00	LF		\$	
0340	01825		ISLAND CURB AND GUTTER	3,378.00	LF		\$	
0350	01830		STANDARD INTEGRAL CURB	680.00	LF		\$	
0360	01845		ISLAND INTEGRAL CURB	303.00	LF		\$	
0370	01875		STANDARD HEADER CURB	384.00	LF		\$	
0380	01891		ISLAND HEADER CURB TYPE 2	790.00	LF		\$	
0390	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	89.00	EACH		\$	

251320

PROPOSAL BID ITEMS

Report Date 8/7/25

Page 2 of 6

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	02001		CURB TO BARRIER WALL TRANS	2.00	EACH		\$	
0410	02014		BARRICADE-TYPE III	5.00	EACH		\$	
0420	02015		CEMENT CONCRETE ISLAND	196.00	SQYD		\$	
0430	02091		REMOVE PAVEMENT	1,173.00	SQYD		\$	
0440	02101		CEM CONC ENT PAVEMENT-8 IN	188.00	SQYD		\$	
0450	02157		PAVED DITCH TYPE 1	6.00	SQYD		\$	
0460	02159		TEMP DITCH	5,690.00	LF		\$	
0470	02160		CLEAN TEMP DITCH	2,845.00	LF		\$	
0480	02200		ROADWAY EXCAVATION	428,430.00	CUYD		\$	
0490	02242		WATER	1,000.00	MGAL		\$	
0500	02351		GUARDRAIL-STEEL W BEAM-S FACE	5,100.00	LF		\$	
0510	02367		GUARDRAIL END TREATMENT TYPE 1	7.00	EACH		\$	
0520	02369		GUARDRAIL END TREATMENT TYPE 2A	8.00	EACH		\$	
0530	02373		GUARDRAIL END TREATMENT TYPE 3	1.00	EACH		\$	
0540	02381		REMOVE GUARDRAIL	200.00	LF		\$	
0550	02396		REMOVE GUARDRAIL END TREATMENT	2.00	EACH		\$	
0560	02429		RIGHT-OF-WAY MONUMENT TYPE 1	113.00	EACH		\$	
0570	02432		WITNESS POST	113.00	EACH		\$	
0580	02482		CHANNEL LINING CLASS IA	517.00	TON		\$	
0590	02483		CHANNEL LINING CLASS II	1,967.00	TON		\$	
0600	02484		CHANNEL LINING CLASS III	368.00	TON		\$	
0610	02545		CLEARING AND GRUBBING 68.2 ACRES	1.00	LS		\$	
0620	02562		TEMPORARY SIGNS	300.00	SQFT		\$	
0630	02585		EDGE KEY	347.00	LF		\$	
0640	02603		FABRIC-GEOTEXTILE CLASS 2	14,775.00	SQYD		\$	
0650	02625		REMOVE HEADWALL	2.00	EACH		\$	
0660	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0670	02651		DIVERSIONS (BY-PASS DETOURS) (PHASE B)	1.00	LS		\$	
0680	02651		DIVERSIONS (BY-PASS DETOURS) (PHASE C)	1.00	LS		\$	
0690	02671		PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH		\$	
0700	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0710	02690		SAFELOADING (REVISED 8-7-25)	275.00	CUYD		\$	
0720	02701		TEMP SILT FENCE	5,690.00	LF		\$	
0730	02703		SILT TRAP TYPE A	57.00	EACH		\$	
0740	02704		SILT TRAP TYPE B	57.00	EACH		\$	
0750	02705		SILT TRAP TYPE C	57.00	EACH		\$	
0760	02706		CLEAN SILT TRAP TYPE A	57.00	EACH		\$	
0770	02707		CLEAN SILT TRAP TYPE B	57.00	EACH		\$	
0780	02708		CLEAN SILT TRAP TYPE C	57.00	EACH		\$	
0790	02720		SIDEWALK-4 IN CONCRETE	420.00	SQYD		\$	
0800	02726		STAKING	1.00	LS		\$	
0810	02775		ARROW PANEL	4.00	EACH		\$	
0820	05950		EROSION CONTROL BLANKET	8,273.00	SQYD		\$	
0830	05952		TEMP MULCH	183,662.00	SQYD		\$	
0840	05953		TEMP SEEDING AND PROTECTION	137,746.00	SQYD		\$	
0850	05963		INITIAL FERTILIZER	6.30	TON		\$	
0860	05964		MAINTENANCE FERTILIZER	10.40	TON		\$	

251320

PROPOSAL BID ITEMS

Page 3 of 6

Report Date 8/7/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0870	05985		SEEDING AND PROTECTION	192,220.00	SQYD		\$	
0880	05990		SODDING	27,964.00	SQYD		\$	
0890	05992		AGRICULTURAL LIMESTONE	170.80	TON		\$	
0900	06406		SBM ALUM SHEET SIGNS .080 IN	1,143.00	SQFT		\$	
0910	06407		SBM ALUM SHEET SIGNS .125 IN	254.00	SQFT		\$	
0920	06410		STEEL POST TYPE 1	1,766.00	LF		\$	
0930	06490		CLASS A CONCRETE FOR SIGNS	34.76	CUYD		\$	
0940	06510		PAVE STRIPING-TEMP PAINT-4 IN	68,521.00	LF		\$	
0950	06542		PAVE STRIPING-THERMO-6 IN W	50,040.00	LF		\$	
0960	06543		PAVE STRIPING-THERMO-6 IN Y	45,340.00	LF		\$	
0970	06546		PAVE STRIPING-THERMO-12 IN W	98.00	LF		\$	
0980	06556		PAVE STRIPING-DUR TY 1-6 IN W	850.00	LF		\$	
0990	06557		PAVE STRIPING-DUR TY 1-6 IN Y	680.00	LF		\$	
1000	06566		PAVE MARKING-THERMO X-WALK-12 IN	2,788.00	LF		\$	
1010	06568		PAVE MARKING-THERMO STOP BAR-24IN	355.00	LF		\$	
1020	06573		PAVE MARKING-THERMO STR ARROW	6.00	EACH		\$	
1030	06574		PAVE MARKING-THERMO CURV ARROW	20.00	EACH		\$	
1040	06575		PAVE MARKING-THERMO COMB ARROW	8.00	EACH		\$	
1050	06610		INLAID PAVEMENT MARKER-MW	320.00	EACH		\$	
1060	06611		INLAID PAVEMENT MARKER-MY	458.00	EACH		\$	
1070	06612		INLAID PAVEMENT MARKER-BY	290.00	EACH		\$	
1080	08100		CONCRETE-CLASS A	7.68	CUYD		\$	
1090	08150		STEEL REINFORCEMENT	326.00	LB		\$	
1100	08902		CRASH CUSHION TY 6 CLASS B TL3	2.00	EACH		\$	
1110	10020NS		FUEL ADJUSTMENT	176,598.00	DOLL	\$1.00	\$	\$176,598.00
1120	10030NS		ASPHALT ADJUSTMENT	152,431.00	DOLL	\$1.00	\$	\$152,431.00
1130	20071EC		JOINT ADHESIVE	30,800.00	LF		\$	
1140	20191ED		OBJECT MARKER TY 3	14.00	EACH		\$	
1150	21289ED		LONGITUDINAL EDGE KEY	800.00	LF		\$	
1160	21373ND		REMOVE SIGN	2.00	EACH		\$	
1170	21596ND		GMSS TYPE D	158.00	EACH		\$	
1180	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	110.00	LF		\$	
1190	23158ES505		DETECTABLE WARNINGS	1,189.00	SQFT		\$	
1200	24114EC		PAVE MARK-THERMO-YIELD	11.00	EACH		\$	
1210	24115EC		ROUNDBOUT ARROW	16.00	EACH		\$	
1220	24631EC		BARCODE SIGN INVENTORY	245.00	EACH		\$	
1230	24679ED		PAVE MARK THERMO CHEVRON	185.00	SQFT		\$	
1240	24814EC		PIPELINE INSPECTION	10,000.00	LF		\$	
1250	24969ED		LONGITUDINAL SAW CUT	1,193.00	LF		\$	
1260	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1270	00462		CULVERT PIPE-18 IN	377.00	LF		\$	
1280	00464		CULVERT PIPE-24 IN	754.00	LF		\$	
1290	00468		CULVERT PIPE-36 IN	296.00	LF		\$	
1300	00492		CULVERT PIPE-24 IN EQUIV	45.00	LF		\$	

251320

PROPOSAL BID ITEMS

Report Date 8/7/25

Page 4 of 6

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1310	00498		CULVERT PIPE-42 IN EQUIV	45.00	LF		\$	
1320	00521		STORM SEWER PIPE-15 IN	2,396.00	LF		\$	
1330	00522		STORM SEWER PIPE-18 IN	7,131.00	LF		\$	
1340	00524		STORM SEWER PIPE-24 IN	158.00	LF		\$	
1350	01202		PIPE CULVERT HEADWALL-15 IN	3.00	EACH		\$	
1360	01204		PIPE CULVERT HEADWALL-18 IN	19.00	EACH		\$	
1370	01208		PIPE CULVERT HEADWALL-24 IN	10.00	EACH		\$	
1380	01212		PIPE CULVERT HEADWALL-36 IN	2.00	EACH		\$	
1390	01215		PIPE CULVERT HEADWALL-42 IN EQUIV	2.00	EACH		\$	
1400	01456		CURB BOX INLET TYPE A	95.00	EACH		\$	
1410	01480		CURB BOX INLET TYPE B	1.00	EACH		\$	
1420	01490		DROP BOX INLET TYPE 1	5.00	EACH		\$	
1430	01559		DROP BOX INLET TYPE 13G	16.00	EACH		\$	
1440	01568		DROP BOX INLET TYPE 13S	1.00	EACH		\$	
1450	01756		MANHOLE TYPE A	7.00	EACH		\$	

Section: 0004 - BRIDGE - OVER BUSHY FORK AND INDENPENDENCE ROAD

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1460	02231		STRUCTURE GRANULAR BACKFILL	827.00	CUYD		\$	
1470	03299		ARMORED EDGE FOR CONCRETE	157.10	LF		\$	
1480	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1490	08020		CRUSHED AGGREGATE SLOPE PROT	3,898.00	TON		\$	
1500	08033		TEST PILES	58.00	LF		\$	
1510	08046		PILES-STEEL HP12X53	723.00	LF		\$	
1520	08094		PILE POINTS-12 IN	30.00	EACH		\$	
1530	08100		CONCRETE-CLASS A	582.50	CUYD		\$	
1540	08104		CONCRETE-CLASS AA	1,151.30	CUYD		\$	
1550	08150		STEEL REINFORCEMENT	89,362.00	LB		\$	
1560	08151		STEEL REINFORCEMENT-EPOXY COATED	342,788.00	LB		\$	
1570	08637		PRECAST PC I BEAM TYPE 7	2,694.70	LF		\$	
1580	20745ED		ROCK SOUNDINGS	62.40	LF		\$	
1590	20746ED		ROCK CORINGS	236.50	LF		\$	
1600	23000EX		DRILLED SHAFT-66 IN (ROCK)	88.00	LF		\$	
1610	23249EC		DRILLED SHAFT-72 IN COMMON	57.00	LF		\$	
1620	23378EC		CONCRETE SEALING	54,483.00	SQFT		\$	
1630	23813EC		DECK DRAIN	12.00	EACH		\$	
1640	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	680.00	LF		\$	
1650	25029ED		STEEL HANDRAIL	1,342.00	LF		\$	
1660	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0005 - SEWER

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1670	01314		PLUG PIPE	1.00	EACH		\$	
1680	15092		S MANHOLE	3.00	EACH		\$	

251320

PROPOSAL BID ITEMS

Report Date 8/7/25

Page 5 of 6

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1690	15093		S MANHOLE ABANDON/REMOVE	2.00	EACH		\$	
1700	15094		S MANHOLE ADJUST TO GRADE	1.00	EACH		\$	
1710	15096		S MANHOLE CASTING WATERTIGHT	3.00	EACH		\$	
1720	15099		S MANHOLE TAP EXISTING	1.00	EACH		\$	
1730	15114		S PIPE PVC 12 INCH	180.00	LF		\$	

Section: 0006 - SIGNAL

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1740	04780		FUSED CONNECTOR KIT	24.00	EACH		\$	
1750	04820		TRENCHING AND BACKFILLING	170.00	LF		\$	
1760	04844		CABLE-NO. 14/5C	1,030.00	LF		\$	
1770	04845		CABLE-NO. 14/7C	3,960.00	LF		\$	
1780	04885		MESSENGER-10800 LB	855.00	LF		\$	
1790	04932		INSTALL STEEL STRAIN POLE	8.00	EACH		\$	
1800	20093NS835		INSTALL PEDESTRIAN HEAD-LED	16.00	EACH		\$	
1810	20188NS835		INSTALL LED SIGNAL-3 SECTION	20.00	EACH		\$	
1820	20390NS835		INSTALL COORDINATING UNIT	2.00	EACH		\$	
1830	21743NN		INSTALL PEDESTRIAN DETECTOR	16.00	EACH		\$	
1840	23157EN		TRAFFIC SIGNAL POLE BASE	32.20	CUYD		\$	
1850	23222EC		INSTALL SIGNAL PEDESTAL	8.00	EACH		\$	
1860	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	145.00	LF		\$	
1870	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	65.00	LF		\$	
1880	24908EC		INSTALL SIGNAL CONTROLLER-TY ATC	2.00	EACH		\$	
1890	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	8.00	EACH		\$	

Section: 0007 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1900	04701		POLE 40 FT MTG HT	20.00	EACH		\$	
1910	04720		BRACKET 4 FT	6.00	EACH		\$	
1920	04723		BRACKET 10 FT	10.00	EACH		\$	
1930	04725		BRACKET 15 FT	4.00	EACH		\$	
1940	04740		POLE BASE	20.00	EACH		\$	
1950	04750		TRANSFORMER BASE	20.00	EACH		\$	
1960	04761		LIGHTING CONTROL EQUIPMENT	2.00	EACH		\$	
1970	04780		FUSED CONNECTOR KIT	40.00	EACH		\$	
1980	04797		CONDUIT-3 IN	865.00	LF		\$	
1990	04820		TRENCHING AND BACKFILLING	2,810.00	LF		\$	
2000	04832		WIRE-NO. 12	3,560.00	LF		\$	
2010	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	5.00	EACH		\$	
2020	21543EN		BORE AND JACK CONDUIT	35.00	LF		\$	
2030	24589ED		LED LUMINAIRE	20.00	EACH		\$	
2040	24851EC		CABLE-NO. 10/3C DUCTED	3,150.00	LF		\$	

251320

PROPOSAL BID ITEMS

Report Date 8/7/25

Page 6 of 6

Section: 0008 - WATER

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2050	14019		W FIRE HYDRANT ASSEMBLY	4.00	EACH		\$	
2060	14020		W FIRE HYDRANT RELOCATE	5.00	EACH		\$	
2070	14030		W METER RELOCATE	3.00	EACH		\$	
2080	14037		W PIPE DUCTILE IRON 08 INCH	445.00	LF		\$	
2090	14039		W PIPE DUCTILE IRON 12 INCH	3,790.00	LF		\$	
2100	14041		W PIPE DUCTILE IRON 20 INCH	1,670.00	LF		\$	
2110	14050		W PIPE DCTL IRON RSTRND JOINT 12 IN	630.00	LF		\$	
2120	14052		W PIPE DCTL IRON RSTRND JOINT 20 IN	150.00	LF		\$	
2130	14095		W TIE-IN 08 INCH	4.00	EACH		\$	
2140	14097		W TIE-IN 12 INCH	8.00	EACH		\$	
2150	14099		W TIE-IN 20 INCH	4.00	EACH		\$	
2160	14106		W VALVE 08 INCH	3.00	EACH		\$	
2170	14108		W VALVE 12 INCH	14.00	EACH		\$	
2180	14111		W VALVE 24 INCH	2.00	EACH		\$	
2190	14120		W VALVE CUT-IN 12 INCH	2.00	EACH		\$	
2200	14149		W SERV COPPER SHORT SIDE 1 IN	3.00	EACH		\$	

Section: 0009 - DEMOBILIZATION AND MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2210	02568		MOBILIZATION	1.00	LS		\$	
2220	02569		DEMOBILIZATION	1.00	LS		\$	