



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

November 25, 2020

CALL NO. 329
CONTRACT ID NO. 202159
ADDENDUM # 1

Subject: WAYNE COUNTY, FD05 116 0090 012-020
Letting December 11, 2020

- (1) Revised - Page 4 of 64
- (2) Revised - Surface Areas - Page 9 of 64
- (3) Revised - Project Map - Page 44 of 64
- (4) Revised - Milling Summary - Page 45 of 64
- (5) Revised - Pavement Marking Summary - Page 46 of 64
- (6) Revised - Delete Pages 48-49 of 64
- (7) Revised - Proposal Bid Items - Pages 64-64(a) of 64

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

ADMINISTRATIVE DISTRICT - 08

CONTRACT ID - 202159
FD05 116 0090 012-018
COUNTY - WAYNE
PCN - MP11600902002
FD05 116 0090 012-018

MONTICELLO TO BRONSTON ROAD (KY 90) (MP 12.900) BEGINNING 0.179 MILES EAST OF KY 1275 EXTENDING
EAST TO OLD MILL SPRINGS ROAD (MP 17.691), A DISTANCE OF 04.79 MILES.PAVEMENT (WITH ALTERNATES)
GEOGRAPHIC COORDINATES LATITUDE 36:53:35.60 LONGITUDE 84:47:54.90

COMPLETION DATE(S):
COMPLETED BY 09/30/2021 APPLIES TO ENTIRE CONTRACT

DEFERRED PAYMENT

The Department will issue a work order with the distinct understanding that payment for any Pay Estimates may be delayed until January 31, 2021.

SURFACING AREAS

The Department estimates the mainline surfacing width to be varied 24-48 feet.

The Department estimates the total mainline area to be surfaced to be 83,678 square yards.

The Department estimates the shoulder width to be varied 1-2 feet on each side.

The Department estimates the total shoulder area to be surfaced to be 5,621 square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

[illegible]

[illegible]

PROPOSAL BID ITEMS

Report Date 11/25/20

Page 1 of 2

Section: 0001 - MICROSURFACE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	21652EN		MICROSURFACING-LEVELING COURSE (REVISED: 11-25-20)	99,825.00	SQYD		\$	
0020	24957EC		MICROSURFACING-SURFACE COURSE - TYPE B (REVISED: 11-25-20)	89,299.00	SQYD		\$	

Section: 0002 - THINLAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0030	00190		LEVELING & WEDGING PG64-22	437.00	TON		\$	
0040	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0050	02677		ASPHALT PAVE MILLING & TEXTURING	15.00	TON		\$	
0060	23307EC		CL3 ASPH SURF NO.4B PG64-22 (REVISED: 11-25-20)	3,690.00	TON		\$	
0070	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING (REVISED: 11-25-20)	28.00	TON		\$	

Section: 0003 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	02562		TEMPORARY SIGNS	800.00	SQFT		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0100	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0110	02697		EDGE LINE RUMBLE STRIPS (REVISED: 11-25-20)	50,000.00	LF		\$	
0120	02775		ARROW PANEL	1.00	EACH		\$	
0130	06510		PAVE STRIPING-TEMP PAINT-4 IN (REVISED: 11-25-20)	35,000.00	LF		\$	
0140	06514		PAVE STRIPING-PERM PAINT-4 IN (REVISED: 11-25-20)	1,000.00	LF		\$	
0150	06542		PAVE STRIPING-THERMO-6 IN W (REVISED: 11-25-20)	54,000.00	LF		\$	
0160	06543		PAVE STRIPING-THERMO-6 IN Y (REVISED: 11-25-20)	22,000.00	LF		\$	
0170	06568		PAVE MARKING-THERMO STOP BAR-24IN (REVISED: 11-25-20)	75.00	LF		\$	
0180	06600		REMOVE PAVEMENT MARKER TYPE V (REVISED: 11-25-20)	515.00	EACH		\$	
0190	20458ES403		CENTERLINE RUMBLE STRIPS (REVISED: 11-25-20)	25,300.00	LF		\$	
0200	23607EC		PAVE MARK THERMO-LANE REDUCTION ARROW	6.00	EACH		\$	

Section: 0004 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
------	----------	-----	-------------	----------	------	-----------	----	--------

PROPOSAL BID ITEMS

Report Date 11/25/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0210	02569		DEMOBILIZATION	1.00	LS		\$	