



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

January 15, 2025

CALL NO. 330
CONTRACT ID NO. 251002
ADDENDUM # 1

Subject: Grayson County, FD06 043 3155 NEWRT
Letting January 23, 2025

- (1) Revised - Notes - Page 494 of 812
- (2) Revised - Proposal Bid Items - Pages 807-812 of 812
- (3) Revised - Plan Sheets: R1, R2K, X38, X39, X40, X41,
X42, X43, X44, X71, X72, X73, R89, R150

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

The Following Contractors are approved for providing construction services for the City of Leitchfield Natural Gas System:

1. Cleary Construction, Tompkinsville, KY
2. Martin Contracting, Richmond, KY
3. Miller Pipeline, Louisville, KY
4. Swartz Pipeline, Olympia, KY

3. INSTALLATION CRITERIA

All natural gas facilities shall be installed to conform to Title 49 of the Code of Federal Regulations, Parts 191 and 192, Transportation of Natural and Other Gas by Pipeline, as promulgated by the United States Department of Transportation and regulated by the Kentucky Public Service Commission.

All materials used for the construction of utility facilities shall be new.

A. Medium Pressure Gas Mains and Appurtenances

- (1) All pipelines and service lines to be operated at less than 60 psi may be polyethylene.
- (2) Minimum depth of bury for gas mains shall be 30 inches, except it shall be 60 inches deep when located on KYTC right-of-way.
- (3) Minimum depth of bury for potable water and sanitary sewer lines shall be 30 inches, except it shall be 42 inches deep when located on KYTC right-of-way.

4. INSPECTION AND TESTING OF MATERIALS

Attention is called to the portions of the specifications requiring various testing of materials.

5. SECOND HAND AND SALVAGED MATERIALS

The use of second-hand and/or salvaged materials will not be permitted.

6. WARRANTY PERIOD

The CONTRACTOR shall return to the site of the work at any time within a period of one year from the date of final acceptance of the work, and shall repair any defect due to faulty workmanship or materials which may occur within this period. This guarantee shall include, but not be limited to, damage done by settlement of backfills, such damage and sinking of fills being considered as defective workmanship.

PROPOSAL BID ITEMS

251002

Report Date 1/15/25

Page 1 of 6

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	46,843.00	TON		\$	
0020	00013		LIME STABILIZED ROADBED	49,911.00	SQYD		\$	
0030	00014		LIME	1,402.00	TON		\$	
0040	00078		CRUSHED AGGREGATE SIZE NO 2	13,182.00	TON		\$	
0050	00100		ASPHALT SEAL AGGREGATE	456.00	TON		\$	
0060	00103		ASPHALT SEAL COAT	63.00	TON		\$	
0070	00190		LEVELING & WEDGING PG64-22	738.00	TON		\$	
0080	00212		CL2 ASPH BASE 1.00D PG64-22	9,893.00	TON		\$	
0090	00216		CL3 ASPH BASE 1.00D PG76-22	635.00	TON		\$	
0100	00221		CL2 ASPH BASE 0.75D PG64-22	6,861.00	TON		\$	
0110	00301		CL2 ASPH SURF 0.38D PG64-22	4,813.00	TON		\$	
0120	00307		CL2 ASPH SURF 0.38B PG64-22	1,313.00	TON		\$	
0130	00356		ASPHALT MATERIAL FOR TACK	70.00	TON		\$	
0140	00358		ASPHALT CURING SEAL	51.00	TON		\$	
0150	00387		CL3 ASPH SURF 0.38B PG76-22	317.00	TON		\$	
0160	02084		JPC PAVEMENT-8 IN	825.00	SQYD		\$	
0170	02602		FABRIC-GEOTEXTILE CLASS 1	14,917.00	SQYD		\$	
0180	02604		FABRIC-GEOTEXTILE CLASS 1A	17,302.00	SQYD		\$	
0190	02702		SAND FOR BLOTTER					

Report Date 1/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0420	02274		FENCE-6 FT CHAIN LINK	171.00	LF		\$	
0430	02287		DOUBLE VEHICULAR CHAIN LINK GATE	2.00	EACH		\$	
0440	02360		GUARDRAIL TERMINAL SECTION NO 1	6.00	EACH		\$	
0450	02381		REMOVE GUARDRAIL	1,106.00	LF		\$	
0460	02391		GUARDRAIL END TREATMENT TYPE 4A	10.00	EACH		\$	
0470	02397		TEMP GUARDRAIL	2,062.50	LF		\$	
0480	02429		RIGHT-OF-WAY MONUMENT TYPE 1	104.00	EACH		\$	
0490	02432		WITNESS POST	3.00	EACH		\$	
0500	02483		CHANNEL LINING CLASS II	8,655.00	TON		\$	
0510	02484		CHANNEL LINING CLASS III	1,964.00	TON		\$	
0520	02545		CLEARING AND GRUBBING 70 ACRES	1.00	LS		\$	
0530	02555		CONCRETE-CLASS B	25.00	CUYD		\$	
0540	02562		TEMPORARY SIGNS	770.00	SQFT		\$	
0550	02585		EDGE KEY	496.00	LF		\$	
0560	02603		FABRIC-GEOTEXTILE CLASS 2	14,000.00	SQYD		\$	
0570	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	9,543.00	SQYD	\$2.00	\$	\$19,086.00
0580	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0590	02651		DIVERSIONS (BY-PASS DETOURS) SOUTH ENGLISH ST.	1.00	LS		\$	
0600	02651		DIVERSIONS (BY-PASS DETOURS) US-62	1.00	LS		\$	
0610	02671		PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH			

Report Date 1/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0890	10030NS		ASPHALT ADJUSTMENT	95,293.00	DOLL	\$1.00	\$	\$95,293.00
0900	20191ED		OBJECT MARKER TY 3	10.00	EACH		\$	
0910	20458ES403		CENTERLINE RUMBLE STRIPS	8,874.00	LF		\$	
0920	20629NS719		THRIE BEAM TO W BEAM CONNECTOR	4.00	EACH		\$	
0930	21289ED		LONGITUDINAL EDGE KEY	2,780.00	LF		\$	
0940	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	4,762.50	LF		\$	
0950	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	60.00	LF		\$	
0960	23158ES505		DETECTABLE WARNINGS	102.00	SQFT		\$	
0970	23649EC		DRAIN POND KY 3155 STA. 923+50	1.00	LS		\$	
0980	23649EC		DRAIN POND KY 3155 STA. 958+00	1.00	LS		\$	
0990	23864EC		CHANNEL LINING CLASS III-MOD	1,887.00	TON		\$	
1000	24540		R/W MONUMENT TYPE 3	85.00	EACH		\$	
1010	24683ED		PAVE MARKING-THERMO DOTTED LANE EXTEN	40.00	LF		\$	
1020	26239EC		RAILROAD FLAGGER	20.00	DAY		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1030	00440		ENTRANCE PIPE-15 IN	1,195.00	LF		\$	
1040	00441		ENTRANCE PIPE-18 IN	340.00	LF		\$	
1050	00443		ENTRANCE PIPE-24 IN	188.00	LF		\$	
1060	00462		CULVERT PIPE-1					

251002

PROPOSAL BID ITEMS

Report Date 1/15/25

Page 4 of 6

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1290	23126EN		BORE AND JACK PIPE-18 IN	103.00	LF		\$	
1300	23610NC		CORED HOLE DRAINAGE BOX CON	1.00	EACH		\$	
1310	24814EC		PIPELINE INSPECTION	5,524.00	LF		\$	

Section: 0004 - BRIDGE - P&L RAILROAD - DWG. 28382

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1320	02231		STRUCTURE GRANULAR BACKFILL	1,557.00	CUYD		\$	
1330	02612		HANDRAIL-TYPE A-2	71.33	LF		\$	
1340	02998		MASONRY COATING	449.00	SQYD		\$	
1350	08002		STRUCTURE EXCAV-SOLID ROCK	489.00	CUYD		\$	
1360	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1370	08104		CONCRETE-CLASS AA	1,056.40	CUYD		\$	
1380	08105		CONCRETE-CLASS AAA	59.70	CUYD		\$	
1390	08150		STEEL REINFORCEMENT	135,813.00	LB		\$	
1400	08151		STEEL REINFORCEMENT-EPOXY COATED	8,935.00	LB		\$	
1410	08160		STRUCTURAL STEEL 107,071 LB	1.00	LS		\$	
1420	24848EC		DECK WATERPROOFING	1.00	LS		\$	
1430	24849EC		DECK DRAIN SYSTEM	1.00	LS		\$	
1440	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	65.20	LF		\$	

Section: 0005 - BRIDGE- CULVERT - CREEK - DWG. 28383

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1450	08003							

251002

PROPOSAL BID ITEMS

Page 5 of 6

Report Date 1/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1620	16052		G VALVE POLYETHYLENE/PLASTIC 06 INCH	4.00	EACH		\$	
1630	16071		G METER AND REGULATOR 2 INCH	1.00	EACH		\$	
1640	16072		G METER AND REGULATOR 3/4 INCH	1.00	EACH		\$	
1650	16607		G CAP EXISTING MAIN	15.00	EACH		\$	
1660	16611		G SERVICE TEST AND RELIGHT	16.00	EACH		\$	

Section: 0007 - SEWER - CITY OF LEITCHFIELD

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1670	15000		S BYPASS PUMPING	3.00	EACH		\$	
1680	15023		S ENCASEMENT STEEL OPEN CUT RANGE 4	100.00	LF		\$	
1690	15057		S FORCE MAIN PVC 02 INCH	265.00	LF		\$	
1700	15060		S FORCE MAIN PVC 06 INCH	495.00	LF		\$	
1710	15069		S FORCE MAIN TAP SLEEVE/VALVE RNG 1	2.00	EACH		\$	
1720	15071		S FORCE MAIN TIE-IN 02 INCH	2.00	EACH		\$	
1730	15084		S FORCE MAIN VALVE GATE	2.00	EACH		\$	
1740	15090		S LATERAL SHORT SIDE 06 INCH	2.00	EACH		\$	
1750	15092		S MANHOLE	11.00	EACH		\$	
1760	15094		S MANHOLE ADJUST TO GRADE	1.00	EACH		\$	
1770	15099		S MANHOLE TAP EXISTING	1.00	EACH		\$	
1780	15112		S PIPE PVC 08 INCH GRAVITY	1,160.00	LF		\$	
1790	15155		S CAP EXISTING MAIN	8.00	EACH			

251002

PROPOSAL BID ITEMS

Page 6 of 6

Report Date 1/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1950	14003		W CAP EXISTING MAIN	9.00	EACH		\$	
1960	14014		W ENCASEMENT STEEL OPEN CUT RANGE 3	640.00	LF		\$	
1970	14019		W FIRE HYDRANT ASSEMBLY	2.00	EACH		\$	
1980	14021		W FIRE HYDRANT REMOVE	2.00	EACH		\$	
1990	14028		W METER 3/4 INCH	4.00	EACH		\$	
2000	14059		W PIPE PVC 06 INCH	2,350.00	LF		\$	
2010	14060		W PIPE PVC 08 INCH	500.00	LF		\$	
2020	14080		W SERV PE/PLST LONG SIDE 3/4 IN	1.00	EACH		\$	
2030	14085		W SERV PE/PLST SHORT SIDE 3/4 IN	6.00	EACH		\$	
2040	14089		W TAPPING SLEEVE AND VALVE SIZE 1	10.00	EACH		\$	
2050	14105		W VALVE 06 INCH	3.00	EACH		\$	
2060	14158		W BLOWOFF ASSEMBLY LEITCHFIELD	5.00	EACH		\$	

Section: 0010 - WATERLINE - GRAYSON COUNTY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2070	14003		W CAP EXISTING MAIN	1.00	EACH		\$	
2080	14009		W ENCASEMENT STEEL BORED RANGE 4	35.00	LF		\$	
2090	14060		W PIPE PVC 08 INCH	1,731.00	LF		\$	
2100	14081		W SERVICE RELOCATE	2.00	EACH		\$	
2110	14086		W SERVICE SPECIAL	1.00	EACH		\$	
2120	14089		W TAPPING SLEEVE AND VALVE SIZE 1	1.00	EACH		\$	
2								

