



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

February 23, 2022

CALL NO. 330
CONTRACT ID NO. 222178
ADDENDUM # 2

Subject: Woodford County, FD05 120 0062 005-008
Letting February 24, 2022

- (1) Revised - Summary Sheet - Page 43 of 57
- (2) Revised - Proposal Bid Items - Page 57 of 57

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**Woodford County
TRAFFIC LOOP SUMMARY
FD05 120 0062 005-008
LOOP SUMMARY FOR ASPHALT PAVEMENT BID ALTERNATE**

INTERSECTION	SAW, SLOT AND FILL		LOOP WIRE		CONDUIT 1 INCH		Rigid Steel CONDUIT 1 1/4 INCH		PVC CONDUIT 1 1/4 INCH		PVC CONDUIT 2 INCH		CABLE NO. 14		JUNCTION TYPE B		Open Cut		Trenching & Backfilling		Boring & Jack		Loop Test		Remove Unused Signal Equipment		NOTES	
	LF		LF		LF		LF		LF		LF		EA		LF		EA		LF		LF		EA		EA			
KY 2113	1115		3190		110		440		440		0		2685		8		0		880		0		0		11		1	
US 60X	925		2308		70		175		175		0		640		3		355		0		355		7		1			
Rose Hill	910		2360		80		55		55		0		1120		4		110		0		0		8		1			
Total	2950		7858		260		670		670		0		4445		15		465		880		355		26		3			

NOTES for all intersections:
 1. Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities
 2. 2 - 1 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/tie-in to poles/cabinets
 Only replace existing conduit if damaged.

PROPOSAL BID ITEMS

Report Date 2/23/22

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	403.00	TON		\$	
0020	00307		CL2 ASPH SURF 0.38B PG64-22	2,950.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	22.00	TON		\$	
0040	02562		TEMPORARY SIGNS	270.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	115.00	TON		\$	
0090	02720		SIDEWALK-4 IN CONCRETE	6.00	SQYD		\$	
0100	03240		BASE FAILURE REPAIR	135.00	SQYD		\$	
0110	04792		CONDUIT-1 IN (REVISED 2-23-22)	260.00	LF		\$	
0115	04793		CONDUIT-1 1/4 IN (ADDED 2-23-22)	670.00	LF		\$	
0120	04811		ELECTRICAL JUNCTION BOX TYPE B	15.00	EACH		\$	
0130	04820		TRENCHING AND BACKFILLING	880.00	LF		\$	
0140	04821		OPEN CUT ROADWAY	465.00	LF		\$	
0150	04830		LOOP WIRE	7,858.00	LF		\$	
0160	04850		CABLE-NO. 14/1 PAIR	4,445.00	LF		\$	
0170	04895		LOOP SAW SLOT AND FILL	2,950.00	LF		\$	
0180	06510		PAVE STRIPING-TEMP PAINT-4 IN	20,000.00	LF		\$	
0190	06515		PAVE STRIPING-PERM PAINT-6 IN	46,000.00	LF		\$	
0200	06544		PAVE STRIPING-THERMO-8 IN W	32.00	LF		\$	
0210	06545		PAVE STRIPING-THERMO-8 IN Y	32.00	LF		\$	
0220	06568		PAVE MARKING-THERMO STOP BAR-24IN	150.00	LF		\$	
0230	06574		PAVE MARKING-THERMO CURV ARROW	23.00	EACH		\$	
0231	10020NS		FUEL ADJUSTMENT (ADDED 2-16-2022)	5,219.00	DOLL	\$1.00	\$	\$5,219.00
0232	10030NS		ASPHALT ADJUSTMENT (REVISED 2-16-2022)	13,109.00	DOLL	\$1.00	\$	\$13,109.00
0240	21543EN		BORE AND JACK CONDUIT	355.00	LF		\$	
0250	23158ES505		DETECTABLE WARNINGS NEW	10.00	SQFT		\$	
0260	23625EC		PAVE MARK THERMO-6 IN W CAT TRAXX	150.00	LF		\$	
0270	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80 (REVISED 2-23-22)	670.00	LF		\$	
0275	24955ED		REMOVE SIGNAL EQUIPMENT (ADDED 2-23-2022)	3.00	EACH		\$	
0280	24963ED		LOOP TEST	26.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0290	02569		DEMOBILIZATION	1.00	LS		\$	