



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

September 15, 2020

CALL NO. 331
CONTRACT ID NO. 202210
ADDENDUM # 1

Subject: JEFFERSON COUNTY, FD05 056 1865 000-001
Letting September 25, 2020

- (1) Revised - Traffic Loop Summary - Page 39 of 55
- (2) Revised - Proposal Bid Items - Page 55 of 55

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**JEFFERSON COUNTY
TRAFFIC LOOP SUMMARY
FD05 056 1865 000-001**

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH		CONDUIT 1 1/4 INCH		CONDUIT 2 INCH		CABLE NO. 14 LF	JUNCTION BORE & JACK TYPE B EA	CONDUIT LF	ROADWAY LF	REMOVE AND REPLACE SIDEWALK SQ YD	Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA	LF	EA								
COMMERCE PARK / OLD NEW CUT																
1865 NB	200	500	30	400		1439	3							400	3	16x30, 2 GES 6X6 LOOPS
1865 SB	200	500	30	400		675	3							400	3	16x30, 2 GES 6X6 LOOPS
old new cut	165	370	10	50		60	1							50	1	6X30 STOP BAR LOOP
commerce park	245	600	10	40		440	1							50	2	2 6X30 STOP BAR LOOPS
Total	810	1970	80	890	0	2614	8	0	0	0	0	0	0	900	9	
Grand Total	810	1970	80	890	0	2614	8	0	0	0	0	0	0	900	9	

1. Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities.
 2. 2 - 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/tie-in to poles/cabinets. specifications.
 Only replace existing conduit if damaged.

PROPOSAL BID ITEMS

202210

Page 1 of 1

Report Date 9/15/20

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	221.00	TON		\$	
0020	00356		ASPHALT MATERIAL FOR TACK	14.00	TON		\$	
0030	00388		CL3 ASPH SURF 0.38B PG64-22	1,960.00	TON		\$	
0040	02562		TEMPORARY SIGNS	290.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02671		PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	1,835.00	TON		\$	
0090	02775		ARROW PANEL	1.00	EACH		\$	
0100	03240		BASE FAILURE REPAIR	40.00	SQYD		\$	
0110	04792		CONDUIT-1 IN (ADDED: 9-15-20)	80.00	LF		\$	
0120	04811		ELECTRICAL JUNCTION BOX TYPE B (ADDED: 9-15-20)	8.00	EACH		\$	
0130	04820		TRENCHING AND BACKFILLING (ADDED: 9-15-20)	900.00	LF		\$	
0140	04830		LOOP WIRE (REVISED: 9-15-20)	1,970.00	LF		\$	
0150	04850		CABLE-NO. 14/1 PAIR (ADDED: 9-15-20)	2,614.00	LF		\$	
0160	04895		LOOP SAW SLOT AND FILL (REVISED: 9-15-20)	810.00	LF		\$	
0170	06510		PAVE STRIPING-TEMP PAINT-4 IN	23,800.00	LF		\$	
0180	06514		PAVE STRIPING-PERM PAINT-4 IN	23,800.00	LF		\$	
0190	06547		PAVE STRIPING-THERMO-12 IN Y	50.00	LF		\$	
0200	06568		PAVE MARKING-THERMO STOP BAR-24IN	212.00	LF		\$	
0210	06569		PAVE MARKING-THERMO CROSS-HATCH	300.00	SQFT		\$	
0220	06574		PAVE MARKING-THERMO CURV ARROW	16.00	EACH		\$	
0230	06600		REMOVE PAVEMENT MARKER TYPE V	114.00	EACH		\$	
0240	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80 (ADDED: 9-15-20)	890.00	LF		\$	
0250	24963ED		LOOP TEST (ADDED: 9-15-20)	9.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0260	02569		DEMOBILIZATION	1.00	LS		\$	