



**COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Matthew G. Bevin**  
Governor

**Greg Thomas**  
Secretary

April 23, 2019

CALL NO. 332  
CONTRACT ID NO. 192147  
ADDENDUM # 1

Subject: MCCREARY COUNTY, FD05 074 0027 000-005  
Letting April 26, 2019

- (1) Revised - Loop Summary Sheet - Page 36 of 60
- (2) Revised - Markings Summary Sheet - Page 37 of 60
- (3) Revised - Proposal Bid Items - Page 60 of 60

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures



An Equal Opportunity Employer M/F/D

**McCreary County**  
**TRAFFIC LOOP SUMMARY**  
**FD05-074-0027-000-005**  
**LOOP SUMMARY**

MPT.	INTERSECTION	SAW SLOT AND FILL		LOOP WIRE		CONDUIT 1 INCH		CONDUIT 1 1/4 INCH		CONDUIT 1 1/2 INCH		CONDUIT 2 INCH		CABLE NO. 14		LOOP TEST		JUNCTION BOX		TRENCHING AND BACKFILLING		NOTES	
		LF		RS	LF	RS	LF	RS	LF	RS	LF	RS	LF	EA	EA	EA	EA	EA	EA	EA			
4.608	US 27 @ KY 2792 & KY 1651																						
	South Leg	348		872		60		280		210		60		3300		3		3		3	600		(1) 6 ft x 30 ft Loop @ Stop Bar in Left Turn Lane, (2) 6 ft x 6 ft Loops 201 ft from Stop Bar in Thru Lanes, (2) 6 ft x 6 ft Loops 352 ft from Stop Bar in Thru Lanes.
<b>TOTAL</b>		<b>348</b>		<b>872</b>		<b>60</b>		<b>280</b>		<b>210</b>		<b>60</b>		<b>3300</b>		<b>3</b>		<b>3</b>		<b>3</b>	<b>600</b>		

**NOTES:**  
1. Quantities are for estimating purposes only. The Contractor shall field measure items to verify quantities.  
2. All loops shall feed into 1" rigid steel conduit as per standard detail



**PROPOSAL BID ITEMS**

192147

Page 1 of 1

Report Date 4/23/19

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	825.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	3,720.00	TON		\$	
0030	00388		CL3 ASPH SURF 0.38B PG64-22	7,455.00	TON		\$	
0040	02562		TEMPORARY SIGNS	430.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	220.00	TON		\$	
0090	02696		SHOULDER RUMBLE STRIPS	49,000.00	LF		\$	
0100	02775		ARROW PANEL	2.00	EACH		\$	
0110	04792		CONDUIT-1 IN	60.00	LF		\$	
0120	04793		CONDUIT-1 1/4 IN	280.00	LF		\$	
0130	04795		CONDUIT-2 IN	60.00	LF		\$	
0140	04811		ELECTRICAL JUNCTION BOX TYPE B	3.00	EACH		\$	
0150	04820		TRENCHING AND BACKFILLING	600.00	LF		\$	
0160	04830		LOOP WIRE	872.00	LF		\$	
0170	04850		CABLE-NO. 14/1 PAIR	3,300.00	LF		\$	
0180	04895		LOOP SAW SLOT AND FILL	348.00	LF		\$	
0190	06510		PAVE STRIPING-TEMP PAINT-4 IN	40,000.00	LF		\$	
0200	06514		PAVE STRIPING-PERM PAINT-4 IN	90,000.00	LF		\$	
0230	06568		PAVE MARKING-THERMO STOP BAR-24IN	215.00	LF		\$	
0240	06569		PAVE MARKING-THERMO CROSS-HATCH	3,000.00	SQFT		\$	
0250	06574		PAVE MARKING-THERMO CURV ARROW	7.00	EACH		\$	
0260	06578		PAVE MARKING-THERMO MERGE ARROW	24.00	EACH		\$	
0270	06600		REMOVE PAVEMENT MARKER TYPE V	850.00	EACH		\$	
0280	10020NS		FUEL ADJUSTMENT	16,803.00	DOLL	\$1.00	\$	\$16,803.00
0290	10030NS		ASPHALT ADJUSTMENT	42,204.00	DOLL	\$1.00	\$	\$42,204.00
0300	20458ES403		CENTERLINE RUMBLE STRIPS	26,500.00	LF		\$	
0310	24963ED		LOOP TEST	3.00	EACH		\$	
0320	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	50.00	TON		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0330	02569		DEMOBILIZATION	1.00	LS		\$	