



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET

[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

September 20, 2021

CALL NO. 332  
CONTRACT ID NO. 212391  
ADDENDUM # 1

Subject: Pulaski County, FD05 100 080X 002-006  
Letting September 24, 2021

(1) Revised - Traffic Loop Summary - Page 33 of 52

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

**Pulaski County**  
**TRAFFIC LOOP SUMMARY**  
**FD05 100 080X 002-006**

MPT.	INTERSECTION	SAW, SLOT AND FILL		LOOP WIRE		RIGID STEEL CONDUIT		PVC CONDUIT		PVC CONDUIT		CABLE NO. 14		LOOP TEST		JUNCTION BOX		NOTES	
		LF	EA	LF	EA	1 INCH LF	1 1/4 INCH LF	2 INCH LF	NO. 14 LF	Each	EA	EA	EA	EA	EA				
	KY 80X @ US 27																		
	East Leg	314		748		20		10				15		2		1		2-6'x30" Loops at stop bar	
	KY 80X @ Maple Street																		
	South Leg	117		304		10		10				150		1		1		1-6'x30" Loop at Relocated Stop Bar Location	
	KY 80X @ Central Ave																		
	South Leg	152		364		10		10				120		1		1		1-6'x30" Loop at Stop Bar	
	KY 80X @ College St																		
	North Leg	110		304		10		10				10		1		1		1-6'x30" Loop at Stop Bar	
	KY 80X @ May St																		
	North Leg	110		300		10		10				200		1		1		***Signal may be permanently removed. Do not install unless directed to by project engineer.	
<b>TOTAL</b>		<b>803</b>		<b>2020</b>		<b>60</b>		<b>50</b>			<b>20</b>	<b>495</b>		<b>6</b>		<b>5</b>			

- NOTES:**
1. Relocate stop bar and loop location for the south leg of the KY 80X @ Maple Street approach.
  2. Field review existing junction box locations with a representative from the Division of Traffic to determine which junction boxes need to be replaced.
  3. All labor, materials, and equipment needed to replace or repair sidewalk damaged by junction box and/or conduit installation shall be incidental to the project.
  4. Coordinate with the City of Somerset for issues related to roadway lighting wired into the decorative signal poles.