



**COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Matthew G. Bevin**  
Governor

**Greg Thomas**  
Secretary

January 22, 2018

CALL NO. 337  
CONTRACT ID NO. 182059  
ADDENDUM # 1

Subject: ROWAN COUNTY, FE06 103 0173 004-003  
Letting January 26, 2018

(1) Revised - Summary Sheet - Page 24 of 47  
(2) Revised - Bid Items - Page 47 of 47

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures



An Equal Opportunity Employer M/F/D

**CRIBBING SUMMARY**  
**FE06 103 173 003-004**

Site	Begin Milepoint	End Milepoint	Length (FT)	Cribbing Depth (FT)	Excavation Width (FT)	Post Spacing (FT)	Number of Rows	Driven Guardrail Posts-9 Ft. (EACH)	Cribbing (SQ FT)	Crushed Limestone No. 2 (TON)	Type IV Geotextile Fabric (SQ YD)
1	3.500	3.548	255	3	4	4	1	65	760	95	280
2	3.599	3.650	270	3	4	4	1	70	805	100	300
3	3.680	3.729	260	3	4	4	1	65	780	100	290
<b>TOTALS</b>									<b>2,345</b>	<b>295</b>	<b>870</b>

**PROPOSAL BID ITEMS**

182059

Page 1 of 1

Report Date 1/22/18

**Section: 0001 - GUARDRAIL**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	110.00	TON		\$	
0020	00078		CRUSHED AGGREGATE SIZE NO 2 (LIMESTONE)	295.00	TON		\$	
0030	00461		CULVERT PIPE-15 IN	60.00	LF		\$	
0040	01380		METAL END SECTION TY 2-15 IN	1.00	EACH		\$	
0050	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	42.00	EACH		\$	
0060	02014		BARRICADE-TYPE III	2.00	EACH		\$	
0070	02353		INSTALL GUARDRAIL-STEEL W BM-S FACE	1,862.50	LF		\$	
0080	02360		GUARDRAIL TERMINAL SECTION NO 1	1.00	EACH		\$	
0090	02371		GUARDRAIL END TREATMENT TYPE 7	6.00	EACH		\$	
0100	02373		GUARDRAIL END TREATMENT TYPE 3	1.00	EACH		\$	
0110	02399		EXTRA LENGTH GUARDRAIL POST INSTALLED-9 FOOT-FOR CRIB WALL)	200.00	EACH		\$	
0120	02562		TEMPORARY SIGNS	150.00	SQFT		\$	
0130	02599		FABRIC-GEOTEXTILE TYPE IV (REVISED: 1-22-18)	870.00	SQYD		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0150	03236		CRIBBING	2,345.00	SQFT		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0160	02569		DEMOBILIZATION	1.00	LS		\$	