



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

April 20, 2023

CALL NO. 344
CONTRACT ID NO. 232221
ADDENDUM # 2

Subject: Franklin County, FEMA 242247
Letting April 27, 2023

(1) Revised - Special Note - Page 11 of 61

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SPECIAL NOTE FOR STAKING

In addition to the requirements of Section 201, perform the following:

1. Contrary to Section 201.03.01, perform items 1-3 usually performed by the Engineer; and
2. Field survey the existing pavement in order to establish the existing cross slopes, transitions and profile. Irregularities in the existing pavement are to be eliminated with the construction of a smooth line and grade of the new pavement to ensure the best rideability possible.
3. Verify intersection and lane profile and alignment and prepare a Drainage Development Worksheet to provide for positive drainage upon completion of construction; and
4. Prior to incorporating into the work, obtain the Engineers approval of all designs and revisions to be provided by the Contractor; and
5. Produce and furnish to the Engineer "As Built" plans; and
6. Perform all other staking operations required to control and construct the work.

Project Discretion

Approximately 15 to 20 trees within the clearing area will be marked by the property owner, to be used by the property owner. The contractor is to remove those trees for the property owner's use. The stumps of the trees are to remain. This work is to be incidental to Clearing and Grubbing.

The contractor is to remove and reset the deck on the west side of KY 1659. Relocate the deck to a location outside of the work area before work begins and reset the deck in its initial location after the work has completed. If the deck is damaged, the contractor shall repair or replace in kind. This work is to be incidental to Clearing and Grubbing.

If the contractor encounters buried pipes or drainage features while excavating, those items are to be put back in the condition that they were found.

KYTC Maintenance (Franklin County) is to investigate placing a pipe across the roadway, draining from east to west, before the reconstruction of the KY 1659. That work is to be carried out by and coordinated with KYTC Franklin County Maintenance.

Michael Dees: 502-210-5400