



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

March 23, 2026

CALL NO. 355
CONTRACT ID NO. 261117
ADDENDUM # 1

Subject: Warren County, FD06 114 0031W 001-002
Letting March 26, 2026

- (1) Revised - Proposal Bid Items - Pages 47-49 of 49
- (2) Revised - Plan Sheet - R2D

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

PROPOSAL BID ITEMS

Report Date 3/23/26

261117

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	3,953.00	TON		\$	
0020	00005		GEOGRID REINFORCEMENT FOR SUBGRADE	3,504.00	SQYD		\$	
0030	00100		ASPHALT SEAL AGGREGATE	11.90	TON		\$	
0040	00103		ASPHALT SEAL COAT	1.40	TON		\$	
0050	00190		LEVELING & WEDGING PG64-22	53.00	TON		\$	
0060	00212		CL2 ASPH BASE 1.00D PG64-22	652.00	TON		\$	
0070	00214		CL3 ASPH BASE 1.00D PG64-22	520.00	TON		\$	
0080	00356		ASPHALT MATERIAL FOR TACK	3.70	TON		\$	
0090	00388		CL3 ASPH SURF 0.38B PG64-22	594.00	TON		\$	
0100	02073		JPC PAVEMENT-9 IN	312.00	SQYD		\$	
0110	02084		JPC PAVEMENT-8 IN	258.00	SQYD		\$	
0120	02602		FABRIC-GEOTEXTILE CLASS 1	3,504.00	SQYD		\$	
0130	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0140	02677		ASPHALT PAVE MILLING & TEXTURING	537.00	TON		\$	
0150	20550ND		SAWCUT PAVEMENT	3,242.00	LF		\$	
0160	21289ED		LONGITUDINAL EDGE KEY	1,779.00	LF		\$	
0170	23379EC		STAMPED CONCRETE	312.00	SQYD		\$	
0180	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0190	01000		PERFORATED PIPE-4 IN	1,592.00	LF		\$	
0200	01740		CORED HOLE DRAINAGE BOX CON-4 IN	18.00	EACH		\$	
0210	01810		STANDARD CURB AND GUTTER	1,554.00	LF		\$	
0220	01820		LIP CURB AND GUTTER	455.00	LF		\$	
0225	01891		ISLAND HEADER CURB TYPE 2 (ADDED 3-23-26)	146.00	LF		\$	
0230	01921		STANDARD BARRIER MEDIAN TYPE 4	97.00	SQYD		\$	
0240	01939		MOUNTABLE MEDIAN TYPE 3	379.00	SQYD		\$	
0250	02091		REMOVE PAVEMENT	59.00	SQYD		\$	
0260	02101		CEM CONC ENT PAVEMENT-8 IN	367.00	SQYD		\$	
0270	02159		TEMP DITCH	821.00	LF		\$	
0280	02160		CLEAN TEMP DITCH	411.00	LF		\$	
0290	02230		EMBANKMENT IN PLACE	1,937.00	CUYD		\$	
0300	02483		CHANNEL LINING CLASS II	43.00	TON		\$	
0310	02545		CLEARING AND GRUBBING APPROX. 6.0 AC.	1.00	LS		\$	
0320	02562		TEMPORARY SIGNS	1,270.00	SQFT		\$	
0330	02585		EDGE KEY	132.00	LF		\$	
0340	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0350	02651		DIVERSIONS (BY-PASS DETOURS)	1.00	LS		\$	

PROPOSAL BID ITEMS

Report Date 3/23/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0370	02701		TEMP SILT FENCE	821.00	LF		\$	
0380	02703		SILT TRAP TYPE A	6.00	EACH		\$	
0390	02704		SILT TRAP TYPE B	6.00	EACH		\$	
0400	02705		SILT TRAP TYPE C	6.00	EACH		\$	
0410	02706		CLEAN SILT TRAP TYPE A	6.00	EACH		\$	
0420	02707		CLEAN SILT TRAP TYPE B	6.00	EACH		\$	
0430	02708		CLEAN SILT TRAP TYPE C	6.00	EACH		\$	
0440	02726		STAKING	1.00	LS		\$	
0450	02775		ARROW PANEL	2.00	EACH		\$	
0460	05950		EROSION CONTROL BLANKET	232.00	SQYD		\$	
0470	05952		TEMP MULCH	19,231.00	SQYD		\$	
0480	05953		TEMP SEEDING AND PROTECTION	14,423.00	SQYD		\$	
0490	05963		INITIAL FERTILIZER	2.60	TON		\$	
0500	05964		MAINTENANCE FERTILIZER	1.30	TON		\$	
0510	05985		SEEDING AND PROTECTION	18,198.00	SQYD		\$	
0520	05990		SODDING	6,547.00	SQYD		\$	
0530	05992		AGRICULTURAL LIMESTONE	16.00	TON		\$	
0540	06511		PAVE STRIPING-TEMP PAINT-6 IN	7,250.00	LF		\$	
0550	06542		PAVE STRIPING-THERMO-6 IN W	3,022.00	LF		\$	
0560	06545		PAVE STRIPING-THERMO-8 IN Y	4,021.00	LF		\$	
0570	06569		PAVE MARKING-THERMO CROSS-HATCH	168.00	SQFT		\$	
0580	06575		PAVE MARKING-THERMO COMB ARROW	4.00	EACH		\$	
0590	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	60.00	LF		\$	
0600	23158ES505		DETECTABLE WARNINGS	184.00	SQFT		\$	
0610	24114EC		PAVE MARK-THERMO-YIELD	4.00	EACH		\$	
0620	24683ED		PAVE MARKING-THERMO DOTTED LANE EXTEN	149.00	LF		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0630	00443		ENTRANCE PIPE-24 IN	53.00	LF		\$	
0640	00462		CULVERT PIPE-18 IN	47.00	LF		\$	
0650	00468		CULVERT PIPE-36 IN	63.00	LF		\$	
0660	00522		STORM SEWER PIPE-18 IN	1,511.00	LF		\$	
0670	01450		S & F BOX INLET-OUTLET-18 IN	1.00	EACH		\$	
0680	01452		S & F BOX INLET-OUTLET-30 IN	2.00	EACH		\$	
0690	01453		S & F BOX INLET-OUTLET-36 IN	2.00	EACH		\$	
0700	01480		CURB BOX INLET TYPE B	11.00	EACH		\$	
0710	01577		DROP BOX INLET TYPE 14	3.00	EACH		\$	
0720	01767		MANHOLE TYPE C	2.00	EACH		\$	
0730	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	2,940.00	SQYD	\$2.00	\$	\$5,880.00
0740	21800EN		BORE AND JACK PIPE-30 IN	90.00	LF		\$	
0750	24186EC		BORE AND JACK PIPE-36 IN	65.00	LF		\$	
0760	24814EC		PIPELINE INSPECTION	1,005.00	LF		\$	

PROPOSAL BID ITEMS

Report Date 3/23/26

Section: 0004 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0770	06406		SBM ALUM SHEET SIGNS .080 IN	283.00	SQFT		\$	
0780	06410		STEEL POST TYPE 1	560.00	LF		\$	
0790	21596ND		GMSS TYPE D	6.00	EACH		\$	
0800	21813NN		REMOVE AND RELOCATE SHEET SIGNS	5.00	EACH		\$	
0810	24631EC		BARCODE SIGN INVENTORY	75.00	EACH		\$	

Section: 0005 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0820	04700		POLE 30 FT MTG HT	6.00	EACH		\$	
0830	04701		POLE 40 FT MTG HT	10.00	EACH		\$	
0840	04721		BRACKET 6 FT	3.00	EACH		\$	
0850	04722		BRACKET 8 FT	2.00	EACH		\$	
0860	04723		BRACKET 10 FT	8.00	EACH		\$	
0870	04724		BRACKET 12 FT	3.00	EACH		\$	
0880	04740		POLE BASE	16.00	EACH		\$	
0890	04750		TRANSFORMER BASE	16.00	EACH		\$	
0900	04761		LIGHTING CONTROL EQUIPMENT	1.00	EACH		\$	
0910	04780		FUSED CONNECTOR KIT	32.00	EACH		\$	
0920	04820		TRENCHING AND BACKFILLING	2,600.00	LF		\$	
0930	04821		OPEN CUT ROADWAY	538.00	LF		\$	
0940	04832		WIRE-NO. 12	1,476.00	LF		\$	
0950	04833		WIRE-NO. 8	9,600.00	LF		\$	
0960	04940		REMOVE LIGHTING	1.00	LS		\$	
0970	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	7.00	EACH		\$	
0980	21543EN		BORE AND JACK CONDUIT	538.00	LF		\$	
0990	24589ED		LED LUMINAIRE	16.00	EACH		\$	
1000	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	2,582.00	LF		\$	
1010	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	556.00	LF		\$	

Section: 0006 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1020	02568		MOBILIZATION	1.00	LS		\$	
1030	02569		DEMOBILIZATION	1.00	LS		\$	

ITEM	DESCRIPTION	NOTE(S)	UNIT	US 31W	KY 240	ENTRANCES	TOTAL PROJECT
00003	CRUSHED STONE BASE	1.6	TON	3645	181	127	3953
00005	GEOGRID REINFORCEMENT FOR SUBGRADE	1	SOYD	3315	189		3504
00100	ASPHALT SEAL AGGREGATE	1	TON	11.9			11.9
00103	ASPHALT SEAL COAT	1	TON	1.4			1.4
00190	LEVELING & WEDGING PG64-22	1	TON	49	4		53
00212	CL2 ASPH BASE 1.00D PG64-22	1.6	TON	652			652
00214	CL3 ASPH BASE 1.00D PG64-22	1	TON	465	6	49	520
00356	ASPHALT MATERIAL FOR TACK	1	TON	3.4	0.2	0.1	3.7
00388	CL3 ASPH SURF 0.388 PG64-22	1	TON	537	37	20	594
00443	ENTRANCE PIPE-24 IN	2	LF			53	53
00462	CULVERT PIPE-18 IN	2	LF	47			47
00468	CULVERT PIPE-36 IN	2	LF	63			63
00522	STORM SEWER PIPE-18 IN	2	LF	1511			1511
01000	PERFORATED PIPE-4 IN	2	LF	1592			1592
01450	S & F BOX INLET-OUTLET-18 IN	2	EACH	1			1
01452	S & F BOX INLET-OUTLET-30 IN	2	EACH	2			2
01453	S & F BOX INLET-OUTLET-36 IN	2	EACH	2			2
01480	CURB BOX INLET TYPE B	2	EACH	11			11
01577	DROP BOX INLET TYPE 14	2	EACH	3			3
01740	CORED HOLE DRAINAGE BOX CON-4 IN	2	EACH	18			18
01767	MANHOLE TYPE C	2	EACH	2			2
01810	STANDARD CURB AND GUTTER		LF	1554			1554
01820	LIP CURB AND GUTTER		LF	455			455
01921	STANDARD BARRIER MEDIAN TYPE 4		SOYD	97			97
01939	MOUNTABLE MEDIAN TYPE 3		SOYD	307	72		379
02073	JPC PAVEMENT-9 IN	1	SOYD	312			312
02084	JPC PAVEMENT-8 IN	1	SOYD			258	258
02091	REMOVE PAVEMENT		SOYD	51	8		59
02101	CEM CONC ENT PAVEMENT-8 IN	1	SOYD			367	367
02159	TEMP DITCH		LF	821			821
02160	CLEAN TEMP DITCH		LF	411			411
02230	EMBANKMENT IN PLACE		CUYD	1937			1937
02483	CHANNEL LINING CLASS II	2	TON	43			43
02545	CLEARING AND GRUBBING	7	LS	1			1
02562	TEMPORARY SIGNS	6.9	SOFT	1020	250		1270
02568	MOBILIZATION		LS	1			1
02569	DEMOBILIZATION		LS	1			1
02585	EDGE KEY		LF	52	80		132
02602	FABRIC-GEOTEXTILE CLASS 1	1	SOYD	3315	189		3504
02607	FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	8	SOYD	2940			2940
02650	MAINTAIN & CONTROL TRAFFIC	6	LS	1			1
02651	DIVERSIONS (BY-PASS DETOURS)	6	LS	1			1
02671	PORTABLE CHANGEABLE MESSAGE SIGN	6	EACH	4			4
02676	MOBILIZATION FOR MILL & TEXT	1	LS	1			1
02677	ASPHALT PAVE MILLING & TEXTURING	1	TON	495	42		537
02701	TEMP SILT FENCE		LF	821			821
02703	SILT TRAP TYPE A		EACH	6			6
02704	SILT TRAP TYPE B		EACH	6			6
02705	SILT TRAP TYPE C		EACH	6			6
02706	CLEAN SILT TRAP TYPE A		EACH	6			6
02707	CLEAN SILT TRAP TYPE B		EACH	6			6
02708	CLEAN SILT TRAP TYPE C		EACH	6			6
02726	STAKING		LS	1			1
02775	ARROW PANEL	5	EACH	2			2
04700	POLE 30 FT MTG HT	5	EACH	6			6

ITEM	DESCRIPTION	NOTE(S)	UNIT	US 31W	KY 240	ENTRANCES	TOTAL PROJECT
04701	POLE 40 FT MTG HT	5	EACH	10			10
04721	BRACKET 6 FT	5	EACH	3			3
04722	BRACKET 8 FT	5	EACH	2			2
04723	BRACKET 10 FT	5	EACH	8			8
04724	BRACKET 12 FT	5	EACH	3			3
04740	POLE BASE	5	EACH	16			16
04750	TRANSFORMER BASE	5	EACH	16			16
04761	LIGHTING CONTROL EQUIPMENT	5	EACH	1			1
04780	FUSED CONNECTOR KIT	5	EACH	32			32
04820	TRENCHING AND BACKFILLING	5	LF	2600			2600
04821	OPEN CUT ROADWAY	5	LF	538			538
04832	WIRE-NO. 12	5	LF	1476			1476
04833	WIRE-NO. 8	5	LF	9600			9600
04940	REMOVE LIGHTING	5	LS	1			1
05990	SODDING		SOYD	6547			6547
05950	EROSION CONTROL BLANKET		SOYD	232			232
05952	TEMP MULCH		SOYD	19231			19231
05953	TEMP SEEDING AND PROTECTION		SOYD	14423			14423
05963	INITIAL FERTILIZER		TON	2.6			2.6
05964	MAINTENANCE FERTILIZER		TON	1.3			1.3
05985	SEEDING AND PROTECTION		SOYD	18198			18198
05992	AGRICULTURAL LIMESTONE		TON	16			16
06406	SBM ALUM SHEET SIGNS .080 IN	3	SOFT	283			283
06410	STEEL POST TYPE 1	3	LF	560			560
06511	PAVE STRIPING-TEMP PAINT-6 IN	4	LF	7250	1500		8750
06542	PAVE STRIPING-THERMO-6 IN W	4	LF	2621	401		3022
06545	PAVE STRIPING-THERMO-8 IN Y	4	LF	3597	424		4021
06569	PAVE MARKING-THERMO CROSS-HATCH	4	SOFT	151	17		168
06575	PAVE MARKING-THERMO COMB ARROW	4	EACH	4			4
20391NS835	ELECTRICAL JUNCTION BOX TYPE A	5	EACH	7			7
20550ND	SAWCUT PAVEMENT	1	LF	2920	322		3242
21289ED	LONGITUDINAL EDGE KEY	1	LF	1698	81		1779
21543EN	BORE AND JACK CONDUIT	5	LF	538			538
21596ND	GMSS TYPE D	3	EACH	6			6
21800EN	BORE AND JACK PIPE-30 IN	2	LF	90			90
21813NN	REMOVE AND RELOCATE SHEET SIGNS	3	EACH	5			5
22520EN	PAVE MARKING-THERMO YIELD BAR-36 IN	4	LF	32	28		60
23158E5505	DETECTABLE WARNINGS		SOFT	160	24		184
23379EC	STAMPED CONCRETE	1	SOYD	312			312
24114EC	PAVE MARK-THERMO-YIELD	4	EACH	2	2		4
24186EC	BORE AND JACK PIPE-36 IN	2	LF	65			65
24589ED	LED LUMINAIRE	5	EACH	16			16
24631EC	BARCODE SIGN INVENTORY	3	EACH	75			75
24683ED	PAVE MARKING-THERMO DOTTED LANE EXTEN	4	LF	149			149
24814EC	PIPELINE INSPECTION		LF	1005			1005
24900EC	PVC CONDUIT-1 1/4 IN-SCHEDULE 80	5	LF	2582			2582
24901EC	PVC CONDUIT-2 IN-SCHEDULE 80	5	LF	556			556
26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1	LS	1			1
01891	ISLAND HEADER CURB TYPE 2		LF	146			146

NOTES

- 1 CARRIED OVER FROM PAVING SUMMARY
 - 2 CARRIED OVER FROM PIPE DRAINAGE SUMMARY
 - 3 CARRIED OVER FROM SIGNAGE SUMMARY
 - 4 CARRIED OVER FROM STRIPING SUMMARY
 - 5 CARRIED OVER FROM LIGHTING PLANS
 - 6 FOR DIVERSION CONSTRUCTION, A QUANTITY OF APPROX. 721 TONS CRUSHED STONE BASE TO BE USED FOR DIVERSION.
 - 7 APPROXIMATELY 6.0 ACRES
- 8 FOR WRAPPING PIPE TRENCH BACKFILL
 - 9 INCLUDES QUANTITY FOR LIGHTING SUMMARY
- PROJECT TOTALS
- SUMMARY OF EARTHWORK
- EXCAVATION 1.537 C.Y.
- EMBANKMENT 1.937 C.Y.
- TOTAL EMBANKMENT 1.937 C.Y.



COMMONWEALTH OF KENTUCKY
DEPARTMENT OF HIGHWAYS



DRAWING TITLE: GENERAL SUMMARY SHEET

ITEM NO.
03-8853.10
SHEET NO.
R2D
COUNTY OF
WARREN

ITEM	DESCRIPTION	NOTE(S)	UNIT	US 31W	KY 240	ENTRANCES	TOTAL PROJECT
00003	CRUSHED STONE BASE	1.6	TON	3645	181	127	3953
00005	GEOGRID REINFORCEMENT FOR SUBGRADE	1	SOYD	3315	189		3504
00100	ASPHALT SEAL AGGREGATE	1	TON	11.9			11.9
00103	ASPHALT SEAL COAT	1	TON	1.4			1.4
00190	LEVELING & WEDGING PG64-22	1	TON	49	4		53
00212	CL2 ASPH BASE 1.00D PG64-22	1.6	TON	652			652
00214	CL3 ASPH BASE 1.00D PG64-22	1	TON	465	6	49	520
00356	ASPHALT MATERIAL FOR TACK	1	TON	3.4	0.2	0.1	3.7
00388	CL3 ASPH SURF 0.388 PG64-22	1	TON	537	37	20	594
00443	ENTRANCE PIPE-24 IN	2	LF			53	53
00462	CULVERT PIPE-18 IN	2	LF	47			47
00468	CULVERT PIPE-36 IN	2	LF	63			63
00522	STORM SEWER PIPE-18 IN	2	LF	1511			1511
01000	PERFORATED PIPE-4 IN	2	LF	1592			1592
01450	S & F BOX INLET-OUTLET-18 IN	2	EACH	1			1
01452	S & F BOX INLET-OUTLET-30 IN	2	EACH	2			2
01453	S & F BOX INLET-OUTLET-36 IN	2	EACH	2			2
01480	CURB BOX INLET TYPE B	2	EACH	11			11
01577	DROP BOX INLET TYPE 14	2	EACH	3			3
01740	CORED HOLE DRAINAGE BOX CON-4 IN	2	EACH	18			18
01767	MANHOLE TYPE C	2	EACH	2			2
01810	STANDARD CURB AND GUTTER		LF	1554			1554
01820	LIP CURB AND GUTTER		LF	455			455
01921	STANDARD BARRIER MEDIAN TYPE 4		SOYD	97			97
01939	MOUNTABLE MEDIAN TYPE 3		SOYD	307	72		379
02073	JPC PAVEMENT-9 IN	1	SOYD	312			312
02084	JPC PAVEMENT-8 IN	1	SOYD			258	258
02091	REMOVE PAVEMENT		SOYD	51	8		59
02101	CEM CONC ENT PAVEMENT-8 IN	1	SOYD			367	367
02159	TEMP DITCH		LF	821			821
02260	CLEAN TEMP DITCH		LF	411			411
02230	EMBANKMENT IN PLACE		CUYD	1937			1937
02483	CHANNEL LINING CLASS II	2	TON	43			43
02545	CLEARING AND GRUBBING	7	LS	1			1
02562	TEMPORARY SIGNS	6.9	SOFT	1020	250		1270
02568	MOBILIZATION		LS	1			1
02569	DEMOBILIZATION		LS	1			1
02585	EDGE KEY		LF	52	80		132
02602	FABRIC-GEOTEXTILE CLASS 1	1	SOYD	3315	189		3504
02607	FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	8	SOYD	2940			2940
02650	MAINTAIN & CONTROL TRAFFIC	6	LS	1			1
02651	DIVERSIONS (BY-PASS DETOURS)	6	LS	1			1
02671	PORTABLE CHANGEABLE MESSAGE SIGN	6	EACH	4			4
02676	MOBILIZATION FOR MILL & TEXT	1	LS	1			1
02677	ASPHALT PAVE MILLING & TEXTURING	1	TON	495	42		537
02701	TEMP SILT FENCE		LF	821			821
02703	SILT TRAP TYPE A		EACH	6			6
02704	SILT TRAP TYPE B		EACH	6			6
02705	SILT TRAP TYPE C		EACH	6			6
02706	CLEAN SILT TRAP TYPE A		EACH	6			6
02707	CLEAN SILT TRAP TYPE B		EACH	6			6
02708	CLEAN SILT TRAP TYPE C		EACH	6			6
02726	STAKING		LS	1			1
02775	ARROW PANEL	5	EACH	2			2
04700	POLE 30 FT MTG HT	5	EACH	6			6

ITEM	DESCRIPTION	NOTE(S)	UNIT	US 31W	KY 240	ENTRANCES	TOTAL PROJECT
04701	POLE 40 FT MTG HT	5	EACH	10			10
04721	BRACKET 6 FT	5	EACH	3			3
04722	BRACKET 8 FT	5	EACH	2			2
04723	BRACKET 10 FT	5	EACH	8			8
04724	BRACKET 12 FT	5	EACH	3			3
04740	POLE BASE	5	EACH	16			16
04750	TRANSFORMER BASE	5	EACH	16			16
04761	LIGHTING CONTROL EQUIPMENT	5	EACH	1			1
04780	FUSED CONNECTOR KIT	5	EACH	32			32
04820	TRENCHING AND BACKFILLING	5	LF	2600			2600
04821	OPEN CUT ROADWAY	5	LF	538			538
04832	WIRE-NO. 12	5	LF	1476			1476
04833	WIRE-NO. 8	5	LF	9600			9600
04940	REMOVE LIGHTING	5	LS	1			1
05990	SODDING		SOYD	6547			6547
05950	EROSION CONTROL BLANKET		SOYD	232			232
05952	TEMP MULCH		SOYD	19231			19231
05953	TEMP SEEDING AND PROTECTION		SOYD	14423			14423
05963	INITIAL FERTILIZER		TON	2.6			2.6
05964	MAINTENANCE FERTILIZER		TON	1.3			1.3
05985	SEEDING AND PROTECTION		SOYD	18198			18198
05992	AGRICULTURAL LIMESTONE		TON	16			16
06406	SBM ALUM SHEET SIGNS .080 IN	3	SOFT	283			283
06410	STEEL POST TYPE 1	3	LF	560			560
06511	PAVE STRIPING-TEMP PAINT-6 IN	4	LF	7250	1500		8750
06542	PAVE STRIPING-THERMO-6 IN W	4	LF	2621	401		3022
06545	PAVE STRIPING-THERMO-8 IN Y	4	LF	3597	424		4021
06569	PAVE MARKING-THERMO CROSS-HATCH	4	SOFT	151	17		168
06575	PAVE MARKING-THERMO COMB ARROW	4	EACH	4			4
20391NS835	ELECTRICAL JUNCTION BOX TYPE A	5	EACH	7			7
20550ND	SAWCUT PAVEMENT	1	LF	2920	322		3242
21289ED	LONGITUDINAL EDGE KEY	1	LF	1698	81		1779
21543EN	BORE AND JACK CONDUIT	5	LF	538			538
21596ND	GMSS TYPE D	3	EACH	6			6
21800EN	BORE AND JACK PIPE-30 IN	2	LF	90			90
21813NN	REMOVE AND RELOCATE SHEET SIGNS	3	EACH	5			5
22520EN	PAVE MARKING-THERMO YIELD BAR-36 IN	4	LF	32	28		60
23158E5505	DETECTABLE WARNINGS		SOFT	160	24		184
23379EC	STAMPED CONCRETE	1	SOYD	312			312
24114EC	PAVE MARK-THERMO-YIELD	4	EACH	2	2		4
24186EC	BORE AND JACK PIPE-36 IN	2	LF	65			65
24589ED	LED LUMINAIRE	5	EACH	16			16
24631EC	BARCODE SIGN INVENTORY	3	EACH	75			75
24683ED	PAVE MARKING-THERMO DOTTED LANE EXTEN	4	LF	149			149
24814EC	PIPELINE INSPECTION		LF	1005			1005
24900EC	PVC CONDUIT-1 1/4 IN-SCHEDULE 80	5	LF	2582			2582
24901EC	PVC CONDUIT-2 IN-SCHEDULE 80	5	LF	556			556
26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1	LS	1			1
01891	ISLAND HEADER CURB TYPE 2		LF	146			146

NOTES

- 1 CARRIED OVER FROM PAVING SUMMARY
 - 2 CARRIED OVER FROM PIPE DRAINAGE SUMMARY
 - 3 CARRIED OVER FROM SIGNAGE SUMMARY
 - 4 CARRIED OVER FROM STRIPING SUMMARY
 - 5 CARRIED OVER FROM LIGHTING PLANS
 - 6 FOR DIVERSION CONSTRUCTION, A QUANTITY OF APPROX. 721 TONS CRUSHED STONE BASE TO BE USED FOR DIVERSION.
 - 7 APPROXIMATELY 6.0 ACRES
- 8 FOR WRAPPING PIPE TRENCH BACKFILL
 - 9 INCLUDES QUANTITY FROM LIGHTING SUMMARY
- PROJECT TOTALS
- SUMMARY OF EARTHWORK
- EXCAVATION 1.537 C.Y.
- EMBANKMENT 1.937 C.Y.
- TOTAL EMBANKMENT 1.937 C.Y.