



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

July 19, 2022

CALL NO. 400
CONTRACT ID NO. 222482
ADDENDUM # 1

Subject: Adair County, 001GR22P047-FD05
Letting July 21, 2022

- (1) Revised - Material Summary - Pages 42-44 of 84
- (2) Revised - Summary Sheet - Page 47 of 84
- (3) Revised - Proposal Bid Items - Pages 83-84 of 84

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

MATERIAL SUMMARY

CONTRACT ID: 222482

001GR22P047-FD05

MP00100612301

COLUMBIA - GREENSBURG ROAD (KY 61) FROM KY 768 EXTENDING NORTH TO GREEN COUNTY LINE ASPHALT RESURFACING, A DISTANCE OF 2.55 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0240	00190	LEVELING & WEDGING PG64-22	273.00	TON
0245	00301	CL2 ASPH SURF 0.38D PG64-22	2,340.00	TON
0250	00356	ASPHALT MATERIAL FOR TACK	20.00	TON
0255	02562	TEMPORARY SIGNS	350.00	SQFT
0260	02585	EDGE KEY	400.00	LF
0265	02650	MAINTAIN & CONTROL TRAFFIC - (KY 61, MP 17-20)	1.00	LS
0270	02697	EDGELINE RUMBLE STRIPS	26,950.00	LF
0275	06510	PAVE STRIPING-TEMP PAINT-4 IN	7,500.00	LF
0280	06542	PAVE STRIPING-THERMO-6 IN W	27,000.00	LF
0285	06543	PAVE STRIPING-THERMO-6 IN Y	18,250.00	LF
0290	06568	PAVE MARKING-THERMO STOP BAR-24IN	50.00	LF
0295	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 222482

001GR22P047-FD05

MP00100612303

BURKESVILLE - COLUMBIA ROAD (KY 61) 530 FEET NORTH OF GOLDENROD LANE EXTENDING TO KY 55 ASPHALT RESURFACING, A DISTANCE OF 1.71 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0065	00190	LEVELING & WEDGING PG64-22	508.00	TON
0070	00301	CL2 ASPH SURF 0.38D PG64-22	1,250.00	TON
0075	00356	ASPHALT MATERIAL FOR TACK	41.00	TON
0080	00388	CL3 ASPH SURF 0.38B PG64-22	4,560.00	TON
0085	02562	TEMPORARY SIGNS	290.00	SQFT
0090	02650	MAINTAIN & CONTROL TRAFFIC - (KY 61, MP 10-13)	1.00	LS
0095	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0100	02676	MOBILIZATION FOR MILL & TEXT - (KY 61, MP 10-13)	1.00	LS
0105	02677	ASPHALT PAVE MILLING & TEXTURING	1,410.00	TON
0110	02696	SHOULDER RUMBLE STRIPS	15,600.00	LF
0115	02775	ARROW PANEL	2.00	EACH
0120	04792	CONDUIT-1 IN	110.00	LF
0125	04811	ELECTRICAL JUNCTION BOX TYPE B	11.00	EACH
0130	04820	TRENCHING AND BACKFILLING	1,330.00	LF
0135	04830	LOOP WIRE	3,450.00	LF
0140	04850	CABLE-NO. 14/1 PAIR	6,775.00	LF
0145	04895	LOOP SAW SLOT AND FILL	1,428.00	LF
0150	06510	PAVE STRIPING-TEMP PAINT-4 IN	20,000.00	LF
0155	06542	PAVE STRIPING-THERMO-6 IN W	24,600.00	LF
0160	06543	PAVE STRIPING-THERMO-6 IN Y	37,000.00	LF
0165	06568	PAVE MARKING-THERMO STOP BAR-24IN	408.00	LF
0170	06569	PAVE MARKING-THERMO CROSS-HATCH	1,726.00	SQFT
0175	06574	PAVE MARKING-THERMO CURV ARROW	44.00	EACH
0180	06575	PAVE MARKING-THERMO COMB ARROW	2.00	EACH
0185	06576	PAVE MARKING-THERMO ONLY	2.00	EACH
0190	06578	PAVE MARKING-THERMO MERGE ARROW	3.00	EACH
0195	06600	REMOVE PAVEMENT MARKER TYPE V	529.00	EACH
0200	10020NS	FUEL ADJUSTMENT	13,368.00	DOLL
0205	10030NS	ASPHALT ADJUSTMENT	33,576.00	DOLL
0210	24679ED	PAVE MARK THERMO CHEVRON	625.00	SQFT
0215	24900EC	PVC CONDUIT-1 1/4 IN-SCHEDULE 80	820.00	LF
0220	24901EC	PVC CONDUIT-2 IN-SCHEDULE 80	210.00	LF
0230	24963ED	LOOP TEST	17.00	EACH
0235	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 222482

001GR22P047-FD05

MP001055X2301

JAMESTOWN STREET (KY 55X) FROM KY 6177/KY 55 EXTENDING NORTH TO CUMBERLAND PARKWAY
 OVERPASS ASPHALT RESURFACING, A DISTANCE OF .39 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	64.00	TON
0010	00356	ASPHALT MATERIAL FOR TACK	5.00	TON
0015	00388	CL3 ASPH SURF 0.38B PG64-22	775.00	TON
0020	02562	TEMPORARY SIGNS	250.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (KY 55X)	1.00	LS
0030	02676	MOBILIZATION FOR MILL & TEXT - (KY 55X)	1.00	LS
0035	02677	ASPHALT PAVE MILLING & TEXTURING	775.00	TON
0040	06510	PAVE STRIPING-TEMP PAINT-4 IN	3,000.00	LF
0045	06515	PAVE STRIPING-PERM PAINT-6 IN	10,000.00	LF
0050	06568	PAVE MARKING-THERMO STOP BAR-24IN	88.00	LF
0055	06574	PAVE MARKING-THERMO CURV ARROW	9.00	EACH
0060	02569	DEMOBILIZATION	1.00	LS

Adair County
 TRAFFIC LOOP SUMMARY
 FD05 001 0061 010-013

MPT.	INTERSECTION	SAW, SLOT AND FILL		CABLE RIGID STEEL NO.14		PVC SCHEDULE 80 1 1/4 IN		PVC SCHEDULE 80 1 1/2 IN		PVC SCHEDULE 80 2 IN		JUNCTION TYBE B		TRENCHING AND BACKFILLING		REMOVE UNUSED SIGNAL EQUIPMENT		Loop Test EA
		LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	EA	EA	EA	EA	EA		
10.843	KY 61 @ KY 80 West & Walmart																	
	KY 61 South Leg	336	1500	30	190	0	0	0	0	0	0	3	430					5
	KY 61 North Leg	336	2420	30	190	0	0	0	0	210	3	430						5
	KY 80 West	252	530	10	20	0	0	0	0	0	1	20						2
	Walmart	252	530	10	20	0	0	0	0	0	1	20						2
12.213	KY 55 & KY 80 @ KY 61																	
	South KY 61	252	1795	30	400	0	0	0	0	0	3	430						3
		1428	3450	6775	110	820	0	0	0	210	11	1330						17

- NOTES:
- Quantities are for estimating purposes only. The Contractor shall field measure items to verify quantities.
 - For loops that are to be replaced, 1" RIGID STEEL conduit SHALL be installed at transition under edge of road & into junction box for each loop as per Division of Traffic detail sheets.
 - Replace any junction boxes that are damaged and/or holding water in accordance to Division of Traffic detail sheets.
 - Replace any disturbed sidewalk required for installation of replacement junction boxes and conduit at no additional cost to the department.
 - Reuse existing conduit as much as possible. Replace any damaged conduit and conduit needed to meet current NEC requirements.
 - 2 - 1 1/4 inch conduits may be used in place of 2" conduit.

PROPOSAL BID ITEMS

Report Date 7/19/22

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	845.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	3,590.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	66.00	TON		\$	
0040	00388		CL3 ASPH SURF 0.38B PG64-22	5,335.00	TON		\$	
0050	02562		TEMPORARY SIGNS	890.00	SQFT		\$	
0060	02585		EDGE KEY	400.00	LF		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC (KY 55X)	1.00	LS		\$	
0080	02650		MAINTAIN & CONTROL TRAFFIC (KY 61, MP 10-13)	1.00	LS		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC (KY 61, MP 17-20)	1.00	LS		\$	
0100	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0110	02676		MOBILIZATION FOR MILL & TEXT (KY 55X)	1.00	LS		\$	
0120	02676		MOBILIZATION FOR MILL & TEXT (KY 61, MP 10-13)	1.00	LS		\$	
0130	02677		ASPHALT PAVE MILLING & TEXTURING	2,185.00	TON		\$	
0140	02696		SHOULDER RUMBLE STRIPS	15,600.00	LF		\$	
0150	02697		EDGE LINE RUMBLE STRIPS	26,950.00	LF		\$	
0160	02775		ARROW PANEL	2.00	EACH		\$	
0170	04792		CONDUIT-1 IN	110.00	LF		\$	
0180	04811		ELECTRICAL JUNCTION BOX TYPE B	11.00	EACH		\$	
0190	04820		TRENCHING AND BACKFILLING	1,330.00	LF		\$	
0200	04830		LOOP WIRE	3,450.00	LF		\$	
0210	04850		CABLE-NO. 14/1 PAIR	6,775.00	LF		\$	
0220	04895		LOOP SAW SLOT AND FILL	1,428.00	LF		\$	
0230	06510		PAVE STRIPING-TEMP PAINT-4 IN	30,500.00	LF		\$	
0240	06515		PAVE STRIPING-PERM PAINT-6 IN	10,000.00	LF		\$	
0250	06542		PAVE STRIPING-THERMO-6 IN W	51,600.00	LF		\$	
0260	06543		PAVE STRIPING-THERMO-6 IN Y	55,250.00	LF		\$	
0270	06568		PAVE MARKING-THERMO STOP BAR-24IN	546.00	LF		\$	
0280	06569		PAVE MARKING-THERMO CROSS-HATCH	1,726.00	SQFT		\$	
0290	06574		PAVE MARKING-THERMO CURV ARROW	53.00	EACH		\$	
0300	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0310	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0320	06578		PAVE MARKING-THERMO MERGE ARROW	3.00	EACH		\$	
0330	06600		REMOVE PAVEMENT MARKER TYPE V	529.00	EACH		\$	
0340	10020NS		FUEL ADJUSTMENT	13,368.00	DOLL	\$1.00	\$	\$13,368.00
0350	10030NS		ASPHALT ADJUSTMENT	33,576.00	DOLL	\$1.00	\$	\$33,576.00
0360	24679ED		PAVE MARK THERMO CHEVRON	625.00	SQFT		\$	
0370	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	820.00	LF		\$	
0380	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	210.00	LF		\$	
0400	24963ED		LOOP TEST	17.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

PROPOSAL BID ITEMS

Report Date 7/19/22

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0410	02569		DEMOBILIZATION	1.00	LS		\$	