



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

September 22, 2025

CALL NO. 401
CONTRACT ID NO. 252124
ADDENDUM # 1

Subject: Campbell County, 019GR25P072 - FD05 & FE01
Letting September 25, 2025

- (1) Added - Special Notes - Page 13A of 77
- (2) Revised - Material Summary - Pages 44-46 of 77
- (3) Revised - Proposal Bid Items - Pages 76-77 of 77

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**SPECIAL NOTE FOR
STANDARD HEADER CURB-MODIFIED AND
CURB BOX INLET TYPE A REPLACEMENT
CAMPBELL COUNTY
FD05 019 1892 000-002**

Remove existing curb and replace with 12" Standard Header Curb-Modified with a 4-inch reveal and 8 inches below pavement to match field conditions. Remove and replace the top compartment of the damage Curb Box Inlets Type A. All locations will be marked by the project engineer prior to construction.

MATERIAL SUMMARY

CONTRACT ID: 252124 019GR25P072 - FD05 & FE01 MP01900082501

MARY INGLES HIGHWAY (KY 8) BEGINNING AT KY 445 EXTENDING EAST TO 0.04 MILES EAST OF MAPLE STREET ASPHALT RESURFACING, A DISTANCE OF 1.91 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0270	00356	ASPHALT MATERIAL FOR TACK	16.00	TON
0275	00388	CL3 ASPH SURF 0.38B PG64-22	2,490.00	TON
0280	02562	TEMPORARY SIGNS	270.00	SQFT
0285	02650	MAINTAIN & CONTROL TRAFFIC - (KY 8)	1.00	LS
0290	02676	MOBILIZATION FOR MILL & TEXT - (KY 8)	1.00	LS
0295	02677	ASPHALT PAVE MILLING & TEXTURING	2,490.00	TON
0300	02697	EDGE LINE RUMBLE STRIPS	18,000.00	LF
0305	03240	BASE FAILURE REPAIR	655.00	SQYD
0310	06510	PAVE STRIPING-TEMP PAINT-4 IN	40,400.00	LF
0315	06515	PAVE STRIPING-PERM PAINT-6 IN	40,400.00	LF
0320	06568	PAVE MARKING-THERMO STOP BAR-24IN	44.00	LF
0325	06574	PAVE MARKING-THERMO CURV ARROW	7.00	EACH
0330	10020NS	FUEL ADJUSTMENT	3,876.00	DOLL
0335	10030NS	ASPHALT ADJUSTMENT	9,735.00	DOLL
0340	20100ES842	PAVE MARK TEMP PAINT LINE ARROW	7.00	EACH
0345	23010EN	PAVE MARK TEMP PAINT STOP BAR-24 IN	44.00	LF
0350	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252124 019GR25P072 - FD05 & FE01 MP01911202501

MEMORIAL PARKWAY (KY 1120) BEGINNING AT WILSON ROAD EXTENDING EAST TO PAVEMENT JOINT AT HIGH SCHOOL ENTRANCE ASPHALT RESURFACING, A DISTANCE OF 2.19 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	42.00	TON
0010	00356	ASPHALT MATERIAL FOR TACK	20.00	TON
0015	00388	CL3 ASPH SURF 0.38B PG64-22	3,185.00	TON
0020	02562	TEMPORARY SIGNS	390.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1120)	1.00	LS
0030	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0035	02676	MOBILIZATION FOR MILL & TEXT - (KY 1120)	1.00	LS
0040	02677	ASPHALT PAVE MILLING & TEXTURING	3,185.00	TON
0045	02697	EDGE LINE RUMBLE STRIPS	12,400.00	LF
0050	02775	ARROW PANEL	2.00	EACH
0055	03240	BASE FAILURE REPAIR	130.00	SQYD
0060	06510	PAVE STRIPING-TEMP PAINT-4 IN	46,700.00	LF
0065	06515	PAVE STRIPING-PERM PAINT-6 IN	45,400.00	LF
0070	06565	PAVE MARKING-THERMO X-WALK-6 IN	1,296.00	LF
0075	06568	PAVE MARKING-THERMO STOP BAR-24IN	332.00	LF
0080	06574	PAVE MARKING-THERMO CURV ARROW	15.00	EACH
0085	06575	PAVE MARKING-THERMO COMB ARROW	5.00	EACH
0090	06576	PAVE MARKING-THERMO ONLY	6.00	EACH
0095	10020NS	FUEL ADJUSTMENT	5,023.00	DOLL
0100	10030NS	ASPHALT ADJUSTMENT	12,616.00	DOLL
0105	20100ES842	PAVE MARK TEMP PAINT LINE ARROW	20.00	EACH
0110	23010EN	PAVE MARK TEMP PAINT STOP BAR-24 IN	332.00	LF
0115	23625EC	PAVE MARK THERMO-6 IN W CAT TRAXX	80.00	LF
0120	26119EC	INSTALL RADAR PRESENCE DETECTOR TYPE A	4.00	EACH
0125	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252124 019GR25P072 - FD05 & FE01 MP01918922501

GRAND AVENUE (KY 1892) BEGINNING AT KY 1120 EXTENDING NORTH TO THE CONCRETE PAVEMENT AT CHURCHILL DRIVE ASPHALT RESURFACING, A DISTANCE OF 1.41 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0130	00307	CL2 ASPH SURF 0.38B PG64-22	3,120.00	TON
0135	00356	ASPHALT MATERIAL FOR TACK	20.00	TON
0140	02562	TEMPORARY SIGNS	470.00	SQFT
0145	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1892)	1.00	LS
0150	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0155	02676	MOBILIZATION FOR MILL & TEXT - (KY 1892)	1.00	LS
0160	02677	ASPHALT PAVE MILLING & TEXTURING	3,120.00	TON
0165	02775	ARROW PANEL	2.00	EACH
0170	03240	BASE FAILURE REPAIR	240.00	SQYD
0175	06510	PAVE STRIPING-TEMP PAINT-4 IN	37,400.00	LF
0180	06515	PAVE STRIPING-PERM PAINT-6 IN	37,400.00	LF
0185	06565	PAVE MARKING-THERMO X-WALK-6 IN	1,982.00	LF
0190	06566	PAVE MARKING-THERMO X-WALK-12 IN	294.00	LF
0195	06568	PAVE MARKING-THERMO STOP BAR-24IN	272.00	LF
0200	06574	PAVE MARKING-THERMO CURV ARROW	35.00	EACH
0205	06576	PAVE MARKING-THERMO ONLY	5.00	EACH
0210	10020NS	FUEL ADJUSTMENT	4,856.00	DOLL
0215	10030NS	ASPHALT ADJUSTMENT	12,198.00	DOLL
0220	20100ES842	PAVE MARK TEMP PAINT LINE ARROW	9.00	EACH
0225	20782NS714	PAVE MARKING THERMO-BIKE	24.00	EACH
0230	23010EN	PAVE MARK TEMP PAINT STOP BAR-24 IN	272.00	LF
0235	26119EC	INSTALL RADAR PRESENCE DETECTOR TYPE A	4.00	EACH
0240	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 252124 019GR25P072 - FD05 & FE01 MP01918922502

GRAND AVENUE (KY 1892) BEGINNING AT KY 1120 EXTENDING NORTH TO THE CONCRETE PAVEMENT AT CHURCHILL DRIVE ASPHALT RESURFACING, A DISTANCE OF 1.41 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0245	01585	REMOVE DROP BOX INLET - (REMOVE AND REPLACE) (FE01 - KY 1892)	10.00	EACH
0250	01876	STANDARD HEADER CURB MOD - (FE01 - KY 1892) - (REVISED 9-22-25)	3,140.00	LF
0255	01904	REMOVE CURB - (FE01 - KY 1892)	3,140.00	LF
0260	06406	SBM ALUM SHEET SIGNS .080 IN - (FE01 - KY 1892)	120.00	SQFT
0265	06510	PAVE STRIPING-TEMP PAINT-4 IN - (FE01 - KY 1892)	112.00	LF

252124

PROPOSAL BID ITEMS

Report Date 9/22/25

Page 1 of 2

252124

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	42.00	TON		\$	
0020	00307		CL2 ASPH SURF 0.38B PG64-22	3,120.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	56.00	TON		\$	
0040	00388		CL3 ASPH SURF 0.38B PG64-22	5,675.00	TON		\$	
0050	02562		TEMPORARY SIGNS	1,130.00	SQFT		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC (KY 1120)	1.00	LS		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC (KY 1892)	1.00	LS		\$	
0080	02650		MAINTAIN & CONTROL TRAFFIC (KY 8)	1.00	LS		\$	
0090	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0100	02676		MOBILIZATION FOR MILL & TEXT (KY 1120)	1.00	LS		\$	
0110	02676		MOBILIZATION FOR MILL & TEXT (KY 1892)	1.00	LS		\$	
0120	02676		MOBILIZATION FOR MILL & TEXT (KY 8)	1.00	LS		\$	
0130	02677		ASPHALT PAVE MILLING & TEXTURING	8,795.00	TON		\$	
0140	02697		EDGE LINE RUMBLE STRIPS	30,400.00	LF		\$	
0150	02775		ARROW PANEL	4.00	EACH		\$	
0160	03240		BASE FAILURE REPAIR	1,025.00	SQYD		\$	
0170	06510		PAVE STRIPING-TEMP PAINT-4 IN	124,500.00	LF		\$	
0180	06515		PAVE STRIPING-PERM PAINT-6 IN	123,200.00	LF		\$	
0190	06565		PAVE MARKING-THERMO X-WALK-6 IN	3,278.00	LF		\$	
0200	06566		PAVE MARKING-THERMO X-WALK-12 IN	294.00	LF		\$	
0210	06568		PAVE MARKING-THERMO STOP BAR-24IN	648.00	LF		\$	
0220	06574		PAVE MARKING-THERMO CURV ARROW	57.00	EACH		\$	
0230	06575		PAVE MARKING-THERMO COMB ARROW	5.00	EACH		\$	
0240	06576		PAVE MARKING-THERMO ONLY	11.00	EACH		\$	
0250	10020NS		FUEL ADJUSTMENT	13,755.00	DOLL	\$1.00	\$	\$13,755.00
0260	10030NS		ASPHALT ADJUSTMENT	34,549.00	DOLL	\$1.00	\$	\$34,549.00
0270	20100ES842		PAVE MARK TEMP PAINT LINE ARROW	36.00	EACH		\$	
0280	20782NS714		PAVE MARKING THERMO-BIKE	24.00	EACH		\$	
0290	23010EN		PAVE MARK TEMP PAINT STOP BAR-24 IN	648.00	LF		\$	
0300	23625EC		PAVE MARK THERMO-6 IN W CAT TRAXX	80.00	LF		\$	
0310	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	8.00	EACH		\$	

Section: 0002 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0320	01585		REMOVE DROP BOX INLET (REMOVE AND REPLACE) (FE01 - KY 1892)	10.00	EACH		\$	
0330	01876		STANDARD HEADER CURB MOD (FE01 - KY 1892) - (REVISED 9-22-25)	3,140.00	LF		\$	

Report Date 9/22/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0340	01904		REMOVE CURB (FE01 - KY 1892)	3,140.00	LF		\$	

Section: 0003 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0350	06406		SBM ALUM SHEET SIGNS .080 IN (FE01 - KY 1892)	120.00	SQFT		\$	
0360	06510		PAVE STRIPING-TEMP PAINT-4 IN (FE01 - KY 1892)	112.00	LF		\$	

Section: 0004 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0370	02569		DEMOBILIZATION	1.00	LS		\$	