



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

June 17, 2025

CALL NO. 401
CONTRACT ID NO. 252259
ADDENDUM # 1

Subject: McCracken County, 073GR25P??? - FD05 & FD04
Letting June 26, 2025

- (1) Revised - Special Note - Page 33 of 125
- (2) Revised - Summary Sheets - Pages 50-52 of 125
- (3) Revised - Proposal Bid Items - Pages 124-125 of 125

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SPECIAL NOTE FOR BASE FAILURE REPAIR

Repair locations listed on the summary are approximate only. The Engineer will determine actual repair locations and dimensions at the time of construction. Prior to overall milling and/or leveling and wedging, excavate the designated base failure areas by milling to a depth 10 inches below the existing asphalt pavement surface level. Dispose of the excavated materials at waste sites off the Right-of-Way obtained by the Contractor at no additional cost to the Department. See Special Note for Waste and Borrow.

On the same day trench is excavated, backfill the excavated area with 10 inches of Class 2 Asphalt Base 1.00D PG64-22, in 3 inch minimum and 4.5 inch maximum courses, up to the existing pavement surface. Compact the asphalt base to the proper compaction as required by Section 403. Seal the asphalt base with leveling and wedging. Perform all base failure repairs in such a manner that removal and replacement are completed on the same day. Do this work as one of the Contractor's first operations in order to allow further compaction by traffic. Do not mill or place new asphalt surface over repaired base failure areas until a minimum of 14 calendar days have elapsed after placement of the final course of asphalt base. After the 14 calendar day waiting period, and/or when the Engineer determines the base failure repair areas have sufficiently stabilized, begin milling and/or resurfacing operations. Prior to milling and/or constructing the new asphalt surface, level and wedge any settlement of the repair areas.

The bidder must draw conclusions as to the conditions encountered. The Department does not give any guarantee as to the accuracy of the data and will not consider any claim for additional compensation if the materials encountered that are not in accord with the classification shown.

Accept payment at the Contract unit prices per ton for Asphalt Milling and Texturing, Asphalt Base, and Leveling and Wedging as full compensation for all labor, materials, equipment, and incidentals for removing pavement and disposing of the materials, furnishing and placing asphalt base, leveling and wedging, and all other items necessary to complete the work according to these notes to the satisfaction of the Engineer.

MATERIAL SUMMARY

CONTRACT ID: 252259 073GR25P073 - FD05 & FD04 MP073045X2501

KENTUCKY AVENUE (US 45X OMIT MP 0.416-1.551) BEGIN AT US 45 EXTENDING NORTH TO 42 FEET SOUTH OF KY-3238/US-60X ASPHALT RESURFACING, A DISTANCE OF 2.11 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	448.00	TON
0010	02676	MOBILIZATION FOR MILL & TEXT - (FD05)	1.00	LS
0015	02677	ASPHALT PAVE MILLING & TEXTURING	2,570.00	TON
0020	10020NS	FUEL ADJUSTMENT	4,719.00	DOLL
0025	10030NS	ASPHALT ADJUSTMENT	11,854.00	DOLL
0030	00212	CL2 ASPH BASE 1.00D PG64-22 - (REVISED 6-17-25)	331.00	TON
0035	23362ES403	CL2 ASPH SURF 0.50B PG64-22	2,239.00	TON
0040	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	14.00	TON
0045	01810	STANDARD CURB AND GUTTER	546.00	LF
0050	01812	REMOVE CURB AND GUTTER	546.00	LF
0055	02014	BARRICADE-TYPE III	2.00	EACH
0060	02562	TEMPORARY SIGNS	590.00	SQFT
0065	02650	MAINTAIN & CONTROL TRAFFIC - (FD05)	1.00	LS
0070	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0075	02720	SIDEWALK-4 IN CONCRETE	100.00	SQYD
0080	02775	ARROW PANEL	2.00	EACH
0085	06510	PAVE STRIPING-TEMP PAINT-4 IN	5,432.00	LF
0090	06511	PAVE STRIPING-TEMP PAINT-6 IN	200.00	LF
0095	06514	PAVE STRIPING-PERM PAINT-4 IN	9,852.00	LF
0100	06515	PAVE STRIPING-PERM PAINT-6 IN	10,780.00	LF
0105	06542	PAVE STRIPING-THERMO-6 IN W	648.00	LF
0110	06565	PAVE MARKING-THERMO X-WALK-6 IN	2,544.00	LF
0115	06568	PAVE MARKING-THERMO STOP BAR-24IN	729.00	LF
0120	06569	PAVE MARKING-THERMO CROSS-HATCH	1,056.00	SQFT
0125	06573	PAVE MARKING-THERMO STR ARROW	2.00	EACH
0130	06574	PAVE MARKING-THERMO CURV ARROW	29.00	EACH
0135	06575	PAVE MARKING-THERMO COMB ARROW	2.00	EACH
0140	06576	PAVE MARKING-THERMO ONLY	2.00	EACH
0145	06610	INLAID PAVEMENT MARKER-MW - (CONCRETE)	36.00	EACH
0150	06612	INLAID PAVEMENT MARKER-BY	203.00	EACH
0155	06612	INLAID PAVEMENT MARKER-BY - (CONCRETE)	291.00	EACH
0160	20099ES842	PAVE MARK TEMP PAINT STOP BAR	729.00	LF
0165	20100ES842	PAVE MARK TEMP PAINT LINE ARROW	14.00	EACH
0170	20782NS714	PAVE MARKING THERMO-BIKE	35.00	EACH
0175	22692NS714	PAVEMENT MARKING-THERMO LETTERS	12.00	EACH
0180	23158ES505	DETECTABLE WARNINGS - (NEW)	24.00	SQFT
0185	23158ES505	DETECTABLE WARNINGS - (RETROFIT)	888.00	SQFT
0190	23261EC	PAVE MARK-THERMO-X-WALK-24 IN	304.00	LF
0195	23974EC	BIKE PATH	423.00	SQYD
0200	24386EC	PAVE MARKING THERMO-BIKE LANE ARROW	35.00	EACH
0205	26119EC	INSTALL RADAR PRESENCE DETECTOR TYPE A	31.00	EACH
0210	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252259 073GR25P073 - FD05 & FD04 MP073045X2502

KENTUCKY AVE. (US 45X) BEGIN AT US 45 EXTENDING NORTH TO 42 FEET SOUTH OF KY-3238/US-60X
SIGNS, A DISTANCE OF 2.11 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0215	01917	STANDARD BARRIER MEDIAN TYPE 2	32.00	SQYD
0220	02562	TEMPORARY SIGNS	590.00	SQFT
0225	02650	MAINTAIN & CONTROL TRAFFIC - (FD04)	1.00	LS
0230	02720	SIDEWALK-4 IN CONCRETE	30.00	SQYD
0235	06510	PAVE STRIPING-TEMP PAINT-4 IN	13,686.00	LF
0240	06511	PAVE STRIPING-TEMP PAINT-6 IN	12,122.00	LF
0245	06514	PAVE STRIPING-PERM PAINT-4 IN	13,686.00	LF
0250	06515	PAVE STRIPING-PERM PAINT-6 IN	12,122.00	LF
0255	06531	PAVE STRIPING REMOVAL-6 IN	700.00	LF
0260	06556	PAVE STRIPING-DUR TY 1-6 IN W	574.00	LF
0265	06598	PAVEMENT MARKING REMOVAL	930.00	SQFT
0270	22664EN	WATER BLASTING EXISTING STRIPE	28,512.00	LF
0275	22680EN	QWICK CURB MEDIAN SEPARATOR	112.00	LF
0280	23158ES505	DETECTABLE WARNINGS - (NEW)	48.00	SQFT
0285	23251ES717	PAVE MARK TY 1 TAPE X-WALK-6 IN	631.00	LF
0290	23265ES717	PAVE MARK TY 1 TAPE STOP BAR-24 IN	309.00	LF
0295	23266ES717	PAVE MARK TY 1 TAPE R/R X BUCKS-16 IN	20.00	LF
0300	23267ES717	PAVE MARK TY 1 TAPE-BIKE	61.00	EACH
0305	23267ES717	PAVE MARK TY 1 TAPE-BIKE - (BIKE LANE ARROW)	59.00	EACH
0310	23269ES717	PAVE MARK TY 1 TAPE-COMBO ARROW	2.00	EACH
0315	23270ES717	PAVE MARK TY 1 TAPE-CURV ARROW	46.00	EACH
0320	23974EC	BIKE PATH	404.00	SQYD
0325	26171EC	RECTANGULAR RAPID FLASHING BEACON	4.00	EACH
0330	06406	SBM ALUM SHEET SIGNS .080 IN	138.89	SQFT
0335	06410	STEEL POST TYPE 1	243.00	LF
0340	06472	INSTALL SPAN MOUNTED SIGN	1.00	EACH
0345	24631EC	BARCODE SIGN INVENTORY	26.00	EACH
0350	02569	DEMOBILIZATION	1.00	LS

GENERAL SUMMARY

COUNTY OF

FUNDING NO.

MCCRACKEN

FD05 073 045X 000-003

ITEM	DESCRIPTION	UNIT	TOTAL PROJECT
190	LEVELING & WEDGING PG64-22	TON	448
1810	STANDARD CURB AND GUTTER	LF	546
1812	REMOVE CURB AND GUTTER	LF	546
2014	BARRICADE-TYPE III	EACH	2
2562	TEMPORARY SIGNS	SQFT	590
2569	DEMOBILIZATION	LS	1
2650	MAINTAIN & CONTROL TRAFFIC	LS	1
2671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2
2676	MOBILIZATION FOR MILL & TEXT	LS	1
2677	ASPHALT PAVE MILLING & TEXTURING	TON	2,570
2720	SIDEWALK-4 IN CONCRETE	SQYD	100
2775	ARROW PANEL	EACH	2
6510	PAVE STRIPING-TEMP PAINT-4 IN	LF	5,432
6511	PAVE STRIPING-TEMP PAINT-6 IN	LF	200
6514	PAVE STRIPING-PERM PAINT-4 IN	LF	9,852
6515	PAVE STRIPING-PERM PAINT-6 IN	LF	10,780
6542	PAVE STRIPING-THERMO-6 IN W	LF	648
6565	PAVE MARKING-THERMO X-WALK-6 IN	LF	2,544
6568	PAVE MARKING-THERMO STOP BAR-24IN	LF	729
6569	PAVE MARKING-THERMO CROSS-HATCH	SQFT	1,056
6573	PAVE MARKING-THERMO STR ARROW	EACH	2
6574	PAVE MARKING-THERMO CURV ARROW	EACH	29
6575	PAVE MARKING-THERMO COMB ARROW	EACH	2
6576	PAVE MARKING-THERMO ONLY	EACH	2
6610	INLAID PAVEMENT MARKER-MW	EACH	36
6610	INLAID PAVEMENT MARKER-MW (CONCRETE)	EACH	21
6612	INLAID PAVEMENT MARKER-BY	EACH	203
6612	INLAID PAVEMENT MARKER-BY (CONCRETE)	EACH	291
10020NS	FUEL ADJUSTMENT	DOLL	4,719
10030NS	ASPHALT ADJUSTMENT	DOLL	11,854
20099ES842	PAVE MARK TEMP PAINT STOP BAR	LF	729
20100ES842	PAVE MARK TEMP PAINT LINE ARROW	EACH	14
00212	CL2 ASPH BASE 1.00D PG64-22	TON	331
20782NS714	PAVE MARKING THERMO-BIKE	EACH	35
22692NS714	PAVEMENT MARKING-THERMO LETTERS	EACH	12
23158ES505	DETECTABLE WARNINGS	SQFT	924
23261EC	PAVE MARK-THERMO-X-WALK-24 IN	LF	304
23362ES403	CL2 ASPH SURF 0.50B PG64-22	TON	2,239
23974EC	BIKE PATH	SQYD	423
24386EC	PAVE MARKING THERMO-BIKE LANE ARROW	EACH	35
24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	TON	14
26119EC	INSTALL RADAR PRESENCE DETECTOR TYPE A	EACH	31

- ① QUANTITY INCLUDES 331 TONS FOR THE REMOVAL OF THE EXISTING ASPHALT IN THE BASE FAILURE REPAIR SUMMARY AND 2,239 TONS IN THE MILLING AND SURFACING SUMMARY.
- ② SEE SPECIAL NOTE FOR CONSTRUCTING INLAID PAVEMENT MARKERS ON PORTLAND CEMENT PAVEMENT FOR PAYMENT OF THE GREEN BIKE LANE MARKING ON ASPHALT SURFACE. PRODUCT TO BE PPG'S MMAX EXTENDED SEASON AREA MARKINGS. SEE PRODUCT DATA SHEET ELSEWHERE IN PROPOSAL FOR MATERIAL AND APPLICATION GUIDANCE.
- ③

MCCRACKEN COUNTY
073GR25P??? - FD05 & FD04
252259

PROPOSAL BID ITEMS

Report Date 6/17/25

Page 1 of 2

252259

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	448.00	TON		\$	
0020	02676		MOBILIZATION FOR MILL & TEXT (FD05)	1.00	LS		\$	
0030	02677		ASPHALT PAVE MILLING & TEXTURING	2,570.00	TON		\$	
0040	10020NS		FUEL ADJUSTMENT	4,719.00	DOLL	\$1.00	\$	\$4,719.00
0050	10030NS		ASPHALT ADJUSTMENT	11,854.00	DOLL	\$1.00	\$	\$11,854.00
0060	00212		CL2 ASPH BASE 1.00D PG64-22 (REVISED 6-17-25)	331.00	TON		\$	
0070	23362ES403		CL2 ASPH SURF 0.50B PG64-22	2,239.00	TON		\$	
0080	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	14.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0090	01810		STANDARD CURB AND GUTTER	546.00	LF		\$	
0100	01812		REMOVE CURB AND GUTTER	546.00	LF		\$	
0110	01917		STANDARD BARRIER MEDIAN TYPE 2	32.00	SQYD		\$	
0120	02014		BARRICADE-TYPE III	2.00	EACH		\$	
0130	02562		TEMPORARY SIGNS	1,180.00	SQFT		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC (FD04)	1.00	LS		\$	
0150	02650		MAINTAIN & CONTROL TRAFFIC (FD05)	1.00	LS		\$	
0160	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0170	02720		SIDEWALK-4 IN CONCRETE	130.00	SQYD		\$	
0180	02775		ARROW PANEL	2.00	EACH		\$	
0190	06510		PAVE STRIPING-TEMP PAINT-4 IN	19,118.00	LF		\$	
0200	06511		PAVE STRIPING-TEMP PAINT-6 IN	12,322.00	LF		\$	
0210	06514		PAVE STRIPING-PERM PAINT-4 IN	23,538.00	LF		\$	
0220	06515		PAVE STRIPING-PERM PAINT-6 IN	22,902.00	LF		\$	
0230	06531		PAVE STRIPING REMOVAL-6 IN	700.00	LF		\$	
0240	06542		PAVE STRIPING-THERMO-6 IN W	648.00	LF		\$	
0250	06556		PAVE STRIPING-DUR TY 1-6 IN W	574.00	LF		\$	
0260	06565		PAVE MARKING-THERMO X-WALK-6 IN	2,544.00	LF		\$	
0270	06568		PAVE MARKING-THERMO STOP BAR-24IN	729.00	LF		\$	
0280	06569		PAVE MARKING-THERMO CROSS-HATCH	1,056.00	SQFT		\$	
0290	06573		PAVE MARKING-THERMO STR ARROW	2.00	EACH		\$	
0300	06574		PAVE MARKING-THERMO CURV ARROW	29.00	EACH		\$	
0310	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0320	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0330	06598		PAVEMENT MARKING REMOVAL	930.00	SQFT		\$	
0340	06610		INLAID PAVEMENT MARKER-MW (CONCRETE)	36.00	EACH		\$	
0350	06612		INLAID PAVEMENT MARKER-BY	203.00	EACH		\$	

MCCRACKEN COUNTY
073GR25P??? - FD05 & FD04
252259

PROPOSAL BID ITEMS

Page 2 of 2

Report Date 6/17/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	06612		INLAID PAVEMENT MARKER-BY (CONCRETE)	291.00	EACH		\$	
0370	20099ES842		PAVE MARK TEMP PAINT STOP BAR	729.00	LF		\$	
0380	20100ES842		PAVE MARK TEMP PAINT LINE ARROW	14.00	EACH		\$	
0390	20782NS714		PAVE MARKING THERMO-BIKE	35.00	EACH		\$	
0400	22664EN		WATER BLASTING EXISTING STRIPE	28,512.00	LF		\$	
0410	22680EN		QWICK CURB MEDIAN SEPARATOR	112.00	LF		\$	
0420	22692NS714		PAVEMENT MARKING-THERMO LETTERS	12.00	EACH		\$	
0430	23158ES505		DETECTABLE WARNINGS (NEW)	72.00	SQFT		\$	
0440	23158ES505		DETECTABLE WARNINGS (RETROFIT)	888.00	SQFT		\$	
0450	23251ES717		PAVE MARK TY 1 TAPE X-WALK-6 IN	631.00	LF		\$	
0460	23261EC		PAVE MARK-THERMO-X-WALK-24 IN	304.00	LF		\$	
0470	23265ES717		PAVE MARK TY 1 TAPE STOP BAR-24 IN	309.00	LF		\$	
0480	23266ES717		PAVE MARK TY 1 TAPE R/R X BUCKS-16 IN	20.00	LF		\$	
0490	23267ES717		PAVE MARK TY 1 TAPE-BIKE	61.00	EACH		\$	
0500	23267ES717		PAVE MARK TY 1 TAPE-BIKE (BIKE LANE ARROW)	59.00	EACH		\$	
0510	23269ES717		PAVE MARK TY 1 TAPE-COMBO ARROW	2.00	EACH		\$	
0520	23270ES717		PAVE MARK TY 1 TAPE-CURV ARROW	46.00	EACH		\$	
0530	23974EC		BIKE PATH	827.00	SQYD		\$	
0540	24386EC		PAVE MARKING THERMO-BIKE LANE ARROW	35.00	EACH		\$	
0550	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	31.00	EACH		\$	
0560	26171EC		RECTANGULAR RAPID FLASHING BEACON	4.00	EACH		\$	

Section: 0003 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0570	06406		SBM ALUM SHEET SIGNS .080 IN	138.89	SQFT		\$	
0580	06410		STEEL POST TYPE 1	243.00	LF		\$	
0590	06472		INSTALL SPAN MOUNTED SIGN	1.00	EACH		\$	
0600	24631EC		BARCODE SIGN INVENTORY	26.00	EACH		\$	

Section: 0004 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0610	02569		DEMOBILIZATION	1.00	LS		\$	