



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

August 16, 2023

CALL NO. 401
CONTRACT ID NO. 232244
ADDENDUM # 1

Subject: Shelby County, 106GR23P046-FD05
Letting August 24, 2023

- (1) Revised - Surfacing Areas - Page 10 of 48
- (2) Revised - Material Summary - Page 26 of 48
- (3) Revised - Proposal Bid Items - Page 48 of 48
- (4) Revised - Omit Proposal Page 27 of 48

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SURFACING AREAS KY 1871

The Department estimates the mainline surfacing width to be 22 feet.

The Department estimates the total mainline area to be surfaced to be 29,658 square yards.

The Department estimates the shoulder width to be varied 0 to 2 feet on each side.

The Department estimates the total shoulder area to be surfaced to be 1,993 square yards.

SURFACING AREAS KY 1005

The Department estimates the mainline surfacing width to be varied 21 to 75 feet.

The Department estimates the total mainline area to be surfaced to be 2,474 square yards.

The Department estimates the shoulder width to be n/a foot on each side.

The Department estimates the total shoulder area to be surfaced to be n/a square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

MATERIAL SUMMARY

CONTRACT ID: 232244

106GR23P046 - FD05

MP10610052301

VIGO ROAD (KY 1005) BEGIN AT KY 43 EXTENDING EAST TO KY 1871 ASPHALT RESURFACING, A DISTANCE OF .16 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0095	00190	LEVELING & WEDGING PG64-22	19.00	TON
0100	00301	CL2 ASPH SURF 0.38D PG64-22	140.00	TON
0105	02562	TEMPORARY SIGNS	210.00	SQFT
0110	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1005)	1.00	LS
0115	02676	MOBILIZATION FOR MILL & TEXT - (KY 1005)	1.00	LS
0120	02677	ASPHALT PAVE MILLING & TEXTURING	44.00	TON
0125	03240	BASE FAILURE REPAIR	50.00	SQYD
0130	06510	PAVE STRIPING-TEMP PAINT-4 IN	500.00	LF
0135	06515	PAVE STRIPING-PERM PAINT-6 IN	1,750.00	LF
0140	06562	PAVE MARKING-THERMO R 6 FT	2.00	EACH
0145	06563	PAVE MARKING-R/R XBUCKS 16 IN	44.00	LF
0150	06568	PAVE MARKING-THERMO STOP BAR-24IN	46.00	LF
0155	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	1.00	TON
0160	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 232244

106GR23P046 - FD05

MP10618712301

ROCKET LANE/CRANBOURNE LANE (KY 1871) BEGIN AT US 60 EXTENDING NORTH TO KY 1005 ASPHALT RESURFACING, A DISTANCE OF 2.08 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	463.00	TON
0010	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED 8-16-23)	1,740.00	TON
0015	02562	TEMPORARY SIGNS	310.00	SQFT
0020	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1871)	1.00	LS
0025	02676	MOBILIZATION FOR MILL & TEXT - (KY 1871)	1.00	LS
0030	02677	ASPHALT PAVE MILLING & TEXTURING	145.00	TON
0035	02697	EDGELINE RUMBLE STRIPS	22,060.00	LF
0040	03240	BASE FAILURE REPAIR	90.00	SQYD
0045	06510	PAVE STRIPING-TEMP PAINT-4 IN	20,500.00	LF
0050	06514	PAVE STRIPING-PERM PAINT-4 IN	25,000.00	LF
0055	06515	PAVE STRIPING-PERM PAINT-6 IN	18,000.00	LF
0060	06565	PAVE MARKING-THERMO X-WALK-6 IN	160.00	LF
0065	06568	PAVE MARKING-THERMO STOP BAR-24IN	30.00	LF
0070	06574	PAVE MARKING-THERMO CURV ARROW	6.00	EACH
0085	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING (REVISED 8-16-23)	15.00	TON
0090	02569	DEMOBILIZATION	1.00	LS

PROPOSAL BID ITEMS

Report Date 8/16/23

Page 1 of 1

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	482.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22 (REVISED 8-16-23)	1,880.00	TON		\$	
0030	02562		TEMPORARY SIGNS	520.00	SQFT		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC (KY 1871)	1.00	LS		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC (KY 1005)	1.00	LS		\$	
0060	02676		MOBILIZATION FOR MILL & TEXT (KY 1871)	1.00	LS		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT (KY 1005)	1.00	LS		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	189.00	TON		\$	
0090	02697		EDGELINE RUMBLE STRIPS	22,060.00	LF		\$	
0100	03240		BASE FAILURE REPAIR	140.00	SQYD		\$	
0110	06510		PAVE STRIPING-TEMP PAINT-4 IN	21,000.00	LF		\$	
0120	06514		PAVE STRIPING-PERM PAINT-4 IN	25,000.00	LF		\$	
0130	06515		PAVE STRIPING-PERM PAINT-6 IN	19,750.00	LF		\$	
0140	06562		PAVE MARKING-THERMO R 6 FT	2.00	EACH		\$	
0150	06563		PAVE MARKING-R/R XBUCKS 16 IN	44.00	LF		\$	
0160	06565		PAVE MARKING-THERMO X-WALK-6 IN	160.00	LF		\$	
0170	06568		PAVE MARKING-THERMO STOP BAR-24IN	76.00	LF		\$	
0180	06574		PAVE MARKING-THERMO CURV ARROW	6.00	EACH		\$	
0210	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING (REVISED 8-16-23)	16.00	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0220	02569		DEMOBILIZATION	1.00	LS		\$	