



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET

[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

November 25, 2020

CALL NO. 402  
CONTRACT ID NO. 202278  
ADDENDUM # 1

Subject: FLOYD COUNTY, 036GR20P054-FD51  
Letting December 11, 2020

- (1) Revised - Material Summary - Pages 38-41 of 75
- (2) Revised - Site Summary - Page 46 of 75
- (3) Revised - Guardrail Summary - Page 47 of 75
- (4) Revised - Proposal Bid Items - Pages 74-75 of 75

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

# MATERIAL SUMMARY

**CONTRACT ID: 202278**

**036GR20P054-FD51**

**MP03607772001**

STONE COAL ROAD (KY 777) FROM 25 FEET SOUTH OF HOOVER HOLLOW ROAD EXTENDING TO 0.407 MILES SOUTH OF HEAD OF TURKEY CREEK ROAD FLOOD REPAIR FOR FEMA, A DISTANCE OF 1.67 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE - (REVISED: 11-25-20)	11.00	TON
0010	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE - (REVISED: 11-25-20)	15.00	EACH
0015	02014	BARRICADE-TYPE III	4.00	EACH
0020	02351	GUARDRAIL-STEEL W BEAM-S FACE	662.50	LF
0025	02371	GUARDRAIL END TREATMENT TYPE 7	4.00	EACH
0030	02562	TEMPORARY SIGNS	300.00	SQFT
0035	02603	FABRIC-GEOTEXTILE CLASS 2 - (REVISED: 11-25-20)	287.00	SQYD
0040	02650	MAINTAIN & CONTROL TRAFFIC - (KY 777)	1.00	LS
0045	03234	RAILROAD RAILS-DRILLED - (REVISED: 11-25-20)	1,599.00	LF
0050	03235	EXCAVATION AND BACKFILL - (REVISED: 11-25-20)	151.00	CUYD
0055	03236	CRIBBING - (REVISED: 11-25-20)	1,310.00	SQFT
0060	20257NC	SITE PREPARATION - KY 777 SITE 1	1.00	LS
0065	20257NC	SITE PREPARATION - KY 777 SITE 2	1.00	LS
0070	21415ND	EROSION CONTROL - KY 777 SITE 1	1.00	LS
0075	21415ND	EROSION CONTROL - KY 777 SITE 2	1.00	LS
0080	02569	DEMOBILIZATION	1.00	LS

**CONTRACT ID: 202278**

**036GR20P054-FD51**

**MP03608502001**

HIPPO TO PYRAMID ROAD (KY 850) FROM 0.51 MILES NORTH OF HILL BRANCH ROAD EXTENDING TO 0.163 MILES SOUTH OF ASTER HICKS ROAD FLOOD REPAIR FOR FEMA, A DISTANCE OF .02 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0085	00001	DGA BASE - (REVISED: 11-25-20)	3.00	TON
0090	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE - (REVISED: 11-25-20)	2.00	EACH
0095	02014	BARRICADE-TYPE III	4.00	EACH
0100	02383	REMOVE & RESET GUARDRAIL - (REVISED: 11-25-20)	87.50	LF
0105	02562	TEMPORARY SIGNS	150.00	SQFT
0110	02603	FABRIC-GEOTEXTILE CLASS 2 - (REVISED: 11-25-20)	117.00	SQYD
0115	02650	MAINTAIN & CONTROL TRAFFIC - (KY 850)	1.00	LS
0120	03234	RAILROAD RAILS-DRILLED - (REVISED: 11-25-20)	468.00	LF
0125	03235	EXCAVATION AND BACKFILL - (REVISED: 11-25-20)	69.00	CUYD
0130	03236	CRIBBING - (REVISED: 11-25-20)	527.00	SQFT
0135	20257NC	SITE PREPARATION - KY 850 SITE 1	1.00	LS
0140	21415ND	EROSION CONTROL - KY 850 SITE 1	1.00	LS
0145	02569	DEMOBILIZATION	1.00	LS

# MATERIAL SUMMARY

**CONTRACT ID: 202278**

**036GR20P054-FD51**

**MP03610862001**

SIZEMORE ROAD (KY 1086) FROM 0.948 MILES NORTH OF STEELE CREEK CULVERT EXTENDING TO 0.152 MILES NORTH OF CEMETERY BRANCH ROAD/STILLHOUSE ROAD FLOOD REPAIR FOR FEMA, A DISTANCE OF 1.83 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0150	00001	DGA BASE - (REVISED: 11-25-20)	13.00	TON
0155	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE - (REVISED: 11-25-20)	82.00	EACH
0160	02014	BARRICADE-TYPE III	8.00	EACH
0165	02351	GUARDRAIL-STEEL W BEAM-S FACE	3,575.00	LF
0170	02360	GUARDRAIL TERMINAL SECTION NO 1	6.00	EACH
0175	02371	GUARDRAIL END TREATMENT TYPE 7	6.00	EACH
0180	02383	REMOVE & RESET GUARDRAIL - (REVISED: 11-25-20)	125.00	LF
0185	02396	REMOVE GUARDRAIL END TREATMENT - TYPE 7	1.00	EACH
0190	02399	EXTRA LENGTH GUARDRAIL POST - - 9 FOOT	20.00	EACH
0195	02562	TEMPORARY SIGNS	150.00	SQFT
0200	02603	FABRIC-GEOTEXTILE CLASS 2 - (REVISED: 11-25-20)	1,294.00	SQYD
0205	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1086)	1.00	LS
0210	03234	RAILROAD RAILS-DRILLED - (REVISED: 11-25-20)	7,566.00	LF
0215	03235	EXCAVATION AND BACKFILL - (REVISED: 11-25-20)	557.00	CUYD
0220	03236	CRIBBING - (REVISED: 11-25-20)	6,100.00	SQFT
0225	20257NC	SITE PREPARATION - KY 1086 SITE 6	1.00	LS
0230	20257NC	SITE PREPARATION - KY 1086 SITE 7	1.00	LS
0235	20257NC	SITE PREPARATION - KY 1086 SITES 1 (REVISED: 11-25-20)	1.00	LS
0240	20257NC	SITE PREPARATION - KY 1086 SITES 3, 4, & 5	1.00	LS
0245	21415ND	EROSION CONTROL - KY 1086 SITE 6	1.00	LS
0250	21415ND	EROSION CONTROL - KY 1086 SITE 7	1.00	LS
0255	21415ND	EROSION CONTROL - KY 1086 SITES 1 (REVISED: 11-25-20)	1.00	LS
0260	21415ND	EROSION CONTROL - KY 1086 SITES 3, 4, & 5	1.00	LS
0265	02569	DEMOBILIZATION	1.00	LS

# MATERIAL SUMMARY

**CONTRACT ID: 202278**

**036GR20P054-FD51**

**MP03612102001**

STEPHEN'S BRANCH ROAD (KY 1210) FROM 0.108 MILES NORTH OF BALLARD PRATER ROAD EXTENDING TO 0.132 MILES SOUTH OF SAMONS DRIVE FLOOD REPAIR FOR FEMA, A DISTANCE OF 3.79 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0270	00001	DGA BASE - (REVISED: 11-25-20)	15.00	TON
0275	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE - (REVISED: 11-25-20)	19.00	EACH
0280	02014	BARRICADE-TYPE III	6.00	EACH
0285	02351	GUARDRAIL-STEEL W BEAM-S FACE	625.00	LF
0290	02371	GUARDRAIL END TREATMENT TYPE 7	2.00	EACH
0295	02383	REMOVE & RESET GUARDRAIL - (REVISED: 11-25-20)	187.50	LF
0300	02396	REMOVE GUARDRAIL END TREATMENT - TYPE 7	2.00	EACH
0305	02562	TEMPORARY SIGNS	450.00	SQFT
0310	02603	FABRIC-GEOTEXTILE CLASS 2 - (REVISED: 11-25-20)	426.00	SQYD
0315	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1210)	1.00	LS
0320	03234	RAILROAD RAILS-DRILLED - (REVISED: 11-25-20)	2,301.00	LF
0325	03235	EXCAVATION AND BACKFILL - (REVISED: 11-25-20)	225.00	CUYD
0330	03236	CRIBBING - (REVISED: 11-25-20)	1,948.00	SQFT
0335	20257NC	SITE PREPARATION - KY 1210 SITE 1	1.00	LS
0340	20257NC	SITE PREPARATION - KY 1210 SITE 2	1.00	LS
0345	20257NC	SITE PREPARATION - KY 1210 SITE 3	1.00	LS
0350	20257NC	SITE PREPARATION - KY 1210 SITE 4	1.00	LS
0355	21415ND	EROSION CONTROL - KY 1210 SITE 1	1.00	LS
0360	21415ND	EROSION CONTROL - KY 1210 SITE 2	1.00	LS
0365	21415ND	EROSION CONTROL - KY 1210 SITE 3	1.00	LS
0370	21415ND	EROSION CONTROL - KY 1210 SITE 4	1.00	LS
0375	02569	DEMOBILIZATION	1.00	LS

# MATERIAL SUMMARY

**CONTRACT ID: 202278**

**036GR20P054-FD51**

**MP03620292001**

SALT LICK ROAD (KY 2029) FROM 0.149 MILES NORTH OF SHEPHERD SPUR ROAD EXTENDING TO 0.240 MILES SOUTH OF RACCOON BRANCH BRIDGE FLOOD REPAIR FOR FEMA, A DISTANCE OF .69 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0380	00001	DGA BASE - (REVISED: 11-25-20)	33.00	TON
0385	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE - (REVISED: 11-25-20)	9.00	EACH
0390	02014	BARRICADE-TYPE III	4.00	EACH
0395	02351	GUARDRAIL-STEEL W BEAM-S FACE	112.50	LF
0400	02371	GUARDRAIL END TREATMENT TYPE 7	1.00	EACH
0405	02383	REMOVE & RESET GUARDRAIL - (REVISED: 11-25-20)	225.00	LF
0410	02396	REMOVE GUARDRAIL END TREATMENT - TYPE 7	1.00	EACH
0415	02483	CHANNEL LINING CLASS II	50.00	TON
0420	02562	TEMPORARY SIGNS	150.00	SQFT
0425	02603	FABRIC-GEOTEXTILE CLASS 2 - (REVISED: 11-25-20)	544.00	SQYD
0430	02650	MAINTAIN & CONTROL TRAFFIC - (KY 2029)	1.00	LS
0435	03234	RAILROAD RAILS-DRILLED - (REVISED: 11-25-20)	2,769.00	LF
0440	03235	EXCAVATION AND BACKFILL - (REVISED: 11-25-20)	303.00	CUYD
0445	03236	CRIBBING - (REVISED: 11-25-20)	2,448.00	SQFT
0450	08019	CYCLOPEAN STONE RIP RAP	145.00	TON
0455	20257NC	SITE PREPARATION - KY 2029 SITE 2	1.00	LS
0460	20257NC	SITE PREPARATION - KY 2029 SITE 3	1.00	LS
0465	20257NC	SITE PREPARATION - KY 229 SITE 1	1.00	LS
0470	21415ND	EROSION CONTROL - KY 2029 SITE 1	1.00	LS
0475	21415ND	EROSION CONTROL - KY 2029 SITE 2	1.00	LS
0480	21415ND	EROSION CONTROL - KY 2029 SITE 3	1.00	LS
0485	02569	DEMOBILIZATION	1.00	LS

# SITE SUMMARY - KY 1086

Site	Begin	End	Length (FT)	Cribbing Depth (FT)	Excavation Width (FT)	Depth to Rock (FT)	Number of Rows	Rail Spacing (FT)	Cribbing Amount (SQ FT)	Drilled RR Rails (FT)	Excav. & Backfill (CU YD)	Geotextile Fabric Class 2 (SQ YD)	DGA (TONS)	
1	2.616	2.625	47	8	3	26	1	3	470	663	42	99	4	
2	2.692	2.722					NOT PART OF THIS CONTRACT							
3	3.065	3.074	51	8	3	26	1	3	510	702	46	108	3	
4	3.177	3.199	115	10	3	26	1	3	1,380	1,560	128	294	6	
5	3.353	3.393	210	10	3	26	1	3	2,520	2,769	234	537	16	
6	3.890	3.903	70	8	3	26	1	3	700	975	63	148	4	
7	4.303	4.315	65	6	3	26	1	3	520	897	44	108	5	
<b>TOTALS</b>										<b>6,100</b>	<b>7,566</b>	<b>557</b>	<b>1,294</b>	<b>13</b>

## GUARDRAIL SUMMARY - KY 1086

NEW GUARDRAIL							REMOVE & RESET GUARDRAIL				
LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	LANE	BEGIN MILEPOINT	END MILEPOINT	LIN FEET	REMARKS
Left	Type 7	2.501	2.618	Term Sect No. 1	625.0						
Left	Type 7	2.737	2.770	Type 7	175.0						
Right	Term Sect No. 1	2.981	3.074	Term Sect No. 1	500.0	5 Extra Length Posts					
Right	Term Sect No. 1	3.143	3.274	Type 7	700.0	5 Extra Length Posts					
Right	Tie to Existin	3.353	3.407	Term Sect No. 1	287.5	5 Extra Length Posts					
Right	Term Sect No. 1	3.750	3.858	Type 7	575.0	5 Exter Length Posts					
							Right	3.885	3.908	125.0	
Right	Type 7	4.193	4.326	Tie to Existin	712.5		Right	4.317		0.0	Remove End Treat Type 7

**TOTAL = 3,575.0**

**TOTAL = 125.0**

**PROPOSAL BID ITEMS**

202278

Page 1 of 2

Report Date 11/25/20

**Section: 0001 - ROADWAY**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE (REVISED: 11-25-20)	75.00	TON		\$	
0020	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE (REVISED: 11-25-20)	127.00	EACH		\$	
0030	02014		BARRICADE-TYPE III	26.00	EACH		\$	
0040	02351		GUARDRAIL-STEEL W BEAM-S FACE	4,975.00	LF		\$	
0050	02360		GUARDRAIL TERMINAL SECTION NO 1	6.00	EACH		\$	
0060	02371		GUARDRAIL END TREATMENT TYPE 7	13.00	EACH		\$	
0070	02383		REMOVE & RESET GUARDRAIL (REVISED: 11-25-20)	625.00	LF		\$	
0080	02396		REMOVE GUARDRAIL END TREATMENT TYPE 7	4.00	EACH		\$	
0090	02399		EXTRA LENGTH GUARDRAIL POST - 9 FOOT	20.00	EACH		\$	
0100	02483		CHANNEL LINING CLASS II	50.00	TON		\$	
0110	02562		TEMPORARY SIGNS	1,200.00	SQFT		\$	
0120	02603		FABRIC-GEOTEXTILE CLASS 2 (REVISED: 11-25-20)	2,668.00	SQYD		\$	
0130	02650		MAINTAIN & CONTROL TRAFFIC (KY 1086)	1.00	LS		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC (KY 1210)	1.00	LS		\$	
0150	02650		MAINTAIN & CONTROL TRAFFIC (KY 2029)	1.00	LS		\$	
0160	02650		MAINTAIN & CONTROL TRAFFIC (KY 777)	1.00	LS		\$	
0170	02650		MAINTAIN & CONTROL TRAFFIC (KY 850)	1.00	LS		\$	
0180	03234		RAILROAD RAILS-DRILLED (REVISED: 11-25-20)	14,703.00	LF		\$	
0190	03235		EXCAVATION AND BACKFILL (REVISED: 11-25-20)	1,305.00	CUYD		\$	
0200	03236		CRIBBING (REVISED: 11-25-20)	12,333.00	SQFT		\$	
0210	08019		CYCLOPEAN STONE RIP RAP	145.00	TON		\$	
0220	20257NC		SITE PREPARATION KY 1086 SITE 6	1.00	LS		\$	
0230	20257NC		SITE PREPARATION KY 1086 SITE 7	1.00	LS		\$	
0240	20257NC		SITE PREPARATION KY 1086 SITES 1 (REVISED: 11-25-20)	1.00	LS		\$	
0250	20257NC		SITE PREPARATION KY 1086 SITES 3, 4, & 5	1.00	LS		\$	
0260	20257NC		SITE PREPARATION KY 1210 SITE 1	1.00	LS		\$	
0270	20257NC		SITE PREPARATION KY 1210 SITE 2	1.00	LS		\$	
0280	20257NC		SITE PREPARATION KY 1210 SITE 3	1.00	LS		\$	
0290	20257NC		SITE PREPARATION KY 1210 SITE 4	1.00	LS		\$	



**PROPOSAL BID ITEMS**

202278

Page 2 of 2

Report Date 11/25/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0300	20257NC		SITE PREPARATION KY 2029 SITE 2	1.00	LS		\$	
0310	20257NC		SITE PREPARATION KY 2029 SITE 3	1.00	LS		\$	
0320	20257NC		SITE PREPARATION KY 229 SITE 1	1.00	LS		\$	
0330	20257NC		SITE PREPARATION KY 777 SITE 1	1.00	LS		\$	
0340	20257NC		SITE PREPARATION KY 777 SITE 2	1.00	LS		\$	
0350	20257NC		SITE PREPARATION KY 850 SITE 1	1.00	LS		\$	
0360	21415ND		EROSION CONTROL KY 1086 SITE 6	1.00	LS		\$	
0370	21415ND		EROSION CONTROL KY 1086 SITE 7	1.00	LS		\$	
0380	21415ND		EROSION CONTROL KY 1086 SITES 1 (REVISED: 11-25-20)	1.00	LS		\$	
0390	21415ND		EROSION CONTROL KY 1086 SITES 3, 4, & 5	1.00	LS		\$	
0400	21415ND		EROSION CONTROL KY 1210 SITE 1	1.00	LS		\$	
0410	21415ND		EROSION CONTROL KY 1210 SITE 2	1.00	LS		\$	
0420	21415ND		EROSION CONTROL KY 1210 SITE 3	1.00	LS		\$	
0430	21415ND		EROSION CONTROL KY 1210 SITE 4	1.00	LS		\$	
0440	21415ND		EROSION CONTROL KY 2029 SITE 1	1.00	LS		\$	
0450	21415ND		EROSION CONTROL KY 2029 SITE 2	1.00	LS		\$	
0460	21415ND		EROSION CONTROL KY 2029 SITE 3	1.00	LS		\$	
0470	21415ND		EROSION CONTROL KY 777 SITE 1	1.00	LS		\$	
0480	21415ND		EROSION CONTROL KY 777 SITE 2	1.00	LS		\$	
0490	21415ND		EROSION CONTROL KY 850 SITE 1	1.00	LS		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0500	02569		DEMOBILIZATION	1.00	LS		\$	