



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

October 14, 2025

CALL NO. 402
CONTRACT ID NO. 252365
ADDENDUM #1

Subject: Letcher County, 067GR25P087 - FD51
Letting October 23, 2025

Revised - Special Note P. 28 of 90
Revised - Material Summary P. 41-46 of 90
Revised - Proposal Bid Items P. 89-90 of 90

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ce
Enclosures

SPECIAL NOTE FOR SHOULDER PREPARATION

Grade, shape, and compact shoulder as shown on the typical section and as directed by the Engineer to provide proper template and foundation for the guardrail. The Department will not measure grading, shaping, and compacting shoulders for separate payment, but shall be incidental to Dense Graded Aggregate constructed on the shoulders and/or Guardrail, End Treatments, and Terminal Sections constructed on the shoulders.

MATERIAL SUMMARY

CONTRACT ID: 252365

067GR25P087-FD51

MP06703432501

FLEMING NEON - McROBERTS ROAD (KY 343) FROM 10 FEET NORTH OF STATE AVENURE EXTENDING NORTH TO 401 FEET SOUTH OF MORNING GLORY DRIVE FLOOD REPAIR FOR FEMA, A DISTANCE OF 2.9 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	46.00	TON
0010	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	4.00	EACH
0015	02187	SITE PREPARATION - (KY 343)	1.00	EACH
0020	02351	GUARDRAIL-STEEL W BEAM-S FACE	137.50	LF
0025	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
0030	02371	GUARDRAIL END TREATMENT TYPE 7	1.00	EACH
0035	02483	CHANNEL LINING CLASS II	37.00	TON
0040	02484	CHANNEL LINING CLASS III	143.00	TON
0045	02562	TEMPORARY SIGNS	350.00	SQFT
0050	02602	FABRIC-GEOTEXTILE CLASS 1	525.00	SQYD
0055	02650	MAINTAIN & CONTROL TRAFFIC - (KY 343)	1.00	LS
0060	03234	RAILROAD RAILS-DRILLED	1,326.00	LF
0065	03235	EXCAVATION AND BACKFILL	176.00	CUYD
0070	03236	CRIBBING	1,188.00	SQFT
0075	21415ND	EROSION CONTROL - (KY 343) - REVISED 10-14-25	1.00	LS
0080	21554EN	EXCAVATION	54.00	CUYD
0085	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252365

067GR25P087-FD51

MP06705882501

BLACKKEY - WHITESBURG ROAD (KY 588) FROM 0.198 MILE WEST OF WINDMILL ACRES ROAD EXTENDING EAST TO 216 FEET WEST OF THE FARM ROAD FLOOD REPAIR FOR FEMA, A DISTANCE OF 4.9 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0090	00001	DGA BASE	11.00	TON
0095	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	8.00	EACH
0100	02187	SITE PREPARATION - (KY 588)	1.00	EACH
0105	02351	GUARDRAIL-STEEL W BEAM-S FACE	75.00	LF
0110	02371	GUARDRAIL END TREATMENT TYPE 7	1.00	EACH
0115	02383	REMOVE & RESET GUARDRAIL	112.50	LF
0120	02396	REMOVE GUARDRAIL END TREATMENT - TYPE 7	1,000.00	EACH
0125	02562	TEMPORARY SIGNS	350.00	SQFT
0130	02602	FABRIC-GEOTEXTILE CLASS 1	216.00	SQYD
0135	02650	MAINTAIN & CONTROL TRAFFIC - (KY 588)	1.00	LS
0140	03234	RAILROAD RAILS-DRILLED	1,209.00	LF
0145	03235	EXCAVATION AND BACKFILL	113.00	CUYD
0150	03236	CRIBBING	756.00	SQFT
0160	02569	DEMOBILIZATION	1.00	LS
0165	21415ND	EROSION CONTROL - (KY 588) - ADDED 10-14-25	1.00	LS

CONTRACT ID: 252365

067GR25P087-FD51

MP06711482501

LITTLE COLLEY ROAD (KY 1148) FROM 580 FEET WEST OF HARRISON BRANCH EXTENDING EAST TO 564 FEET WEST OF HANNA DRIVE FLOOD REPAIR FOR FEMA, A DISTANCE OF 1.18 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0165	00001	DGA BASE	46.00	TON
0170	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	16.00	EACH
0175	02187	SITE PREPARATION - (KY 1148)	1.00	EACH
0180	02383	REMOVE & RESET GUARDRAIL	550.00	LF
0185	02483	CHANNEL LINING CLASS II	4.00	TON
0190	02484	CHANNEL LINING CLASS III	16.00	TON
0195	02562	TEMPORARY SIGNS	350.00	SQFT
0200	02602	FABRIC-GEOTEXTILE CLASS 1	475.00	SQYD
0205	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1148)	1.00	LS
0210	03234	RAILROAD RAILS-DRILLED	2,886.00	LF
0215	03235	EXCAVATION AND BACKFILL	212.00	CUYD
0220	03236	CRIBBING	1,410.00	SQFT
0225	21415ND	EROSION CONTROL - (KY 1148)	1.00	LS
0230	21554EN	EXCAVATION	6.00	CUYD
0235	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252365

067GR25P087-FD51

MP06714102501

AIRPORT ROAD (KY 1410) FROM 443 FEET WEST OF LOGAN DRIVE EXTENDING EAST TO CAMP FORK ROAD
FLOOD REPAIR FOR FEMA, A DISTANCE OF .67 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0240	00001	DGA BASE	30.00	TON
0245	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	11.00	EACH
0250	02187	SITE PREPARATION - (KY 1410)	1.00	EACH
0255	02351	GUARDRAIL-STEEL W BEAM-S FACE	187.50	LF
0260	02371	GUARDRAIL END TREATMENT TYPE 7	4.00	EACH
0265	02383	REMOVE & RESET GUARDRAIL	187.50	LF
0270	02483	CHANNEL LINING CLASS II	3.00	TON
0275	02484	CHANNEL LINING CLASS III	11.00	TON
0280	02562	TEMPORARY SIGNS	350.00	SQFT
0285	02602	FABRIC-GEOTEXTILE CLASS 1	740.00	SQYD
0290	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1410)	1.00	LS
0295	03234	RAILROAD RAILS-DRILLED	3,003.00	LF
0300	03235	EXCAVATION AND BACKFILL	400.00	CUYD
0305	03236	CRIBBING	2,691.00	SQFT
0310	21415ND	EROSION CONTROL - (KY 1410)	1.00	LS
0315	21554EN	EXCAVATION	3.00	CUYD
0320	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252365

067GR25P087-FD51

MP06718112501

SMOOT CREEK ROAD (KY 1811) FROM 280 FEET NORTH OF KY 15 EXTENDING NORTH TO 549 FEET SOUTH OF KY 1148 FLOOD REPAIR FOR FEMA, A DISTANCE OF 2.66 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0325	00001	DGA BASE	42.00	TON
0330	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	10.00	EACH
0335	02187	SITE PREPARATION - (KY 1811)	1.00	EACH
0340	02351	GUARDRAIL-STEEL W BEAM-S FACE	125.00	LF
0345	02371	GUARDRAIL END TREATMENT TYPE 7	3.00	EACH
0350	02383	REMOVE & RESET GUARDRAIL	175.00	LF
0355	02396	REMOVE GUARDRAIL END TREATMENT - (TYPE 7)	1.00	EACH
0360	02483	CHANNEL LINING CLASS II	16.00	TON
0365	02484	CHANNEL LINING CLASS III	62.00	TON
0370	02562	TEMPORARY SIGNS	350.00	SQFT
0375	02602	FABRIC-GEOTEXTILE CLASS 1	644.00	SQYD
0380	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1811)	1.00	LS
0385	03234	RAILROAD RAILS-DRILLED	2,613.00	LF
0390	03235	EXCAVATION AND BACKFILL	263.00	CUYD
0395	03236	CRIBBING	1,758.00	SQFT
0400	21415ND	EROSION CONTROL - (KY 1811)	1.00	LS
0405	21554EN	EXCAVATION	24.00	CUYD
0410	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252365

067GR25P087-FD51

MP06720342501

CRAFTS COLLEY ROAD (KY 2034) FROM 195 FEET SOUTH OF RASPBERRY ROAD EXTENDING NORTH TO 0.267 MILES SOUTH OF MAGNOLIA ROAD FLOOD REPAIR FOR FEMA, A DISTANCE OF 2.17 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0415	00001	DGA BASE	36.00	TON
0420	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	11.00	EACH
0425	02187	SITE PREPARATION - (KY 2034)	1.00	EACH
0430	02351	GUARDRAIL-STEEL W BEAM-S FACE	50.00	LF
0435	02371	GUARDRAIL END TREATMENT TYPE 7	2.00	EACH
0440	02383	REMOVE & RESET GUARDRAIL	275.00	LF
0445	02483	CHANNEL LINING CLASS II	17.00	TON
0450	02484	CHANNEL LINING CLASS III	70.00	TON
0455	02562	TEMPORARY SIGNS	350.00	SQFT
0460	02602	FABRIC-GEOTEXTILE CLASS 1	558.00	SQYD
0465	02650	MAINTAIN & CONTROL TRAFFIC - (KY 2034)	1.00	LS
0470	03234	RAILROAD RAILS-DRILLED	2,613.00	LF
0475	03235	EXCAVATION AND BACKFILL	223.00	CUYD
0480	03236	CRIBBING	1,484.00	SQFT
0485	21415ND	EROSION CONTROL - (KY 2034)	1.00	LS
0490	21554EN	EXCAVATION	27.00	CUYD
0495	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 252365

067GR25P087-FD51

MP06720352501

LITTLE COWAN ROAD (KY 2035) FROM 549 FEET EAST OF EDRIE DRIVE EXTENDING EAST TO 0.258 MILES WEST OF DUCE DRIVE FLOOD REPAIR FOR FEMA, A DISTANCE OF 2.26 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0500	00001	DGA BASE	96.00	TON
0505	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	6.00	EACH
0510	02187	SITE PREPARATION - (KY 2035)	1.00	EACH
0515	02351	GUARDRAIL-STEEL W BEAM-S FACE	162.50	LF
0520	02371	GUARDRAIL END TREATMENT TYPE 7	4.00	EACH
0525	02483	CHANNEL LINING CLASS II	116.00	TON
0530	02484	CHANNEL LINING CLASS III	464.00	TON
0535	02562	TEMPORARY SIGNS	350.00	SQFT
0540	02602	FABRIC-GEOTEXTILE CLASS 1	558.00	SQYD
0545	02650	MAINTAIN & CONTROL TRAFFIC - (KY 2035)	1.00	LS
0550	03234	RAILROAD RAILS-DRILLED	1,365.00	LF
0555	03235	EXCAVATION AND BACKFILL	88.00	CUYD
0560	03236	CRIBBING	585.00	SQFT
0565	21415ND	EROSION CONTROL - (KY 2035)	1.00	LS
0570	21554EN	EXCAVATION	175.00	CUYD
0575	02569	DEMOBILIZATION	1.00	LS

252365

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	307.00	TON		\$	
0020	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	66.00	EACH		\$	
0030	02187		SITE PREPARATION (KY 1148)	1.00	EACH		\$	
0040	02187		SITE PREPARATION (KY 1410)	1.00	EACH		\$	
0050	02187		SITE PREPARATION (KY 1811)	1.00	EACH		\$	
0060	02187		SITE PREPARATION (KY 2034)	1.00	EACH		\$	
0070	02187		SITE PREPARATION (KY 2035)	1.00	EACH		\$	
0080	02187		SITE PREPARATION (KY 343)	1.00	EACH		\$	
0090	02187		SITE PREPARATION (KY 588)	1.00	EACH		\$	
0100	02351		GUARDRAIL-STEEL W BEAM-S FACE	737.50	LF		\$	
0110	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0120	02371		GUARDRAIL END TREATMENT TYPE 7	15.00	EACH		\$	
0130	02383		REMOVE & RESET GUARDRAIL	1,300.00	LF		\$	
0140	02396		REMOVE GUARDRAIL END TREATMENT (TYPE 7)	1.00	EACH		\$	
0150	02396		REMOVE GUARDRAIL END TREATMENT TYPE 7	1,000.00	EACH		\$	
0160	02483		CHANNEL LINING CLASS II	193.00	TON		\$	
0170	02484		CHANNEL LINING CLASS III	766.00	TON		\$	
0180	02562		TEMPORARY SIGNS	2,450.00	SQFT		\$	
0190	02602		FABRIC-GEOTEXTILE CLASS 1	3,716.00	SQYD		\$	
0200	02650		MAINTAIN & CONTROL TRAFFIC (KY 1148)	1.00	LS		\$	
0210	02650		MAINTAIN & CONTROL TRAFFIC (KY 1410)	1.00	LS		\$	
0220	02650		MAINTAIN & CONTROL TRAFFIC (KY 1811)	1.00	LS		\$	
0230	02650		MAINTAIN & CONTROL TRAFFIC (KY 2034)	1.00	LS		\$	
0240	02650		MAINTAIN & CONTROL TRAFFIC (KY 2035)	1.00	LS		\$	
0250	02650		MAINTAIN & CONTROL TRAFFIC (KY 343)	1.00	LS		\$	
0260	02650		MAINTAIN & CONTROL TRAFFIC (KY 588)	1.00	LS		\$	
0270	03234		RAILROAD RAILS-DRILLED	15,015.00	LF		\$	
0280	03235		EXCAVATION AND BACKFILL	1,475.00	CUYD		\$	
0290	03236		CRIBBING	9,872.00	SQFT		\$	
0300	21415ND		EROSION CONTROL (KY 1148)	1.00	LS		\$	
0310	21415ND		EROSION CONTROL (KY 1410)	1.00	LS		\$	

Report Date 10/14/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0320	21415ND		EROSION CONTROL (KY 1811)	1.00	LS		\$	
0330	21415ND		EROSION CONTROL (KY 2034)	1.00	LS		\$	
0340	21415ND		EROSION CONTROL (KY 2035)	1.00	LS		\$	
0345	21415ND		EROSION CONTROL (KY 588) - ADDED 10-14-25	1.00	LS		\$	
0350	21415ND		EROSION CONTROL (KY 343) - REVISED 10-14-25	1.00	LS		\$	
0360	21554EN		EXCAVATION	289.00	CUYD		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0370	02569		DEMOBILIZATION	1.00	LS		\$	