



Andy Beshear  
GOVERNOR

## TRANSPORTATION CABINET

200 Mero Street  
Frankfort, Kentucky 40601

Jim Gray  
SECRETARY

August 21, 2023

CALL NO. 406  
CONTRACT ID NO. 232902  
ADDENDUM # 1

Subject: Nelson County, 090GR23M026  
Letting August 24, 2023

- (1) Revised - Dates - Pages 4 and 21 of 61
- (2) Revised - Notes - Page 23 of 61
- (3) Revised - Material Summary - Pages 37-39 of 61
- (4) Revised - Proposal Bid Items - Page 61 of 61

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

### ADMINISTRATIVE DISTRICT - 04

**CONTRACT ID - 232902**

**090GR23M026**

**COUNTY - NELSON**

**PCN - MB09000482301**

**FE02 090 0048 B00004N 02.00**

Highgrove Road (KY 48) BRIDGE 090B00004N OVER WEST FORK SIMPSON CREEK AT MP 02.00BRIDGE DECK RESTORATION & WATERPROOFING

GEOGRAPHIC COORDINATES LATITUDE 37:55:23.00 LONGITUDE 85:21:13.00

ADT

**PCN - MB09006052301**

**FE02 090 0605 B00086N 01.50**

WOODLAWN ROAD (KY 605) BRIDGE 090B00086N OVER BLUE GRASS PARKWAY AT MP 01.50BRIDGE DECK RESTORATION & WATERPROOFING

GEOGRAPHIC COORDINATES LATITUDE 37:49:07.00 LONGITUDE 85:23:50.00

ADT

**PCN - MB09018582301**

**FE02 090 1858 B00093N 00.10**

STRINGTOWN ROAD (KY 1858) BRIDGE 090B00093N OVER BLUE GRASS PARKWAY AT MP 00.22BRIDGE DECK RESTORATION & WATERPROOFING

GEOGRAPHIC COORDINATES LATITUDE 37:50:20.00 LONGITUDE 85:22:09.00

ADT

**COMPLETION DATE(S):**

COMPLETED BY 07/01/2024

30 CALENDAR Days

30 CALENDAR Days

20 CALENDAR Days

APPLIES TO ENTIRE CONTRACT

APPLIES TO 090B00004N

APPLIES TO 090B00086N

APPLIES TO 090B00093N

by the date listed below. An allotted number of Calendar days are assigned to each structure in this contract as shown below.

<u>STRUCTURE</u>	<u>NO. OF CALENDAR DAYS</u>	<u>COMPLETION DATE</u>
090B00004N	30	July 1, 2024
090B00096N	30	July 1, 2024
090B00093N	20	July 1, 2024

Contrary to Section 108.07.03, the Engineer will begin charging calendar days for a structure on the day the Contractor starts work or sets up traffic control on that particular structure. A **penalty of \$500.00 per day** will be assessed when the allotted number of calendar days is exceeded for each structure.

All construction must be completed in accordance with the weather limitations specified in Section 606 and/or Section 601 as applicable. No extension of Contract time will be granted due to inclement weather or temperature limitations that occur due to starting work on the Contract or a structure late in the construction season.

## 6. TEMPORARY SIGNAL

Provide, install, and maintain a temporary traffic signal as specified below. The Contractor must provide a 24-hour contact person and number available to maintain the temporary signals as needed.

<u>Structure</u>	<u>Signal</u>
090B00004N	2 Phase
090B00086N	2 Phase

## 7. DIVERSIONS (BYPASS DETOURS) (090B00093N)

The Contractor shall close the bridge to traffic and construct a detour to maintain traffic. See attached detailed drawing for the suggested detour plan. Once work on the structure begins that impacts traffic, ensure work progresses to minimize the effected time to the public. All materials that must be made specific for the project should be ordered and made prior to closure of the bridge so that delivery does not delay progress of the work until all materials that must be made specific for the project are ordered and made so that use of the detour is minimized. The diversion plan and project schedule shall be submitted as part of the traffic control plan. All cost to close the bridge and provide all detour items shall be included in the bid item for Diversions (Bypass Detours).

## 8. ADDITIONAL LANE CLOSURES. (090B00086N & 090B00093N)

Shoulder, single closures will be permitted on KY 9002 for any necessary work below this structure. The shoulder and lane closures will be determined by the Engineer. All shoulder and lane closures shall be removed when not working. All cost shall be considered incidental to the lump sum bid for Maintain and Control Traffic.

## 9. MEASUREMENT.

### **Temporary Signs:**

The Cabinet will measure this item by "Square Feet".

### **Maintain and Control Traffic and Diversion (Bypass Detours):**

The Cabinet will measure this item by "Lump Sum".

### **Lane Closure, and Temp Signal 2 Phase:**

The Cabinet will measure this item by "Each".

### **Pave Striping-Temp Rem Tape-B, W, and Y:**

The Department will measure the quantity in "Linear Feet".

## 10. PAYMENT.

### **Temporary Signs (02562):**

Payment at the contract unit price for "Square Feet" is full compensation for all items to complete this work as specified.

### **Maintain and Control Traffic (02650) and Diversions (Bypass Detours) (02671):**

Payment at the contract unit price for "Lump Sum" is full compensation for all items to complete this work as specified.

### **Lane Closure (02653) and Temp Signal 2 Phase (04933):**

# MATERIAL SUMMARY

**CONTRACT ID: 232902**

**090GR23M026**

**MB09000482301**

Highgrove Road (KY 48) BRIDGE 090B00004N OVER WEST FORK SIMPSON CREEK AT MP 02.00 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02562	TEMPORARY SIGNS	145.00	SQFT
0010	02650	MAINTAIN & CONTROL TRAFFIC - - APPLIES TO 090B00004N	1.00	LS
0015	02653	LANE CLOSURE	2.00	EACH
0020	03299	ARMORED EDGE FOR CONCRETE	70.00	LF
0025	03300	ELIMINATE TRANSVERSE JOINT	77.00	LF
0030	03304	BRIDGE OVERLAY APPROACH PAVEMENT	334.00	SQYD
0035	04933	TEMP SIGNAL 2 PHASE	1.00	EACH
0040	06514	PAVE STRIPING-PERM PAINT-4 IN	488.00	LF
0045	06549	PAVE STRIPING-TEMP REM TAPE-B	1,000.00	LF
0050	06550	PAVE STRIPING-TEMP REM TAPE-W	2,000.00	LF
0055	06551	PAVE STRIPING-TEMP REM TAPE-Y	2,000.00	LF
0060	08150	STEEL REINFORCEMENT	789.00	LB
0065	08504	EPOXY SAND SLURRY	107.00	SQYD
0070	08510	REM EPOXY BIT FOREIGN OVERLAY	480.00	SQYD
0075	08526	CONC CLASS M FULL DEPTH PATCH	1.00	CUYD
0080	08534	CONCRETE OVERLAY-LATEX	20.00	CUYD
0085	08549	BLAST CLEANING	896.00	SQYD
0090	24094EC	PARTIAL DEPTH PATCHING	15.00	CUYD
0095	24692EC	DECK DRAIN RETROFIT	18.00	EACH
0100	02569	DEMOBILIZATION	1.00	LS

# MATERIAL SUMMARY

**CONTRACT ID: 232902**

**090GR23M026**

**MB09006052301**

WOODLAWN ROAD (KY 605) BRIDGE 090B00086N OVER BLUE GRASS PARKWAY AT MP 01.50 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0105	02562	TEMPORARY SIGNS	145.00	SQFT
0110	02650	MAINTAIN & CONTROL TRAFFIC - - APPLIES TO 090B00086N	1.00	LS
0115	02653	LANE CLOSURE	2.00	EACH
0120	03293	EXPAN JOINT REPLACE 1 IN	33.00	LF
0125	03298	EXPAN JOINT REPLACE 4 IN	66.00	LF
0130	03299	ARMORED EDGE FOR CONCRETE	66.00	LF
0135	03304	BRIDGE OVERLAY APPROACH PAVEMENT	578.00	SQYD
0140	04933	TEMP SIGNAL 2 PHASE	1.00	EACH
0145	06514	PAVE STRIPING-PERM PAINT-4 IN	1,688.00	LF
0150	06549	PAVE STRIPING-TEMP REM TAPE-B	1,000.00	LF
0155	06550	PAVE STRIPING-TEMP REM TAPE-W	2,000.00	LF
0160	06551	PAVE STRIPING-TEMP REM TAPE-Y	2,000.00	LF
0165	08150	STEEL REINFORCEMENT	270.00	LB
0170	08504	EPOXY SAND SLURRY	164.00	SQYD
0175	08526	CONC CLASS M FULL DEPTH PATCH	1.00	CUYD
0180	08534	CONCRETE OVERLAY-LATEX (REVISED 8-21-2023)	26.60	CUYD
0185	08549	BLAST CLEANING	803.00	SQYD
0190	08551	MACHINE PREP OF SLAB	639.00	SQYD
0195	24094EC	PARTIAL DEPTH PATCHING	20.00	CUYD
0200	24981EC	BRIDGE CLEANING - - APPLIES TO 090B00086N	1.00	LS
0205	24982EC	CONCRETE COATING - - APPLIES TO 090B00086N	1.00	LS
0210	24983EC	BEARING LUBRICATION	8.00	EACH
0215	02569	DEMOBILIZATION	1.00	LS

# MATERIAL SUMMARY

**CONTRACT ID: 232902**

**090GR23M026**

**MB09018582301**

STRINGTOWN ROAD (KY 1858) BRIDGE 090B00093N OVER BLUE GRASS PARKWAY AT MP 00.22 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0220	02650	MAINTAIN & CONTROL TRAFFIC - - APPLIES TO 090B00093N	1.00	LS
0225	02651	DIVERSIONS (BY-PASS DETOURS) - - APPLIES TO 090B00093N	1.00	LS
0230	03295	EXPAN JOINT REPLACE 2 IN	26.00	LF
0235	03299	ARMORED EDGE FOR CONCRETE	52.00	LF
0240	03300	ELIMINATE TRANSVERSE JOINT	52.00	LF
0245	03304	BRIDGE OVERLAY APPROACH PAVEMENT	578.00	SQYD
0250	06514	PAVE STRIPING-PERM PAINT-4 IN	792.00	LF
0255	08150	STEEL REINFORCEMENT	813.00	LB
0260	08504	EPOXY SAND SLURRY	146.00	SQYD
0265	08526	CONC CLASS M FULL DEPTH PATCH	5.00	CUYD
0270	08534	CONCRETE OVERLAY-LATEX (REVISED 8-21-23)	27.20	CUYD
0275	08549	BLAST CLEANING	712.00	SQYD
0280	08551	MACHINE PREP OF SLAB	567.00	SQYD
0285	24094EC	PARTIAL DEPTH PATCHING	15.00	CUYD
0290	02569	DEMOBILIZATION	1.00	LS

## PROPOSAL BID ITEMS

Report Date 8/21/23

### Section: 0001 - BRIDGES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	02562		TEMPORARY SIGNS	290.00	SQFT		\$	
0020	02650		MAINTAIN & CONTROL TRAFFIC - APPLIES TO 090B00004N	1.00	LS		\$	
0030	02650		MAINTAIN & CONTROL TRAFFIC - APPLIES TO 090B00086N	1.00	LS		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC - APPLIES TO 090B00093N	1.00	LS		\$	
0050	02651		DIVERSIONS (BY-PASS DETOURS) - APPLIES TO 090B00093N	1.00	LS		\$	
0060	02653		LANE CLOSURE	4.00	EACH		\$	
0070	03293		EXPAN JOINT REPLACE 1 IN	33.00	LF		\$	
0080	03295		EXPAN JOINT REPLACE 2 IN	26.00	LF		\$	
0090	03298		EXPAN JOINT REPLACE 4 IN	66.00	LF		\$	
0100	03299		ARMORED EDGE FOR CONCRETE	188.00	LF		\$	
0110	03300		ELIMINATE TRANSVERSE JOINT	129.00	LF		\$	
0120	03304		BRIDGE OVERLAY APPROACH PAVEMENT	1,490.00	SQYD		\$	
0130	04933		TEMP SIGNAL 2 PHASE	2.00	EACH		\$	
0140	06514		PAVE STRIPING-PERM PAINT-4 IN	2,968.00	LF		\$	
0150	06549		PAVE STRIPING-TEMP REM TAPE-B	2,000.00	LF		\$	
0160	06550		PAVE STRIPING-TEMP REM TAPE-W	4,000.00	LF		\$	
0170	06551		PAVE STRIPING-TEMP REM TAPE-Y	4,000.00	LF		\$	
0180	08150		STEEL REINFORCEMENT	1,872.00	LB		\$	
0190	08504		EPOXY SAND SLURRY	417.00	SQYD		\$	
0200	08510		REM EPOXY BIT FOREIGN OVERLAY	480.00	SQYD		\$	
0210	08526		CONC CLASS M FULL DEPTH PATCH	7.00	CUYD		\$	
0220	08534		CONCRETE OVERLAY-LATEX (REVISED 8-21-2023)	73.80	CUYD		\$	
0230	08549		BLAST CLEANING	2,411.00	SQYD		\$	
0240	08551		MACHINE PREP OF SLAB	1,206.00	SQYD		\$	
0250	24094EC		PARTIAL DEPTH PATCHING	50.00	CUYD		\$	
0260	24692EC		DECK DRAIN RETROFIT	18.00	EACH		\$	
0270	24981EC		BRIDGE CLEANING - APPLIES TO 090B00086N	1.00	LS		\$	
0280	24982EC		CONCRETE COATING - APPLIES TO 090B00086N	1.00	LS		\$	
0290	24983EC		BEARING LUBRICATION	8.00	EACH		\$	

### Section: 0002 - DEMOB

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0300	02569		DEMOBILIZATION	1.00	LS		\$	