



**COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Matthew G. Bevin**  
Governor

**Greg Thomas**  
Secretary

February 19, 2019

CALL NO. 406  
CONTRACT ID NO. 192058  
ADDENDUM # 1

Subject: WHITLEY COUNTY, 118GR19P010-FE06  
Letting February 22, 2019

- (1) Revised - Special Notes for Guardrail - Page 13 of 55
- (2) Revised - Material Summary - Page 27 of 55
- (3) Revised - Proposal Bid Items - Page 55 of 55

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures



An Equal Opportunity Employer M/F/D

**SPECIAL NOTES FOR GUARDRAIL**  
**FE06 118 0006 000-002**  
**FE06 118 1804 000-001**

---

**I. DESCRIPTION**

Except as specified herein, perform all work in accordance with the Department's 2012 Standard and Supplemental Specifications and Standard and Sepia Drawings, current editions. Article references are to the Standard Specifications.

Furnish all equipment, labor, materials, and incidentals for the following work items:

(1) Site and Shoulder Preparation; (2) Install Guardrail furnished by the Department; (3) Install Extra Length Posts and Cribbing furnished by the Department; (4) Furnish and install End Treatments, and Terminal Sections, as applicable; (5) Furnish and Install Delineators for Guardrail; (4) Maintain and Control Traffic; and (5) all other work specified as part of this contract.

**II. MATERIALS**

Except as specified herein, provide for all materials to be sampled and tested in accordance with the Department's Sampling Manual, and make the materials available for sampling a sufficient time in advance of the use of the materials to allow for the necessary time for testing.

**A Maintain and Control Traffic.** See Traffic Control Plan.

**B. Erosion Control.** See Special Note for Erosion Control.

**C. Dense Graded Aggregate.** Furnish Dense Graded Aggregate (DGA) according to Section 312, no alternate. Do not furnish Crushed Stone Base in lieu of DGA.

**D. Guardrail.** The Department will furnish guardrail elements and radius rail, steel posts, approximately 500 extra length (9 foot) steel posts, and off set blocks in general conformance to Section 814 and the Standard Drawings, but may vary in some respects, such as gage, pre-punched hole patterns, etc. The Department will make the materials available to the Contractor at the Bailey Bridge Lot in Frankfort, KY between the hours of 8:00 a.m. and 3:30 p.m. Monday through Friday. Determine curvature of radius rail for entrances and terminal sections and provide the Engineer a list of requirements fourteen (14) calendar days prior to beginning work. Punch additional post bolt slots as required in guardrail and paint with two (2) coats of zinc dust-zinc oxide paint conforming to Federal Specification TT-P641.

The Contractor shall furnish guardrail hardware (nuts, bolts, and washers), end treatments, and terminal sections in accordance with the Sepia and Standard Drawings.

**E. Cribbing.** The Department will furnish used guardrail elements for Cribbing. The

# MATERIAL SUMMARY

**CONTRACT ID: 192058**

**118GR19P010-FE06**

**MP11800061901**

BARBOURVILLE ROAD FROM 512 FEET EAST OF KY 1064 EXTENDING EAST TO 2,017 FEET WEST OF ELLIOT HOLLOW ROAD GUARDRAIL, A DISTANCE OF .34 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02562	TEMPORARY SIGNS	150.00	SQFT
0010	02650	MAINTAIN & CONTROL TRAFFIC - (KY 6)	1.00	LS
0015	02360	GUARDRAIL TERMINAL SECTION NO 1	5.00	EACH
0020	02373	GUARDRAIL END TREATMENT TYPE 3	1.00	EACH
0025	02371	GUARDRAIL END TREATMENT TYPE 7	2.00	EACH
0030	02353	INSTALL GUARDRAIL-STEEL W BM-S FACE	2,587.50	LF
0035	03236	CRIBBING - (REVISED: 2-19-19)	8,000.00	SQFT
0040	00001	DGA BASE - (REVISED: 2-19-19)	1,000.00	TON
0045	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	50.00	EACH
0050	02569	DEMOBILIZATION	1.00	LS

**CONTRACT ID: 192058**

**118GR19P010-FE06**

**MP11818041901**

HIGHWAY 1804 FROM 227 FEET EAST OF US 25W EXTENDING EAST TO 1,389 FEET WEST OF RAILROAD CROSSING GUARDRAIL, A DISTANCE OF .25 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0055	00001	DGA BASE	75.00	TON
0060	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	26.00	EACH
0065	02353	INSTALL GUARDRAIL-STEEL W BM-S FACE	1,300.00	LF
0070	02360	GUARDRAIL TERMINAL SECTION NO 1	1.00	EACH
0075	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
0080	02562	TEMPORARY SIGNS	190.00	SQFT
0085	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1804)	1.00	LS
0090	02569	DEMOBILIZATION	1.00	LS

**PROPOSAL BID ITEMS**

192058

Page 1 of 1

Report Date 2/19/19

**Section: 0001 - GUARDRAIL**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE (REVISED: 2-19-19)	1,075.00	TON		\$	
0020	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	76.00	EACH		\$	
0030	02353		INSTALL GUARDRAIL-STEEL W BM-S FACE	3,887.50	LF		\$	
0040	02360		GUARDRAIL TERMINAL SECTION NO 1	6.00	EACH		\$	
0050	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0060	02371		GUARDRAIL END TREATMENT TYPE 7	2.00	EACH		\$	
0070	02373		GUARDRAIL END TREATMENT TYPE 3	1.00	EACH		\$	
0080	02562		TEMPORARY SIGNS	340.00	SQFT		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC (KY 1804)	1.00	LS		\$	
0100	02650		MAINTAIN & CONTROL TRAFFIC (KY 6)	1.00	LS		\$	
0110	03236		CRIBBING (REVISED: 2-19-19)	8,000.00	SQFT		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0120	02569		DEMOBILIZATION	1.00	LS		\$	