



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

November 12, 2025

CALL NO. 408
CONTRACT ID NO. 253135
ADDENDUM # 1

Subject: Laurel County, 063GR25R067-CB06
Letting November 20, 2025

(1) Revised - Summary Sheets - Pages 38-43 of 57

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

Mile Point	Notes	Length	Width	Avg Depth	Tons
10.951	Beginning edge key for the resurfacing project.	100	20	0.5	6.1
12.848	Edge key on the East side of the intersection with KY-472.	100	20	0.5	6.1
12.848	Edge key on the West side of the intersection with KY-472.	100	20	0.5	6.1
13.042	Ending edge key for the resurfacing project.	100	20	0.5	6.1
				Total:	24.4

Milepoint	Location	Notes	PAVE MARKIN G- THERMO STOP BAR-24IN
12.848	KY-472	New 24" Thermo Stop Bar on the East side of KY-638 at the intersection with KY-472 measured at 11.00 LF.	11
12.848	KY-472	New 24" Thermo Stop Bar on the West side of KY-638 at the intersection with KY-472 measured at 14.00 LF.	14
Total:			25

Mile Point	Notes	Length	Width	Avg Depth	Tons
4.353	Beginning edge key for the resurfacing project. Milling operation was extended from 100 feet to 430 feet to correct the existing pavement slippage in the WB lane heading towards the stop sign at the intersection with KY-2392.	430	20	0.5	26.3
8.034	Ending edge key for the resurfacing project.	100	20	0.5	6.1
	Bridge Milling				
				Total:	32.4

Project: CB06 063
1223 004-009

County: Laurel

District: D11 - Manchester

Milepoint	Location	Notes	PAVE MARKIN G- THERMO STOP BAR-24IN
4.353	KY-2392	New 24" Thermo Stop Bar on KY-1223 at the intersection with KY-2392 measured at 12.00 LF.	12
8.034	Hopkins Cemetery Road/ McClure Bridge Road	New 24" Thermo Stop Bar on KY-1223 at the intersection with Hopkins Cemetery Road and McClure Bridge Road measured at 14.00 LF.	14
Total:			26

Mile Point	Notes	Length	Width	Avg Depth	Tons
0.000	Beginning edge key for the resurfacing project. Milling operation was extended from 100 feet to 320 feet to correct the existing pavement slippage in the SB lane heading towards the stop sign at the intersection with US-25W.	320	22	0.5	21.5
0.534	Ending edge key for the resurfacing project.	100	22	0.5	6.7
				Total:	28.2

Milepoint	Location	Notes	PAVE MARKIN G- THERMO STOP BAR-24IN
0.000	US-25W	New 24" Thermo Stop Bar on KY-3431 at the intersection with US-25W measured at 13.00 LF.	13
0.503	KY-1223	New 24" Thermo Stop Bar on KY-1223 at the intersection with KY-3431 measured at 12.00 LF.	12
Total:			25