



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

June 14, 2023

CALL NO. 408
CONTRACT ID NO. 233062
ADDENDUM # 2

Subject: Morgan County, 088GR22R102-CB06

Letting June 22, 2023

- (1) Revised - Material Summary P. 27-29 of 59
- (2) Revised - Summary Sheets P. 36, 37, & 39 of 59
- (3) Revised - Proposal Bid Items P. 59 of 59

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:so
Enclosures

MATERIAL SUMMARY

CONTRACT ID: 233062

088GR22R102-CB06

1008807723301

KY 711 (KY 711) FROM DEVILS FORK RD (CR 1333), 0.013 MILES SOUTH, EXTENDING NORTH 0.12 MILES NORTH OF BLAZE RD (CR 3420). ASPHALT RESURFACING, A DISTANCE OF .86 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	150.00	TON
0010	00212	CL2 ASPH BASE 1.00D PG64-22	107.00	TON
0015	00301	CL2 ASPH SURF 0.38D PG64-22	615.00	TON
0020	00356	ASPHALT MATERIAL FOR TACK	4.00	TON
0025	02562	TEMPORARY SIGNS	255.00	SQFT
0030	02650	MAINTAIN & CONTROL TRAFFIC - (KY 711)	1.00	LS
0035	02676	MOBILIZATION FOR MILL & TEXT - (KY 711)	1.00	LS
0040	02677	ASPHALT PAVE MILLING & TEXTURING	190.00	TON
0045	06510	PAVE STRIPING-TEMP PAINT-4 IN	6,000.00	LF
0050	06514	PAVE STRIPING-PERM PAINT-4 IN	9,100.00	LF
0055	10020NS	FUEL ADJUSTMENT	1,357.00	DOLL
0060	10030NS	ASPHALT ADJUSTMENT	3,409.00	DOLL
0065	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 233062

088GR22R102-CB06

1008810022301

KY 1002 (KY 1002) FROM PATRICK ROAD (CR 1444), 0.007 MILES NORTH, EXTENDING NORTH 0.071 MILES PAST ANGLE CEMETERY RD (CR 1327) ASPHALT RESURFACING, A DISTANCE OF 1.49 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0070	00190	LEVELING & WEDGING PG64-22	265.00	TON
0075	00212	CL2 ASPH BASE 1.00D PG64-22	132.00	TON
0080	00301	CL2 ASPH SURF 0.38D PG64-22	1,105.00	TON
0085	00356	ASPHALT MATERIAL FOR TACK	7.00	TON
0090	02562	TEMPORARY SIGNS	175.00	SQFT
0095	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1002)	1.00	LS
0100	02676	MOBILIZATION FOR MILL & TEXT - (KY 1002)	1.00	LS
0105	02677	ASPHALT PAVE MILLING & TEXTURING	160.00	TON
0110	06510	PAVE STRIPING-TEMP PAINT-4 IN	15,700.00	LF
0115	06514	PAVE STRIPING-PERM PAINT-4 IN	15,700.00	LF
0120	10020NS	FUEL ADJUSTMENT	2,338.00	DOLL
0125	10030NS	ASPHALT ADJUSTMENT	5,872.00	DOLL
0130	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 233062

088GR22R102-CB06

1008810102301

KY 1010 (KY 1010) FROM BLACKWATER RD (CR 1247), NORTH 0.067 MILES, EXTENDING NORTH TO US 460 W. ASPHALT RESURFACING, A DISTANCE OF 1.64 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0135	00190	LEVELING & WEDGING PG64-22	270.00	TON
0140	00212	CL2 ASPH BASE 1.00D PG64-22	126.00	TON
0145	00301	CL2 ASPH SURF 0.38D PG64-22	1,140.00	TON
0150	00356	ASPHALT MATERIAL FOR TACK	8.00	TON
0155	02562	TEMPORARY SIGNS	200.00	SQFT
0160	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1010)	1.00	LS
0165	02676	MOBILIZATION FOR MILL & TEXT - (KY 1010)	1.00	LS
0170	02677	ASPHALT PAVE MILLING & TEXTURING	150.00	TON
0175	06510	PAVE STRIPING-TEMP PAINT-4 IN	12,000.00	LF
0180	06514	PAVE STRIPING-PERM PAINT-4 IN	17,300.00	LF
0185	10020NS	FUEL ADJUSTMENT	2,391.00	DOLL
0190	10030NS	ASPHALT ADJUSTMENT	6,005.00	DOLL
0195	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 233062

088GR22R102-CB06

1008820272301

KY 2027 (KY 2027) FROM WOLFE COUNTY LINE, EXTENDING EAST TO KY 1010. ASPHALT RESURFACING, A DISTANCE OF .53 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0200	00190	LEVELING & WEDGING PG64-22	85.00	TON
0205	00212	CL2 ASPH BASE 1.00D PG64-22 REVISED 6-14-23	155.00	TON
0210	00301	CL2 ASPH SURF 0.38D PG64-22	330.00	TON
0215	00356	ASPHALT MATERIAL FOR TACK	3.00	TON
0220	02562	TEMPORARY SIGNS	175.00	SQFT
0225	02650	MAINTAIN & CONTROL TRAFFIC - (KY 2027)	1.00	LS
0230	02676	MOBILIZATION FOR MILL & TEXT - (KY 2027)	1.00	LS
0235	02677	ASPHALT PAVE MILLING & TEXTURING REVISED 6-14-23	155.00	TON
0240	06510	PAVE STRIPING-TEMP PAINT-4 IN	5,800.00	LF
0245	06514	PAVE STRIPING-PERM PAINT-4 IN	5,800.00	LF
0250	10020NS	FUEL ADJUSTMENT	833.00	DOLL
0255	10030NS	ASPHALT ADJUSTMENT	2,092.00	DOLL
0260	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 233062

088GR22R102-CB06

1008830362301

KY 3036 (KY 3036) FROM HICKORY RD (CR 1446), EXTENDING EAST 0.132 MILES SOUTH OF BLEVINS RD (CR 1411). ASPHALT RESURFACING, A DISTANCE OF .43 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0265	00190	LEVELING & WEDGING PG64-22	70.00	TON
0270	00212	CL2 ASPH BASE 1.00D PG64-22	125.00	TON
0275	00301	CL2 ASPH SURF 0.38D PG64-22	280.00	TON
0280	00356	ASPHALT MATERIAL FOR TACK	2.00	TON
0285	02562	TEMPORARY SIGNS	170.00	SQFT
0290	02650	MAINTAIN & CONTROL TRAFFIC - (KY 3036)	1.00	LS
0295	02676	MOBILIZATION FOR MILL & TEXT - (KY 3036)	1.00	LS
0300	02677	ASPHALT PAVE MILLING & TEXTURING	150.00	TON
0305	06510	PAVE STRIPING-TEMP PAINT-4 IN	3,200.00	LF
0310	06514	PAVE STRIPING-PERM PAINT-4 IN	4,600.00	LF
0315	10020NS	FUEL ADJUSTMENT	739.00	DOLL
0320	10030NS	ASPHALT ADJUSTMENT	1,857.00	DOLL
0325	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 233062

088GR22R102-CB06

1008834202301

KY 3420 (KY 3420) FROM LEWIS CEMETERY NO 1 RD (CR 1367), EAST 0.198 MILES, EXTENDING NORTH 0.333 NORTH OF PLEASANT RUN RD (CR 1322). ASPHALT RESURFACING, A DISTANCE OF .76 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0330	00190	LEVELING & WEDGING PG64-22	115.00	TON
0335	00212	CL2 ASPH BASE 1.00D PG64-22	83.00	TON
0340	00301	CL2 ASPH SURF 0.38D PG64-22	460.00	TON
0345	00356	ASPHALT MATERIAL FOR TACK	3.00	TON
0350	02562	TEMPORARY SIGNS	175.00	SQFT
0355	02650	MAINTAIN & CONTROL TRAFFIC - (KY 3420)	1.00	LS
0360	02677	ASPHALT PAVE MILLING & TEXTURING	95.00	TON
0365	06510	PAVE STRIPING-TEMP PAINT-4 IN	6,000.00	LF
0370	06514	PAVE STRIPING-PERM PAINT-4 IN	8,100.00	LF
0375	10020NS	FUEL ADJUSTMENT	1,024.00	DOLL
0380	10030NS	ASPHALT ADJUSTMENT	2,573.00	DOLL
0385	02569	DEMOBILIZATION	1.00	LS
0390	02676	MOBILIZATION FOR MILL & TEXT - (KY 3420) REVISED 6-6-2023	1.00	LS

Base Failure Summary Sheet

Project: CB06 088
2027 000-001

County: Morgan

District: D10 - Jackson

Direction	Milepoint	Length (ft)	Width (ft)	Assumed Depth (in)	Total Sq. Yards	NoBid Item
North Bound	0.281	450	7	4	350	0
Total:					350	0

Milling Summary Sheet

Project: CB06 088
2027 000-001

County: Morgan

District: D10 - Jackson

Mile Point	Notes	Length	Width	Avg Depth	Tons
0.000	Base failures	450	7	4	131
0.000	Edge Key	100	18	1	11
0.532	Edge Key	100	20	1	13
				Total:	155

Milling Summary Sheet

Project: CB06 088
3036 000-003

County: Morgan

District: D10 - Jackson

Mile Point	Notes	Length	Width	Avg Depth	Tons
0.000	Edge Key	100	18	1	11
1.400	Base Failures	850	6	4	124.9
2.250	Edge Key	100	20	1	12.2
				Total:	148.1

PROPOSAL BID ITEMS

Report Date 6/14/23

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	955.00	TON		\$	
0020	00212		CL2 ASPH BASE 1.00D PG64-22 REVISED 6-14-23	728.00	TON		\$	
0030	00301		CL2 ASPH SURF 0.38D PG64-22	3,930.00	TON		\$	
0040	00356		ASPHALT MATERIAL FOR TACK	27.00	TON		\$	
0050	02562		TEMPORARY SIGNS	1,150.00	SQFT		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC (KY 1002)	1.00	LS		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC (KY 1010)	1.00	LS		\$	
0080	02650		MAINTAIN & CONTROL TRAFFIC (KY 2027)	1.00	LS		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC (KY 3036)	1.00	LS		\$	
0100	02650		MAINTAIN & CONTROL TRAFFIC (KY 3420)	1.00	LS		\$	
0110	02650		MAINTAIN & CONTROL TRAFFIC (KY 711)	1.00	LS		\$	
0120	02676		MOBILIZATION FOR MILL & TEXT (KY 1002)	1.00	LS		\$	
0130	02676		MOBILIZATION FOR MILL & TEXT (KY 1010)	1.00	LS		\$	
0140	02676		MOBILIZATION FOR MILL & TEXT (KY 2027)	1.00	LS		\$	
0150	02676		MOBILIZATION FOR MILL & TEXT (KY 3036)	1.00	LS		\$	
0155	02676		MOBILIZATION FOR MILL & TEXT (KY 3420) REVISED 6-6-2023	1.00	LS		\$	
0160	02676		MOBILIZATION FOR MILL & TEXT (KY 711)	1.00	LS		\$	
0170	02677		ASPHALT PAVE MILLING & TEXTURING REV 6-14-23	900.00	TON		\$	
0180	06510		PAVE STRIPING-TEMP PAINT-4 IN	48,700.00	LF		\$	
0190	06514		PAVE STRIPING-PERM PAINT-4 IN	60,600.00	LF		\$	
0200	10020NS		FUEL ADJUSTMENT	8,682.00	DOLL	\$1.00	\$	\$8,682.00
0210	10030NS		ASPHALT ADJUSTMENT	21,808.00	DOLL	\$1.00	\$	\$21,808.00

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0220	02569		DEMOBILIZATION	1.00	LS		\$	