



Andy Beshear  
GOVERNOR

## TRANSPORTATION CABINET

200 Mero Street  
Frankfort, Kentucky 40601

Jim Gray  
SECRETARY

April 23, 2025

CALL NO. 408  
CONTRACT ID NO. 252973  
ADDENDUM # 2

Subject: Spencer-Jefferson Counties, 121GR25M049  
Letting April 24, 2025

(1) Revised - Special Note - Page 25 of 75

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

## **SPECIAL NOTE FOR PREVENTIVE MAINTENANCE**

### **1. DESCRIPTION.**

Perform all work in accordance with the Kentucky Transportation Cabinet, Department of Highway's Standard Specifications for Road and Bridge Construction and applicable Supplemental Specifications, the Standard Drawings, (current editions), this Note and Attached Detailed Drawings. Section references are to the Standard Specifications. This work consists of the following: (1) Furnish all labor, materials, tools, and equipment, (2) Bridge Cleaning, (3) Concrete Coatings (4) Any other work specified as part of this contract.

### **2. MATERIALS.**

#### **A. Wash Water**

Use clean potable water for all pressure washing.

#### **B. Concrete Coatings**

See The Division of Material's list of approved materials for concrete coatings. Contrary to Section 821 closely match the existing color with the values from the University of Louisville link:  
<https://teamcolorcodes.com/louisville-cardinals-color-codes/#:~:text=The%20red%20color%20code%20for,4%2C%20PANTONE%3A%20PMS%201797>

### **3. CONSTRUCTION.**

#### **A. Bridge Cleaning.**

Specified bridge components shall have all debris removed. See attached detailed drawings addressing components having debris removal. Equipment for removing debris from the bridge components shall be determined by the Contractor, subject to the approval of the Engineer. The Contractor shall prevent any debris from entering any body of water, bridge drainage system, or traffic lanes. All debris removed shall be disposed of in a suitable off-site disposal facility.

**All cost to complete remove debris shall be included in the Lump Sum price for "Bridge Cleaning".**