



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

February 8, 2011

CALL NO. 409  
CONTRACT ID NO. 112066  
ADDENDUM # 2

Subject: McCracken County, 073GR11P026-FD05  
Letting February 18, 2011

- (1) Revised - Table of Contents - Page 2 of 97
- (2) Deleted - Fuel & Asphalt Pay Adjustment - Pages 6-7 of 97
- (3) Revised - Material Summary - Pages 34-35 of 97
- (4) Revised - Bid Items - Pages 96-97 of 97

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:ks  
Enclosures



An Equal Opportunity Employer M/F/D

## TABLE OF CONTENTS

PART I	SCOPE OF WORK
	<ul style="list-style-type: none"><li>• PROJECT(S), COMPLETION DATE(S), &amp; LIQUIDATED DAMAGES</li><li>• CONTRACT NOTES</li><li>• 2011 DEFERRED PAYMENT</li><li>• SURFACING AREAS</li><li>• ASPHALT MIXTURE</li><li>• DGA BASE FOR SHOULDERS</li><li>• INCIDENTAL SURFACING</li><li>• OPTION A</li><li>• OPTION B</li><li>• EDGE KEY</li><li>• ASPHALT MILLING AND TEXTURING</li><li>• TYPICAL SECTION DIMENSIONS</li><li>• TRAFFIC CONTROL PLAN</li><li>• TRAFFIC CONTROL PLAN</li><li>• TRAFFIC SIGNAL LOOP DETECTORS</li><li>• TRAFFIC SIGNAL LOOP REPLACEMENT</li><li>• SKETCH MAP(S)</li><li>• MATERIAL SUMMARY</li><li>• SUMMARY SHEET(S)</li><li>• TYPICAL SECTION(S)</li><li>• BRIDGE DETAIL FOR PAVING PROJECT</li></ul>
PART II	SPECIFICATIONS AND STANDARD DRAWINGS
	<ul style="list-style-type: none"><li>• SPECIFICATIONS REFERENCE</li><li>• SUPPLEMENTAL SPECIFICATIONS</li><li>• [SN-1I] PORTABLE CHANGEABLE SIGNS</li><li>• STANDARD DRAWINGS THAT APPLY</li></ul>
PART III	EMPLOYMENT, WAGE AND RECORD REQUIREMENTS
	<ul style="list-style-type: none"><li>• LABOR AND WAGE REQUIREMENTS</li><li>• EXECUTIVE BRANCH CODE OF ETHICS</li><li>• KENTUCKY EQUAL EMPLOYMENT OPPORTUNITY ACT OF 1978</li><li>• PROJECT WAGE RATES</li></ul>
PART IV	INSURANCE
PART V	BID ITEMS

**DEFERRED PAYMENT: The successful bidder on this project may request a work order with an effective date prior to June 15, 2011. The request must be in writing to the Department. A work order issued at the request of the Contractor will be with the distinct understanding that payment for any work performed estimates may be delayed until July 15, 2011. A work order will be issued June 15, 2011, for this project unless the bidder requests an earlier work date.**

### **SURFACING AREAS**

#### **US 45X**

Mainline surfacing width is estimated to vary from 44-60 feet.

Total mainline area to be surfaced is estimated to be 15,678 square yards.

#### **US 60**

Mainline surfacing width is estimated to be 50 feet.

Total mainline area to be surfaced is estimated to be 7,358 square yards.

#### **KY 1565**

Mainline surfacing width is estimated to vary from 17-20 feet.

Total mainline area to be surfaced is estimated to be 8,139 square yards.

Shoulder width is estimated to be 1 foot on each side.

Total shoulder area to be surfaced is estimated to be 751 square yards

### **ASPHALT MIXTURE**

The rate of application for all asphalt mixtures shall be estimated at 110 lbs/sy per inch of depth, unless otherwise noted.

### **DGA BASE FOR SHOULDERS**

#### **KY 1565**

The rate of application shall be estimated at 115 lbs/sy per inch of depth. Payment for necessary grading and/or shaping of existing shoulders prior to placing of Dense Graded Aggregate Base shall be included in the unit price bid per ton for Dense Graded Aggregate Base.

### **INCIDENTAL SURFACING**

The quantities established in the proposal include estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, and road and street approaches. These items are to be paved to the limits as shown on Standard Drawing RPM 110 or to the limits as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, the paving of the crossroads shall be to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. These areas are to be surfaced or resurfaced as directed by the Engineer and no direct payment will be allowed for placing and compacting.

### **OPTION A**

#### **US 45X**

The Contractor is advised that the compaction of asphalt mixtures furnished for driving lanes and ramps, at 25mm (1 inch) or greater, on this project will be accepted according to OPTION A in accordance with Section 402 and Section 403 of the current Standard Specification. Joint cores as described in subsection 402.03.02 are required for surface mixtures only. The compaction of all other asphalt mixtures will be accepted by OPTION B.

---

OPTION B

US 60 & KY 1565

The Contractor is advised that the compaction of asphalt mixtures furnished to this project will be accepted by OPTION B in accordance with Section 402 and Section 403 of the current Standard Specification.

MATERIAL SUMMARY

CONTRACT ID: 112066

FD05 073 0060 013-014 PES NO: MP07300601004  
JOE CLIFTON DRIVE (US 60) FROM US 60X (MP 13.174) EXTENDING EAST TO US 45-LACLEDE  
STREET (MP 13.402), A DISTANCE OF 0.230000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
0010	00330	CL3 ASPH SURF 0.50A PG64-22	607.00	TON
0020	02562	SIGNS	290.00	SQFT
0030	02650	MAINTAIN & CONTROL TRAFFIC US 60	1.00	LS
0050	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0060	02676	MOBILIZATION FOR MILL & TEXT US 60	1.00	LS
0070	02677	ASPHALT PAVE MILLING & TEXTURING	552.00	TON
0090	02775	ARROW PANEL	2.00	EACH
0100	04793	CONDUIT-1 1/4 IN	25.00	LF
0110	04820	TRENCHING AND BACKFILLING	25.00	LF
0120	04830	LOOP WIRE	1,000.00	LF
0130	04895	LOOP SAW SLOT AND FILL	350.00	LF
0140	06510	PAVE STRIPING-TEMP PAINT-4 IN	6,500.00	LF
0150	06514	PAVE STRIPING-PERM PAINT-4 IN	6,500.00	LF
0160	06568	PAVE MARKING-THERMO STOP BAR-24IN	80.00	LF
0170	06574	PAVE MARKING-THERMO CURV ARROW	3.00	EACH
0180	06575	PAVE MARKING-THERMO COMB ARROW	6.00	EACH
0190	06600	REMOVE PAVEMENT MARKER TYPE V	61.00	EACH
0220	02569	DEMOBILIZATION	1.00	LS

FD05 073 045X 000-001 PES NO: MP073045X1003  
KENTUCKY AVENUE (US 45X) FROM US 45 (MP 0.000) EXTENDING NORTH TO 0.06 MILES NORTH  
OF 24TH STREET (MP 0.423), A DISTANCE OF 0.420000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
0010	00190	LEVELING & WEDGING PG64-22	217.00	TON
0020	02562	SIGNS	310.00	SQFT
0030	02650	MAINTAIN & CONTROL TRAFFIC US 45X	1.00	LS
0050	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0060	02676	MOBILIZATION FOR MILL & TEXT US 45X	1.00	LS
0070	02677	ASPHALT PAVE MILLING & TEXTURING	165.00	TON
0090	02775	ARROW PANEL	2.00	EACH
0100	06510	PAVE STRIPING-TEMP PAINT-4 IN	7,000.00	LF
0110	06514	PAVE STRIPING-PERM PAINT-4 IN	13,000.00	LF
0120	06565	PAVE MARKING-THERMO X-WALK-6 IN	584.00	LF
0130	06568	PAVE MARKING-THERMO STOP BAR-24IN	102.00	LF
0140	06569	PAVE MARKING-THERMO CROSS-HATCH	1,765.00	SQFT
0150	06574	PAVE MARKING-THERMO CURV ARROW	6.00	EACH
0160	06575	PAVE MARKING-THERMO COMB ARROW	2.00	EACH
0170	06600	REMOVE PAVEMENT MARKER TYPE V	130.00	EACH
0200	23362ES403	CL2 ASPH SURF 0.5B PG64-22	1,295.00	TON
0210	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 112066

FD05 073 1565 003-005

PES NO: MP07315651101

MAYFIELD METROPOLIS ROAD (KY 1565) FROM KY 3520 (MP 3.913) EXTENDING NORTH TO US 60  
(MP 4.553), A DISTANCE OF 0.640000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
0010	00001	DGA BASE	90.00	TON
0020	00190	LEVELING & WEDGING PG64-22	162.00	TON
0030	00301	CL2 ASPH SURF 0.38D PG64-22	450.00	TON
0040	02562	SIGNS	290.00	SQFT
0050	02650	MAINTAIN & CONTROL TRAFFIC KY 1565	1.00	LS
0060	02676	MOBILIZATION FOR MILL & TEXT KY 1565	1.00	LS
0070	02677	ASPHALT PAVE MILLING & TEXTURING	44.00	TON
0080	06510	PAVE STRIPING-TEMP PAINT-4 IN	1,000.00	LF
0090	06514	PAVE STRIPING-PERM PAINT-4 IN	5,100.00	LF
0100	06568	PAVE MARKING-THERMO STOP BAR-24IN	25.00	LF
0130	02569	DEMOBILIZATION	1.00	LS

---

CONTRACT ID: 112066  
COUNTY: MCCRACKEN  
PROPOSAL: 073GR11P026-FD05

PAGE: 1  
LETTING: 02/18/11  
CALL NO: 409

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY						
0010	00001	DGA BASE	90.000	TON		
0020	00190	LEVELING & WEDGING PG64-22	379.000	TON		
0030	00301	CL2 ASPH SURF 0.38D PG64-22	450.000	TON		
0040	00330	CL3 ASPH SURF 0.50A PG64-22	607.000	TON		
0050	02562	SIGNS	890.000	SQFT		
0060	02650	MAINTAIN & CONTROL TRAFFIC KY 1565	( 1.00)	LS		
0070	02650	MAINTAIN & CONTROL TRAFFIC US 45X	( 1.00)	LS		
0080	02650	MAINTAIN & CONTROL TRAFFIC US 60	( 1.00)	LS		
0090	02671	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH		
0100	02676	MOBILIZATION FOR MILL & TEXT KY 1565	( 1.00)	LS		
0110	02676	MOBILIZATION FOR MILL & TEXT US 45X	( 1.00)	LS		
0120	02676	MOBILIZATION FOR MILL & TEXT US 60	( 1.00)	LS		
0130	02677	ASPHALT PAVE MILLING & TEXTURING	761.000	TON		
0140	02775	ARROW PANEL	4.000	EACH		
0150	04793	CONDUIT-1 1/4 IN	25.000	LF		
0160	04820	TRENCHING AND BACKFILLING	25.000	LF		
0170	04830	LOOP WIRE	1,000.000	LF		
0180	04895	LOOP SAW SLOT AND FILL	350.000	LF		
0190	06510	PAVE STRIPING-TEMP PAINT-4 IN	14,500.000	LF		
0200	06514	PAVE STRIPING-PERM PAINT-4 IN	24,600.000	LF		

CONTRACT ID: 112066  
COUNTY: MCCRACKEN  
PROPOSAL: 073GR11P026-FD05

PAGE: 2  
LETTING: 02/18/11  
CALL NO: 409

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0210	06565	PAVE MARKING-THERMO X-WALK-6 IN	584.000	LF		
0220	06568	PAVE MARKING-THERMO STOP BAR-24IN	207.000	LF		
0230	06569	PAVE MARKING-THERMO CROSS-HATCH	1,765.000	SQFT		
0240	06574	PAVE MARKING-THERMO CURV ARROW	9.000	EACH		
0250	06575	PAVE MARKING-THERMO COMB ARROW	8.000	EACH		
0260	06600	REMOVE PAVEMENT MARKER TYPE V	191.000	EACH		
0290	23362ES403	CL2 ASPH SURF 0.5B PG64-22	1,295.000	TON		
SECTION 0002 DEMOBILIZATION						
0300	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				