



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

March 4, 2021

CALL NO. 413
CONTRACT ID NO. 213052
ADDENDUM # 1

Subject: SCOTT COUNTY, 105GR21R024-CB06
Letting March 19, 2021

- (1) Revised - Special Notes - Page 15 of 53
- (2) Revised - Material Summary - Pages 29 of 53
- (3) Revised - Base Failure Repair Summary - Page 33 of 53
- (4) Revised - Proposal Bid Items - Page 53 of 53

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SPECIAL NOTE FOR BASE FAILURE REPAIR

Repair locations listed on the summary are approximate only. The Engineer will determine actual repair locations and dimensions at the time of construction. Prior to overall milling and/or leveling and wedging, excavate the designated base failure areas to a depth 8 inches below the existing asphalt pavement surface level. Dispose of the excavated materials at waste sites off the Right-of-Way obtained by the Contractor at no additional cost to the Department. See Special Note for Waste and Borrow.

Backfill the excavated areas with Class 2 Asphalt Base 1.00D PG64-22. Compact the asphalt base to the compaction required in Section 403.03.10. Seal the asphalt base with leveling and wedging. Perform all base failure repairs in such a manner that removal and replacement are completed on the same day. Do this work as one of the Contractor's first operations in order to allow further compaction by traffic. Do not mill or place new asphalt surface over repaired base failure areas until a minimum of 7 calendar days have elapsed after placement of the asphalt base. After a minimum of 7 calendar days and when the Engineer determines the base failure repair areas have sufficiently stabilized, begin milling and/or resurfacing operations. Prior to milling and/or constructing the new asphalt surface, level and wedge any settlement of the repair areas.

The bidder must draw conclusions as to the conditions encountered. The Department does not give any guarantee as to the accuracy of the data and will not consider any claim for additional compensation if the materials encountered that are not in accord with the classification shown.

Accept payment at the Contract unit prices per square yard for Base Failure repair and per ton for Leveling and Wedging as full compensation for all labor, materials, equipment, and incidentals for removing pavement and disposing of the materials, furnishing and placing asphalt base, leveling and wedging, and all other items necessary to complete the work according to these notes to the satisfaction of the Engineer.

1-3606basefailurerepairmillinlaypaybysy
01/02/2012

MATERIAL SUMMARY

CONTRACT ID: 213052

105GR21R024-CB06

0710519632001

LISLE RD (KY 1963) FROM 0.128 MILES NORTH OF KY 2909 EXTENDING NORTH TO KY 1962 ASPHALT RESURFACING, A DISTANCE OF 1.4 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	150.00	TON
0010	00301	CL2 ASPH SURF 0.38D PG64-22	1,040.00	TON
0015	00356	ASPHALT MATERIAL FOR TACK	8.00	TON
0020	02562	TEMPORARY SIGNS	170.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1963)	1.00	LS
0030	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0035	02676	MOBILIZATION FOR MILL & TEXT - (KY 1963)	1.00	LS
0040	02677	ASPHALT PAVE MILLING & TEXTURING	15.00	TON
0045	06510	PAVE STRIPING-TEMP PAINT-4 IN	15,000.00	LF
0050	06514	PAVE STRIPING-PERM PAINT-4 IN	15,000.00	LF
0055	10020NS	FUEL ADJUSTMENT	1,863.00	DOLL
0060	10030NS	ASPHALT ADJUSTMENT	4,680.00	DOLL
0065	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 213052

105GR21R024-CB06

0710519732001

IRONWORKS RD (KY 1973) FROM 0.132 MILES NORTH OF YARNALLTON PIKE EXTENDING NORTH TO 0.458 MILES NORTH OF US 62 ASPHALT RESURFACING, A DISTANCE OF 2.9 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0070	00190	LEVELING & WEDGING PG64-22	300.00	TON
0075	00301	CL2 ASPH SURF 0.38D PG64-22	2,050.00	TON
0080	00356	ASPHALT MATERIAL FOR TACK	17.00	TON
0085	02562	TEMPORARY SIGNS	190.00	SQFT
0090	02650	MAINTAIN & CONTROL TRAFFIC - (KY 1973)	1.00	LS
0095	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0100	02676	MOBILIZATION FOR MILL & TEXT - (KY 1973)	1.00	LS
0105	02677	ASPHALT PAVE MILLING & TEXTURING	130.00	TON
0110	02697	EDGE LINE RUMBLE STRIPS	61,200.00	LF
0115	03240	BASE FAILURE REPAIR - (REVISED: 3-4-21)	200.00	SQYD
0120	06510	PAVE STRIPING-TEMP PAINT-4 IN	66,000.00	LF
0125	06514	PAVE STRIPING-PERM PAINT-4 IN	66,000.00	LF
0130	06547	PAVE STRIPING-THERMO-12 IN Y	120.00	LF
0135	06574	PAVE MARKING-THERMO CURV ARROW	4.00	EACH
0140	06575	PAVE MARKING-THERMO COMB ARROW	4.00	EACH
0145	10020NS	FUEL ADJUSTMENT	3,677.00	DOLL
0150	10030NS	ASPHALT ADJUSTMENT	9,235.00	DOLL
0155	02569	DEMOBILIZATION	1.00	LS

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	450.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	3,090.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	25.00	TON		\$	
0040	02562		TEMPORARY SIGNS	360.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC (KY 1963)	1.00	LS		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC (KY 1973)	1.00	LS		\$	
0070	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0080	02676		MOBILIZATION FOR MILL & TEXT (KY 1963)	1.00	LS		\$	
0090	02676		MOBILIZATION FOR MILL & TEXT (KY 1973)	1.00	LS		\$	
0100	02677		ASPHALT PAVE MILLING & TEXTURING	145.00	TON		\$	
0110	02697		EDGE LINE RUMBLE STRIPS	61,200.00	LF		\$	
0120	03240		BASE FAILURE REPAIR (REVISED: 3-4-21)	200.00	SQYD		\$	
0130	06510		PAVE STRIPING-TEMP PAINT-4 IN	81,000.00	LF		\$	
0140	06514		PAVE STRIPING-PERM PAINT-4 IN	81,000.00	LF		\$	
0150	06547		PAVE STRIPING-THERMO-12 IN Y	120.00	LF		\$	
0160	06574		PAVE MARKING-THERMO CURV ARROW	4.00	EACH		\$	
0170	06575		PAVE MARKING-THERMO COMB ARROW	4.00	EACH		\$	
0180	10020NS		FUEL ADJUSTMENT	5,540.00	DOLL	\$1.00	\$	\$5,540.00
0190	10030NS		ASPHALT ADJUSTMENT	13,915.00	DOLL	\$1.00	\$	\$13,915.00

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0200	02569		DEMOBILIZATION	1.00	LS		\$	