



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

September 20, 2021

CALL NO. 417
CONTRACT ID NO. 212915
ADDENDUM # 1

Subject: Magoffin-Perry Counties, 121GR21M097-FE02
Letting September 24, 2021

- (1) Revised - Special Note - Page 19 of 43
- (2) Revised - Material Summary - Pages 21-22 of 43
- (3) Revised - Proposal Bid Items - Page 43 of 43

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

V. PROJECT PHASING & CONSTRUCTION PROCEDURES

For 077B00071N, the Contractor shall maintain one lane of traffic during construction in accordance with Standard Drawing No. TTC-110 for lane closures. The minimum clear lane width required is 11'-0".

For 097B00087N, the Contractor shall maintain one lane of traffic during construction in accordance with Standard Drawing No. TTC-110 for lane closures. The minimum clear lane width required is 11'-0".

Parkway lane closures will not be permitted on these days:

Memorial Day Weekend (Friday-Monday)

Independence Day, when July 4th is on Tuesday, Wednesday, or Thursday; or

Independence Day Weekend, when July 4th is on Monday (Saturday-Monday) or Friday (Friday-Sunday)

Labor Day Weekend (Friday-Monday)

VI. BARRIER WALL

Payment of the contract unit price per linear foot for "CONCRETE BARRIER WALL TYPE 9T" shall be full compensation for furnishing, installing, maintaining, adjusting alignment as needed, removing the barrier when no longer needed, and all incidental items necessary to complete the work.

Provide one side mounted barrier wall delineator per each section of barrier. See Standard Drawing RBM-020 for types. No direct payment allowed for delineators.

VII. CRASH CUSHION / END TREATMENTS

To the satisfaction of the Engineer extend Barrier wall out of the clear zone. If Barrier wall is not extended out of the clear zone to the satisfaction of the engineer provide crash cushions / end treatments for the barrier wall.

Provide Barrier end treatments that comply with NCHRP 350 LEVEL 3.

IX. TEMPORARY SIGNAL

For 077B00071N, the Contractor shall provide, install, and maintain a temporary multi-phase traffic signal. For 097B00087N, the Contractor shall provide, install, and maintain a temporary 2 phase traffic signal. The Contractor must provide a 24-hour contact person and number available to maintain the temporary signals as needed.

MATERIAL SUMMARY

CONTRACT ID: 212915

121GR21M097-FE02

MB07733332101

KY 3333 (MP 0.569). BRIDGE OVER LICK CREEK. BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02562	TEMPORARY SIGNS	149.00	SQFT
0010	02650	MAINTAIN & CONTROL TRAFFIC - APPLIES TO 077B00071N	1.00	LS
0015	02653	LANE CLOSURE	2.00	EACH
0020	03296	EXPAN JOINT REPLACE 2 1/2 IN	55.40	LF
0025	03299	ARMORED EDGE FOR CONCRETE	55.40	LF
0030	03300	ELIMINATE TRANSVERSE JOINT	63.40	LF
0035	03304	BRIDGE OVERLAY APPROACH PAVEMENT	533.00	SQYD
0040	04934	TEMP SIGNAL MULTI PHASE	1.00	EACH
0045	06514	PAVE STRIPING-PERM PAINT-4 IN	598.00	LF
0050	06549	PAVE STRIPING-TEMP REM TAPE-B	500.00	LF
0055	06550	PAVE STRIPING-TEMP REM TAPE-W	1,000.00	LF
0060	06551	PAVE STRIPING-TEMP REM TAPE-Y	2,000.00	LF
0065	08150	STEEL REINFORCEMENT	868.40	LB
0070	08504	EPOXY SAND SLURRY	84.30	SQYD
0075	08526	CONC CLASS M FULL DEPTH PATCH	4.00	CUYD
0080	08534	CONCRETE OVERLAY-LATEX	11.00	CUYD
0085	08549	BLAST CLEANING	348.00	SQYD
0090	08551	MACHINE PREP OF SLAB	264.00	SQYD
0095	24094EC	PARTIAL DEPTH PATCHING	7.30	CUYD
0100	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 212915

121GR21M097-FE02

MB09790062101

HAL ROGERS PKWY (MP 0.569). BRIDGE OVER KY 80 AND BIG CREEK. BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0105	02003	RELOCATE TEMP CONC BARRIER	900.00	LF
0110	02562	TEMPORARY SIGNS	149.00	SQFT
0115	02650	MAINTAIN & CONTROL TRAFFIC - APPLIES TO 097B00087N	1.00	LS
0120	02653	LANE CLOSURE	2.00	EACH
0125	02671	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0130	02775	ARROW PANEL	1.00	EACH
0135	02898	RELOCATE CRASH CUSHION	1.00	EACH
0140	02900	INSTALL TEMP CRASH CUSHION	1.00	EACH
0145	03171	CONCRETE BARRIER WALL TYPE 9T	900.00	LF
0150	03298	EXPAN JOINT REPLACE 4 IN	122.10	LF
0155	03299	ARMORED EDGE FOR CONCRETE	122.10	LF
0160	03304	BRIDGE OVERLAY APPROACH PAVEMENT	556.00	SQYD
0165	06514	PAVE STRIPING-PERM PAINT-4 IN	2,744.00	LF
0170	06549	PAVE STRIPING-TEMP REM TAPE-B	500.00	LF
0175	06550	PAVE STRIPING-TEMP REM TAPE-W	1,000.00	LF
0180	06551	PAVE STRIPING-TEMP REM TAPE-Y	2,000.00	LF
0185	08150	STEEL REINFORCEMENT	267.20	LB
0190	08504	EPOXY SAND SLURRY	336.40	SQYD
0195	08510	REM EPOXY BIT FOREIGN OVERLAY	3,256.00	SQYD
0200	08526	CONC CLASS M FULL DEPTH PATCH	4.00	CUYD
0205	08534	CONCRETE OVERLAY-LATEX	135.60	CUYD
0210	08549	BLAST CLEANING	3,592.00	SQYD
0215	24094EC	PARTIAL DEPTH PATCHING	90.40	CUYD
0220	02569	DEMOBILIZATION	1.00	LS
0225	04933	TEMP SIGNAL 2 PHASE - (ADDED 9-20-2021)	1.00	EACH

PROPOSAL BID ITEMS

Report Date 9/20/21

Section: 0001 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	02003		RELOCATE TEMP CONC BARRIER	900.00	LF		\$	
0020	02562		TEMPORARY SIGNS	298.00	SQFT		\$	
0030	02650		MAINTAIN & CONTROL TRAFFIC APPLIES TO 077B00071N	1.00	LS		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC APPLIES TO 097B00087N	1.00	LS		\$	
0050	02653		LANE CLOSURE	4.00	EACH		\$	
0060	02671		PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH		\$	
0070	02775		ARROW PANEL	1.00	EACH		\$	
0080	02898		RELOCATE CRASH CUSHION	1.00	EACH		\$	
0090	02900		INSTALL TEMP CRASH CUSHION	1.00	EACH		\$	
0100	03171		CONCRETE BARRIER WALL TYPE 9T	900.00	LF		\$	
0110	03296		EXPAN JOINT REPLACE 2 1/2 IN	55.40	LF		\$	
0120	03298		EXPAN JOINT REPLACE 4 IN	122.10	LF		\$	
0130	03299		ARMORED EDGE FOR CONCRETE	177.50	LF		\$	
0140	03300		ELIMINATE TRANSVERSE JOINT	63.40	LF		\$	
0150	03304		BRIDGE OVERLAY APPROACH PAVEMENT	1,089.00	SQYD		\$	
0155	04933		TEMP SIGNAL 2 PHASE (ADDED 9-20-2021)	1.00	EACH		\$	
0160	04934		TEMP SIGNAL MULTI PHASE	1.00	EACH		\$	
0170	06514		PAVE STRIPING-PERM PAINT-4 IN	3,342.00	LF		\$	
0180	06549		PAVE STRIPING-TEMP REM TAPE-B	1,000.00	LF		\$	
0190	06550		PAVE STRIPING-TEMP REM TAPE-W	2,000.00	LF		\$	
0200	06551		PAVE STRIPING-TEMP REM TAPE-Y	4,000.00	LF		\$	
0210	08150		STEEL REINFORCEMENT	1,135.60	LB		\$	
0220	08504		EPOXY SAND SLURRY	420.70	SQYD		\$	
0230	08510		REM EPOXY BIT FOREIGN OVERLAY	3,256.00	SQYD		\$	
0240	08526		CONC CLASS M FULL DEPTH PATCH	8.00	CUYD		\$	
0250	08534		CONCRETE OVERLAY-LATEX	146.60	CUYD		\$	
0260	08549		BLAST CLEANING	3,940.00	SQYD		\$	
0270	08551		MACHINE PREP OF SLAB	264.00	SQYD		\$	
0280	24094EC		PARTIAL DEPTH PATCHING	97.70	CUYD		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0290	02569		DEMOBILIZATION	1.00	LS		\$	