## Supplemental Specifications to The Standard Specifications for Road and Bridge Construction, 2008 Edition

(Effective with the May 23, 2008 Letting)

SUBSECTION:	112.03.12 Project Traffic Coordinator (PTC).		
<b>REVISION:</b>	Add the following at the end of the subsection:		
	•		
	After October 1, 2008 the Department will require the PTC to have successfully completed the		
	applicable qualification courses. Personnel that have not successfully completed the applicable		
	courses by that date will not be considered qualified. Prior to October 1, 2008, conform to Subsection		
	108.06 A) and ensure the designated PTC has sufficient skill and experience to properly perform the		
	task.		
SUBSECTION:	837.03.01 Composition.		
<b>REVISION:</b>	COMPOSITION Table:		
	Replace		<u> </u>
	Lead Chromate	0.0 max.	4.0 min.
	with		
	Heavy Metals Content	Comply with 40 CFR 261	
SUBSECTION:	213.03.05 Temporary Control Measures.		
PART:	F) Temporary Mulch.		
<b>REVISION:</b>	Replace the last sentence with the following:		
	Place temporary mulch to an approximate 2-inch loose depth (2 tons per acre) and anchor it into the		
	soil by mechanically crimping it into the soil surface or applying tackifier to provide a protective		
	cover. Regardless of the anchoring method used, ensure the protective cover holds until disturbance is		
	required or permanent controls are in installed.		
SUBSECTION:	410.05 PAYMENT.		
<b>REVISION:</b>	Replace the last sentence of the first paragraph with the following:		
	The Department will not apply positive ride adjustments to 0.1-lane-mile sections when their		
	associated sublot's density pay value is less than 0.95.		
SUBSECTION:	805.04 Concrete		
REVISION:	Replace the "AASHTO T 160" reference in first sentence of the third paragraph with "KM 64-629"		
SUBSECTION:	805.16 Sampling and Testing		
<b>REVISION:</b>	Replace the "AASHTO T 160" reference with "KM 64-629" for the Concrete Beam Expansion Test.		