

**US 150 Washington County  
Mayfield Lane to US 150 Bypass  
April 9 & April 23, 2019**

|                                | Alternative #1 | Alternative #2 |
|--------------------------------|----------------|----------------|
| Length (ft.)                   | 17,038         | 17,038         |
| Maximum Grade %                | 6.54%          | 6.54%          |
| Earthwork                      | \$10/CY        | \$10/CY        |
| Cut (cu yd.)                   | 116,020        | 111,205        |
| Fill (cu yd.)                  | 15,262         | 13,878         |
| Net (cu yd.)                   | 100,758        | 97,327         |
| Disturb Limits (acres)         | 24.65          | 25.43          |
| Blueline Stream Crossings      | 2              | 2              |
| Impact to Parker Run (LF)      | 85             | 85             |
| Crop Land Impacts              | LOW            | LOW            |
| Number of Parcels              | 22             | 23             |
| Right of Way Acquisition (AC)  | 4.811          | 4.112          |
| Easements (SF)                 | 15,865         | 22,706         |
| Residential Takings            | 0              | 0              |
| Garage/Barn Takings            | 1              | 1              |
|                                |                |                |
| Maintenance of Traffic Impacts | High           | High           |
| Utility Impacts                | LOW            | LOW            |
| Costs                          |                |                |
| Right of Way                   | \$490,000      | \$440,000      |
| Utilities                      | \$260,000      | \$290,000      |
| Construction                   | \$6,390,000    | \$6,390,000    |
| Contingency      25%           | \$1,600,000    | \$1,600,000    |
| Total                          | \$8,740,000    | \$8,720,000    |