

SPECIAL NOTE FOR GEOGRID PLACEMENT

This Special Note will apply when indicated on the plans or in the proposal. Section references herein are to the Department's Standard Specifications for Road and Bridge Construction.

1.0 DESCRIPTION.

Additional notes in addition to the Standard Specifications for the placement of Geogrid.

2.0 MATERIALS

2.1 Geogrid: Furnish a punched and drawn Geogrid meeting the requirements of Section 304.

2.2 Type IV Geotextile Fabric: Conform to Section 843.

3.0 CONSTRUCTION

Place the type IV geotextile fabric first, and then place the geogrid on top of the geotextile fabric so that they are at the bottom of the aggregate layer. Maintain tension on the geogrid and ensure there are no buckles or folds. Geogrid should not be completely placed before placing aggregate, but should be placed down at the front of a "paving train" consisting of the geogrid laydown equipment followed no further than 50 feet by the aggregate placement equipment. In curves and intersections, cut and overlap the geogrid. Place the geogrid and aggregate according to Sections 304 and 302. Contrary to Section 302.03.03, if the total aggregate base thickness is less than 12 inches, the aggregate base will be placed in one lift. If greater than 12 inches, place the aggregate in 3 inch to 12 inch lifts with the first lift being a minimum of 10 inches. All other construction and density requirements of Section 302 will apply.

4.0 MEASUREMENT.

The Department will measure the quantity of Geogrid in square yards and the quantity of Type IV Fabric in square yards. The Department will not make payment for providing a geogrid manufacturer's representative and will consider it incidental to the bid item for Geogrid.

5.0 PAYMENT.

The Cabinet will make payment for the completed and accepted quantities under the following:

<u>Code</u>	<u>Pay Item</u>	<u>Pay Unit</u>
00005	GEOGRID REINFORCEMENT FOR SUBGRADE	Square Yard
02599	FABRIC-GEOTEXTILE TYPE IV	Square Yard

The Cabinet will consider payment as full compensation for all work required in this note.