

COUNTY OF	ITEM NO.	SHEET NO.

DGA WEDGE & CHIP SEAL								
Offset	Begin Mile Point	Begin Station	End Mile Point	End Station	Description	DGA (tons)	Asphalt Seal Aggregate (tons)	Asphalt Seal Coat (tons)
LT	21.052	8+18	21.407	26+94	DGA Wedge & Chip Seal	96	17	2
LT	21.563	35+19	21.846	50+12	DGA Wedge & Chip Seal	77	13	1.7
LT	22.033	60+00	22.204	69+00	DGA Wedge & Chip Seal	46	8	1.1
LT	22.346	76+50	22.469	83+02	DGA Wedge & Chip Seal	34	6	0.7
LT	22.493	84+25	22.675	93+90	DGA Wedge & Chip Seal	50	9	1.1
LT	22.772	99+00	22.804	100+70	DGA Wedge & Chip Seal	9	2	0.2
LT	22.866	103+98	22.929	107+28	DGA Wedge & Chip Seal	17	3	0.4
LT	23.432	133+86	25.022	217+80	DGA Wedge & Chip Seal	430	76	9.2
RT	21.056	8+39	21.407	26+94	DGA Wedge & Chip Seal	96	17	2.1
RT	22.033	60+00	22.215	69+61	DGA Wedge & Chip Seal	51	9	1.1
RT	22.234	70+60	22.347	76+56	DGA Wedge & Chip Seal	32	5	0.7
RT	22.452	82+10	22.469	83+02	DGA Wedge & Chip Seal	6	1	0.1
RT	22.656	92+86	22.675	93+86	DGA Wedge & Chip Seal	7	1	0.1
RT	22.792	100+05	22.833	102+20	DGA Wedge & Chip Seal	12	2	0.2
RT	22.845	102+85	22.849	103+08	DGA Wedge & Chip Seal	2	1	0.1
RT	22.930	107+37	22.942	108+00	DGA Wedge & Chip Seal	4	1	0.1
RT	23.007	111+40	23.156	119+26	DGA Wedge & Chip Seal	41	7	0.8
RT	23.230	123+19	23.283	126+00	DGA Wedge & Chip Seal	46	3	0.3
RT	23.432	133+86	23.511	138+00	DGA Wedge & Chip Seal	22	4	0.4
RT	23.557	140+45	24.057	166+83	DGA Wedge & Chip Seal	136	24	2.9
RT	24.124	170+40	24.216	175+26	DGA Wedge & Chip Seal	26	4	0.5
RT	24.280	178+60	24.423	186+15	DGA Wedge & Chip Seal	40	7	0.8
RT	24.609	196+00	25.022	217+80	DGA Wedge & Chip Seal	113	20	2.4
PROJECT TOTAL:						1393	240	29

ITEM	DESCRIPTION	UNIT	QUANTITY
1	DGA BASE	TON	1393
100	ASPHALT SEAL AGGREGATE	TON	240
103	ASPHALT SEAL COAT	TON	29

Note: These numbers are for estimate purposes only. Final locations and quantities will be determined by the Engineer in the field.

NOTE: ALL QUANTITIES CARRIED OVER TO GENERAL SUMMARY

DGA WEDGE & CHIP SEAL TABULATION