



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

May 22, 2018

CALL NO. 100
CONTRACT ID NO. 181217
ADDENDUM # 1

Subject: Rockcastle County, NHPP IM 0753 (100)
Letting May 25, 2018

- (1) Revised - Pavement Summary - Page 31 of 151
- (2) Revised - Bid Items - Pages 150-151 of 151

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mw
Enclosures



An Equal Opportunity Employer M/F/D

**I-75 PAVEMENT REHABILITATION
 ROCKCASTLE COUNTY
 ITEM NO. 8-2030.00**

PAVEMENT SUMMARY						
ITEM CODE	ITEM	UNIT	NORTHBOUND I-75	SOUTHBOUND I-75	TOTAL	
78	CRUSHED AGGREGATE NO 2	(7) TON			45	
100	ASPHALT SEAL AGGREGATE	(1) TON	119	116	235	
103	ASPHALT SEAL COAT	(2) TON	14	14	28	
339	CL3 ASPH SURF 0.38D PG64-22	(3) TON	1,928	1,908	3,836	
342	CL4 ASPH SURF 0.38A PG76-22	(3) TON	6,591	6,595	13,186	
356	ASPHALT MATERIAL FOR TACK	(5) TON	33	32	65	
1000	PERFORATED PIPE - 4 INCH	(7) LF			60	
1028	PERFORATED PIPE HEADWALL TY3-4 INCH	(7) EA			5	
2599	FABRIC - GEOTEXTILE TYPE IV	(7) SY			75	
2676	MOBILIZATION FOR MILLING & TEXTURING	LS			1	
2677	ASPHALT PAVEMENT MILLING & TEXTURING	(3) TON	8,519	8,503	17,022	
2696	SHOULDER RUMBLE STRIPS-SAWED	LF	27,654	27,671	55,325	
3240	BASE FAILURE REPAIR	(7) SY			110	
3383	PVC PIPE - 4 INCH	(7) LF			125	
20071EC	JOINT ADHESIVE	(4) LF	55,308	55,342	110,650	
24781EC	INTELLIGENT COMPACTION FOR ASPHALT	(6) TON	8,519	8,503	17,022	
24891EC	PAVE MOUNT INFRARED TEMP EQUIPMENT	(8) SF	697,024	695,649	1,392,673	

NOTES:

- (1) Estimated at 20 pounds per square yard per application with two applications required.
- (2) Estimated at 2.4 pounds per square yard per application with two applications required.
- (3) Estimated at 110 pounds per square yard per inch depth.
- (4) See Special Note For Longitudinal Pavement Joint Adhesive.
- (5) Estimated at 0.84 pounds per square yard.
- (6) See the special notes for Intelligent Compaction Of Asphalt Mixtures.
- (7) For Base Failure Repairs - To be used as directed by the Engineer. Item No. 78 quantity Includes 1 ton per each "Perforated Pipe Headwall TY3-4 Inch" to be placed around each headwall per Std Dwg RDP-010-08. See the Base Failure Repair Detail sheets. Estimated 5 Dry and 5 Wet Failures.
- (8) See the special notes for Pavement Mounted Temperature Control Profiles.

PROPOSAL BID ITEMS

Report Date 5/22/18

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00078		CRUSHED AGGREGATE SIZE NO 2	45.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	235.00	TON		\$	
0030	00103		ASPHALT SEAL COAT	28.00	TON		\$	
0050	00339		CL3 ASPH SURF 0.38D PG64-22	3,836.00	TON		\$	
0060	00342		CL4 ASPH SURF 0.38A PG76-22	13,186.00	TON		\$	
0070	00356		ASPHALT MATERIAL FOR TACK	65.00	TON		\$	
0080	01000		PERFORATED PIPE-4 IN	60.00	LF		\$	
0090	01028		PERF PIPE HEADWALL TY 3-4 IN	5.00	EACH		\$	
0100	02599		FABRIC-GEOTEXTILE TYPE IV	75.00	SQYD		\$	
0110	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0120	02677		ASPHALT PAVE MILLING & TEXTURING	17,022.00	TON		\$	
0130	02696		SHOULDER RUMBLE STRIPS	55,325.00	LF		\$	
0140	03240		BASE FAILURE REPAIR	110.00	SQYD		\$	
0150	03383		PVC PIPE-4 IN	125.00	LF		\$	
0160	20071EC		JOINT ADHESIVE	110,650.00	LF		\$	
0170	24781EC		INTELLIGENT COMPACTION FOR ASPHALT	17,022.00	TON		\$	
0180	24891EC		PAVE MOUNT INFRARED TEMP EQUIPMENT	1,392,673.00	SF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0190	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	88.00	EACH		\$	
0200	01985		DELINEATOR FOR BARRIER - YELLOW	305.00	EACH		\$	
0210	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0220	02351		GUARDRAIL-STEEL W BEAM-S FACE	75.00	LF		\$	
0230	02367		GUARDRAIL END TREATMENT TYPE 1	3.00	EACH		\$	
0240	02381		REMOVE GUARDRAIL	225.00	LF		\$	
0250	02483		CHANNEL LINING CLASS II	250.00	TON		\$	
0260	02562		TEMPORARY SIGNS	500.00	SQFT		\$	
0270	02575		DITCHING AND SHOULDERING	13,831.00	LF		\$	
0280	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0290	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0300	02701		TEMP SILT FENCE	500.00	LF		\$	
0310	02703		SILT TRAP TYPE A	5.00	EACH		\$	
0320	02704		SILT TRAP TYPE B	5.00	EACH		\$	
0330	02705		SILT TRAP TYPE C	5.00	EACH		\$	
0340	02726		STAKING	1.00	LS		\$	
0350	02775		ARROW PANEL	4.00	EACH		\$	
0360	03260		CLEAN ROADWAY DRAINS	24.00	EACH		\$	
0370	05950		EROSION CONTROL BLANKET	1,000.00	SQYD		\$	
0380	06401		FLEXIBLE DELINEATOR POST-M/W	74.00	EACH		\$	
0390	06511		PAVE STRIPING-TEMP PAINT-6 IN	138,313.00	LF		\$	
0400	06542		PAVE STRIPING-THERMO-6 IN W	41,495.00	LF		\$	
0410	06543		PAVE STRIPING-THERMO-6 IN Y	27,662.00	LF		\$	
0420	10020NS		FUEL ADJUSTMENT	15,272.00	DOLL	\$1.00	\$	\$15,272.00

PROPOSAL BID ITEMS

Report Date 5/22/18

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0430	10030NS		ASPHALT ADJUSTMENT	30,852.00	DOLL	\$1.00	\$	\$30,852.00
0440	20191ED		OBJECT MARKER TY 3	3.00	EACH		\$	
0450	24489EC		INLAID PAVEMENT MARKER	692.00	EACH		\$	

Section: 0003 - TRAFFIC LOOPS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0460	04793		CONDUIT-1 1/4 IN	80.00	LF		\$	
0470	04795		CONDUIT-2 IN	20.00	LF		\$	
0480	04820		TRENCHING AND BACKFILLING	90.00	LF		\$	
0490	04829		PIEZOELECTRIC SENSOR	6.00	EACH		\$	
0500	04830		LOOP WIRE	2,650.00	LF		\$	
0510	04895		LOOP SAW SLOT AND FILL	560.00	LF		\$	
0520	20359NN		GALVANIZED STEEL CABINET	2.00	EACH		\$	
0530	20360ES818		WOOD POST	4.00	EACH		\$	
0540	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH		\$	

Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0550	02568		MOBILIZATION	1.00	LS		\$	
0560	02569		DEMOBILIZATION	1.00	LS		\$	