



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET

[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

September 20, 2022

CALL NO. 100  
CONTRACT ID NO. 221343  
ADDENDUM # 1

Subject: WHITLEY COUNTY, STP 0902 (008)  
Letting September 22, 2022

- (1) Revised - Table of Contents - Page 2 of 313
- (2) Revised - Ride Quality - Page 16 of 313
- (3) Revised - Plan Sheet - R002W

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

## TABLE OF CONTENTS

### SCOPE OF WORK

- PROJECT(S), COMPLETION DATE(S), & LIQUIDATED DAMAGES
- CONTRACT NOTES
- FEDERAL CONTRACT NOTES
- NATIONAL HIGHWAY
- SIGNIFICANT PROJECT -PROJECT TRAFFIC COORDINATOR
- ASPHALT MIXTURE
- DGA BASE
- DGA BASE FOR SHOULDERS
- INCIDENTAL SURFACING
- FUEL AND ASPHALT PAY ADJUSTMENT
- ASPHALT PAVEMENT RIDE QUALITY CAT B
- COMPACTION OPTION A
- MATERIAL TRANSFER VEHICLE (MTV)
- SPECIAL NOTE(S) APPLICABLE TO PROJECT
- TREE REMOVAL
- PIPELINE INSPECTION
- NON-TRACKING TACK COAT
- EXPERIMENTAL KYCT AND HAMBURG TESTING
- SPRAY APPLIED THERMOPLASTIC PAVEMENT MARKING MATERIALS
- RIGHT OF WAY CERTIFICATION
- UTILITY IMPACT & RAIL CERTIFICATION NOTES
- GENERAL UTILITY NOTES
- WATER STANDARD UTILITY BID ITEMS
- SEWER STANDARD UTILITY BID ITEMS
- UTILITY SPECIFICATIONS
- KPDES STORM WATER PERMIT, BMP AND ENOI

### PART II SPECIFICATIONS AND STANDARD DRAWINGS

- SPECIFICATIONS REFERENCE
- SUPPLEMENTAL SPECIFICATION
- [SN-1I] PORTABLE CHANGEABLE SIGNS
- [SN-11F] TURF REINFORCEMENT MAT
- [SP-69] EMBANKMENT AT BRIDGE END BENT STRUCTURES

### PART III EMPLOYMENT, WAGE AND RECORD REQUIREMENTS

- FEDERAL-AID CONSTRUCTION CONTRACTS - FHWA 1273
- NONDISCRIMINATION OF EMPLOYEES
- EXECUTIVE BRANCH CODE OF ETHICS
- PROJECT WAGE RATES LOCALITY 2 / FEDERAL
- NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EEO WHITLEY

### PART IV INSURANCE

### PART V BID ITEMS

### **NATIONAL HIGHWAY**

Be advised this project is on the NATIONAL HIGHWAY SYSTEM.

### **PROJECT TRAFFIC COORDINATOR (PTC)**

Be advised this project is a significant project pursuant to section 112.03.12.

### **ASPHALT MIXTURE**

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

### **DGA BASE**

Unless otherwise noted, the Department estimates the rate of application for DGA Base to be 115 lbs/sy per inch of depth.

### **DGA BASE FOR SHOULDERS**

Unless otherwise noted, the Department estimates the rate of application for DGA Base for Shoulders to be 115 lbs/sy per inch of depth. The Department will not measure necessary grading and/or shaping of existing shoulders prior to placing of DGA Base, but shall be incidental to the Contract unit price per ton for DGA Base.

Accept payment at the Contract unit price per ton as full compensation for all labor, materials, equipment, and incidentals for grading and/or shaping of existing shoulders and furnishing, placing, and compacting the DGA Base.

### **INCIDENTAL SURFACING**

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

### **FUEL AND ASPHALT PAY ADJUSTMENT**

The Department has included the Contract items Asphalt Adjustment and Fuel Adjustment for possible future payments at an established Contract unit price of \$1.00. The Department will calculate actual adjustment quantities after work is completed. If existing Contract amount is insufficient to pay all items on the contract with the adjustments, the Department will establish additional monies with a change order.

### **ASPHALT PAVEMENT RIDE QUALITY CATEGORY B**

The Department will apply Pavement Rideability Requirements on this project in accordance with Section 410, Category B.

### **OPTION A**

Be advised that the Department will accept compaction of asphalt mixtures furnished for driving lanes and ramps, at 1 inch (25mm) or greater, on this project according to OPTION A in accordance with Section 402 and Section 403 of the current Standard Specifications. The Department will require joint cores as described in Section 402.03.02 for surface mixtures only. The Department will accept compaction of all other asphalt mixtures according to OPTION B.

# GENERAL NOTES

## PROPOSAL ATTACHMENTS

### SPECIAL NOTES

- SPECIAL NOTE FOR CONCRETE SEALING
- SPECIAL NOTE FOR PIPELINE INSPECTION
- SPECIAL NOTE FOR NON-TRACKING TACK COAT
- EXPERIMENTAL KYTC AND HAMBURG TESTING (OVER 4,000 TONS ASPH SURF)
- SPECIAL NOTE FOR SPRAY APPLIED THERMOPLASTIC PAVEMENT MARKING MATERIALS

### GENERAL PROVISIONS

THIS PROJECT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "KENTUCKY TRANSPORTATION CABINET/DEPARTMENT OF HIGHWAYS, STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", STANDARD DRAWINGS, MANUALS, GUIDELINES, AND M.U.T.C.D., LATEST EDITIONS, UNLESS OTHERWISE NOTED IN THESE PLANS.

### CONTROL OF WORK

THE CONTRACTOR SHALL CONDUCT HIS OPERATIONS AND COOPERATE WITH OTHER CONTRACTORS, E.G. PUBLIC UTILITY COMPANIES, SO THAT INTERFERENCE WITH SUCH OTHER WORK WILL BE REDUCED TO A MINIMUM.

160 N.G.S. (U.S.G.S.) BENCH MARKS

DO NOT DISTURB N.G.S. (U.S.G.S.) BENCH MARKS IN ANY MANNER UNLESS DIRECTED BY THE ENGINEER.

165 BEFORE YOU DIG

THE CONTRACTOR IS INSTRUCTED TO CALL 1-800-752-6007 TO REACH KY 811, THE ONE-CALL SYSTEM FOR INFORMATION ON THE LOCATION OF EXISTING UNDERGROUND UTILITIES. THE CALL IS TO BE PLACED A MINIMUM OF TWO (2) AND NO MORE THAN TEN (10) BUSINESS DAYS PRIOR TO EXCAVATION. THE CONTRACTOR SHOULD BE AWARE THAT OWNERS OF UNDERGROUND FACILITIES ARE NOT REQUIRED TO BE MEMBERS OF THE KY 811 ONE-CALL BEFORE-U-DIG (BU-D) SERVICE. THE CONTRACTOR MUST COORDINATE EXCAVATION WITH THE UTILITY OWNERS, INCLUDING THOSE WHOM DO NOT SUBSCRIBE TO KY 811. IT MAY BE NECESSARY FOR THE CONTRACTOR TO CONTACT THE COUNTY COURT CLERK TO DETERMINE WHAT UTILITY COMPANIES HAVE FACILITIES IN THE AREA.

190 DEPARTMENT OF THE ARMY PERMIT AND WATER QUALITY CERTIFICATION APPROVALS

A DEPARTMENT OF THE ARMY (DA) PERMIT, WHICH MAY REQUIRE APPROVAL OF A STATE WATER QUALITY CERTIFICATION FROM THE KENTUCKY DIVISION OF WATER, REGULATES THIS PROJECT AT ONE OR MORE LOCATIONS. PERFORM ALL APPLICABLE WORK IN COMPLIANCE WITH THE CONDITIONS STATED IN THE DA PERMIT AND THE APPROVED WATER QUALITY CERTIFICATION. POST A COPY OF THE DA PERMIT AND THE WATER QUALITY CERTIFICATION IN A CONSPICUOUS PLACE AT THE PROJECT SITE. IF A DA PERMIT OR WATER QUALITY CERTIFICATION APPROVAL IS PENDING, DO NOT WORK IN OR DISTURB THE DESIGNATED AREAS) UNTIL OBTAINING THE APPROPRIATE APPROVAL(S). REFER TO NOTICE(S) CONTAINED IN THE CONTRACT BID PROPOSAL FOR DESIGNATED AREAS) WHERE WORK IS PROHIBITED BY THE ABSENCE OF APPROVAL.

429 WINTER CLOSDOWN

ANY ASPHALT CONCRETE BASE AND/OR SURFACE COURSE USED AS A RIDING SURFACE EXPOSED TO TRAFFIC DURING WINTER CLOSDOWN PERIODS SHALL CONTAIN NATURAL, CONGLOMERATE, CRUSHED SLAG, CRUSHED GRANITE OR CRUSHED SANDSTONE SAND IN THE PROPORTION OF NO LESS THAN 25% OF THE TOTAL COMBINED COARSE AND FINE AGGREGATE.

444 ASPHALT PAVEMENT RIDE QUALITY

PAVEMENT RIDEABILITY REQUIREMENTS, IN ACCORDANCE WITH SECTION 410 OF THE STANDARD SPECIFICATIONS, SHALL APPLY ON THIS PROJECT. CATEGORY "B" SHALL APPLY.

447 COMPACTION OF ASPHALT MIXTURES

WILL ACCEPT THE COMPACTION OF ASPHALT MIXTURES FURNISHED FOR DRIVING LANES AND RAMPS AT ONE INCH (25 MM) OR GREATER ON THIS PROJECT BY OPTION A ACCORDING TO SUBSECTIONS 402 AND 403 OF THE CURRENT STANDARD SPECIFICATIONS. USE JOINT CORES AS DESCRIBED IN SUBSECTION 402.03.02 FOR SURFACE MIXTURES ONLY. WILL ACCEPT THE COMPACTION OF ALL OTHER ASPHALT MIXTURES BY OPTION B.

## GENERAL PROVISIONS (cont.)

455 EDGE KEY

THIS WORK INCLUDES CUTTING OUT THE EXISTING ASPHALT SURFACE TO A MINIMUM DEPTH AND WIDTH AS DETAILED ELSEWHERE IN THE PLANS SO THAT THE NEW SURFACE MAY HEEL INTO THE EXISTING SURFACE. THE CONTRACT UNIT PRICE BID LINEAR FOOT FOR "EDGE KEY" INCLUDES ALL NECESSARY MATERIALS, LABOR AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND DISPOSE OF THE REMOVED ASPHALT MATERIAL.

650 STANDARD DRAWINGS

STANDARD DRAWINGS ARE NOT ATTACHED TO THESE PLANS. A STANDARD DRAWING BOOK AND THE HEADWALL SUPPLEMENTAL BOOK MAY BE OBTAINED FROM THE POLICY SUPPORT BRANCH OF THE DEPARTMENT OF ADMINISTRATIVE SERVICES IN FRANKFORT, KY. AT (502) 564-4610

730 EXISTING LANDSCAPE MATERIAL

DO NOT DISTURB LANDSCAPE PLANTS UNLESS ABSOLUTELY NECESSARY. DO NOT TO DISTURB ANY PLANTS WITHOUT PRIOR APPROVAL OF THE PROJECT ENGINEER. THE PROJECT ENGINEER SHALL NOTIFY THE DISTRICT AGRONOMIST FOR POSSIBLE DEPARTMENT SALVAGE OF ANY PLANTS NEEDING REMOVAL.

## PROJECT SPECIFIC NOTES

### PARCEL 11 DOUBLE BURIAL SITE

DUE TO THE PRESENCE OF A DOUBLE BURIAL, A TWENTY FOOT (20-FT) BUFFER SHALL BE ESTABLISHED AROUND THE EXTANT DOUBLE HEADSTONE LOCATED IN A FORMER SIDE YARD ON PARCEL 11, SOUTHWEST OF KY 727 (5TH STREET ROAD). THE HEADSTONE IS LOCATED AT LATITUDE 36.9103947 AND LONGITUDE -84.152664. NO PROJECT ACTIVITIES SHALL OCCUR WITHIN THIS BUFFER, INCLUDING, BUT NOT LIMITED TO: GROUND DISTURBANCE, EQUIPMENT STAGING, EQUIPMENT MOVEMENT, OR EXCAVATION.

IF PROJECT PLANS CHANGE AND THIS AREA IS TO BE IMPACTED, THE CONTRACTOR SHALL CONTACT JOSHUA HIGGINS, DISTRICT ENVIRONMENTAL COORDINATOR AT 606-598-2145. IN THIS SITUATION, THE BURIALS MAY HAVE TO BE RELOCATED IN ACCORDANCE WITH KYTC HUMAN REMAINS RELOCATION PROCEDURES (ROW 403-4; AUTHORIZED BY 600 KAR 3:020 AND 901 KAR 5:090). THE RELOCATION PROCESS TAKES A MINIMUM OF 60 DAYS TO ACCOMPLISH.

### EXISTING DRAINAGE

EXISTING PIPES AND DRAINAGE STRUCTURES THAT ARE NOT TO BE UTILIZED ARE MARKED FOR REMOVAL. IF THESE ITEMS ARE LOCATED WITHIN THE DISTURBED LIMITS, THEIR REMOVAL SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. IF THESE ITEMS ARE LOCATED OUTSIDE THE DISTURBED LIMITS, THEIR REMOVAL SHALL BE PAID AS QUANTIFIED ON THESE PLAN SHEETS.

### SUBGRADE DRAINAGE

SEE PERFORATED PIPE UNDERDRAIN SYSTEM SUMMARY FOR UNDERDRAIN SYSTEM PIPE SIZES AND TYPE.

### PROPOSED STORM SEWER SYSTEM

FOR PROPOSED DRAINAGE STRUCTURE ELEVATIONS, SEE THE STORM SEWER PROFILE SHEETS.

### TEMPORARY DRAINAGE

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DRAINAGE FOR TEMPORARY ROADWAYS INCLUDING DIVERSIONS AND FRONTAGE ROADS. IF A TEMPORARY PIPE IS NOT SPECIFIED, A MINIMUM OPENING OF AT LEAST 15" DIAMETER SHALL BE UTILIZED.

### EXISTING UTILITIES

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UNDERGROUND UTILITY SERVICE LINES. NO DIRECT PAYMENT WILL BE MADE FOR REPAIR OR REPLACEMENT OF SERVICE LINES. IF A UTILITY LINE IS IN CONFLICT WITH CONSTRUCTION AND CANNOT BE AVOIDED, THE OWNER SHALL BE CONTACTED IMMEDIATELY.

COUNTY OF	ITEM NO.	SHEET NO.
WHITLEY	11-186.00	R002W

## PROJECT SPECIFIC NOTES CONT.

### PIPE REMOVAL / SAFELOADING

REMOVE ALL PIPE THAT ARE ABANDONED, OR NO LONGER IN USE DUE TO THE PROJECT, IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 203 WHETHER THEY ARE IDENTIFIED SPECIFICALLY ON THE PLAN OR NOT. CONTRARY TO SECTION 701, THIS WORK WILL NOT BE MEASURED FOR PAYMENT BUT WILL BE INCIDENTAL TO THE PROJECT, UNLESS SPECIFICALLY CALLED OUT FOR PAYMENT. THE CONTRACTOR MAY ELECT TO SAFELOAD ANY PIPE THAT IS TO BE REMOVED WITH PRIOR WRITTEN APPROVAL FROM THE ENGINEER FOR EACH SPECIFIC LOCATION. SAFELOADING OF PIPE SHALL BE INCIDENTAL TO THE PROJECT UNLESS SPECIFICALLY CALLED OUT FOR PAYMENT IN THE PLANS OR DIRECTED BY THE ENGINEER. IF THE ENGINEER DEEMS IT NECESSARY TO SAFELOAD A PIPE, IN LIEU OF REMOVAL, DUE TO IMPACTS TO TRAFFIC OR FOR OTHER LOCATION SPECIFIC REASONS, THIS WORK SHALL BE PAID AT THE UNIT BID PRICE FOR SAFELOADING.

### TREE REMOVAL

NO CLEARING OF TREES 5 INCHES OR GREATER (DIAMETER BREAST HEIGHT) FROM JUNE 1 THROUGH JULY 31. SEE SPECIAL NOTE FOR TREE REMOVAL

### GRADING BEHIND RETAINING WALLS

THE CONTRACTOR SHALL BE RESPONSIBLE FOR GRADING ALL AREAS BEHIND RETAINING WALLS TO DRAIN TO AVOID TRAPPING WATER BEHIND THE WALL.

### STRIPING REMOVAL

ALL LANE MARKING REMOVAL SHALL BE PERFORMED BY WATERBLASTING IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 713 AND 714, UNLESS SPECIFICALLY CALLED OUT. STRIPING REMOVAL WILL NOT BE MEASURED FOR PAYMENT BUT WILL BE INCIDENTAL TO OTHER ITEMS IN THE CONTRACT.

### PAVEMENT REMOVAL

THIS ITEM SHALL CONSIST OF REMOVING EXISTING PAVEMENT AND BASE COURSES TO A DEPTH OF 12" MINIMUM AND RESHAPING GROUND TO THE ACCEPTANCE OF THE ENGINEER. THIS ITEM SHALL INCLUDE ALL MATERIALS, LABOR AND EQUIPMENT NECESSARY TO COMPLETE PAVEMENT AND BASE REMOVAL & RESHAPE TO THE SATISFACTION OF THE ENGINEER. NO ADDITIONAL PAYMENT WILL BE MADE FOR ANY ITEMS NECESSARY TO COMPLETE THIS WORK. AREAS ARE INCLUDED IN THE "SEEDING AND PROTECTION" QUANTITY.

### GUARDRAIL

CONTRACTOR SHALL INSPECT GUARDRAIL TO BE INSTALLED AT STORM PIPES FOR CONFLICTS.

### GUARDRAIL REMOVAL

SALVAGE EXISTING MATERIAL AS PER SECTION 719.03.07. EXCEPT THAT THE CONTRACTOR SHALL DELIVER EXISTING SALVAGED GUARDRAIL SYSTEM MATERIALS TO THE CENTRAL SIGN SHOP AND RECYCLE CENTER AT 1224 WILKINSON BLVD IN FRANKFORT, KY. CONTACT SECTION SUPERVISOR AT (502)564-8187 TO SCHEDULE THE DELIVERY OF MATERIAL. DELIVER THE MATERIAL BETWEEN THE HOURS OF 8:00 AM AND 3:00 PM, MONDAY THROUGH FRIDAY. REMOVE ANY EXISTING GUARDRAIL WITH A LANE CLOSURE IN PLACE. DO NOT LEAVE UNPROTECTED. AFTER THE GUARDRAIL IS REMOVED, A SHOULDER CLOSURE SHALL REMAIN IN PLACE UNTIL THE GUARDRAIL IS REPLACED IN THAT AREA.

### MATERIAL TRANSFER VEHICLE

A MATERIAL TRANSFER VEHICLE (MTV) SHALL BE REQUIRED FOR ALL PAVING ON THIS JOB IN ACCORDANCE WITH SECTION 403.02.10 AND 403.03.05 OF STANDARD SPECIFICATION, CURRENT EDITION.

### TOPSOIL

STOCKPILE AND SPREAD TOPSOIL FOR USE IN THE MEDIAN AREAS IN ACCORDANCE WITH STANDARD SPECIFICATION 204.03, 212.03.02 B) AND 212.04.03. ADDITIONALLY, IN THE MEDIAN AREAS DESIGNATED FOR TOPSOIL, DO NOT PLACE ANY STONE OR MASONRY FRAGMENT, NOR ANY QUANTITIES OF QUARRIES GRAVEL OR ROCK, WHETHER THEY ARE WITHIN 1 FOOT OF SUBGRADE OR NOT. THE CONTRACTOR MAY STOCKPILE CLEAN SOIL FROM EXCAVATION FOR THIS PURPOSE ONCE ALL TOPSOILS DEEMED TO MEET SECTION 827.10 HAVE BEEN EXHAUSTED, AS DETERMINED BY THE ENGINEER. TOPSOIL MATERIALS MAY BE PLACED DIRECTLY FROM THE EXCAVATION BUT WILL NOT BE MEASURED FOR SEPARATE PAYMENT UNLESS STOCKPILED IN A DESIGNATED AREA FOR MEASUREMENT.

GENERAL NOTES  
US 25W RECONSTRUCTION

SCALE: 1"=N/A

# GENERAL NOTES

## PROPOSAL ATTACHMENTS

### SPECIAL NOTES

- SPECIAL NOTE FOR CONCRETE SEALING
- SPECIAL NOTE FOR PIPELINE INSPECTION
- SPECIAL NOTE FOR NON-TRACKING TACK COAT
- EXPERIMENTAL KYTC AND HAMBURG TESTING (OVER 4,000 TONS ASPH SURF)
- SPECIAL NOTE FOR SPRAY APPLIED THERMOPLASTIC PAVEMENT MARKING MATERIALS

### GENERAL PROVISIONS

THIS PROJECT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "KENTUCKY TRANSPORTATION CABINET/DEPARTMENT OF HIGHWAYS, STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", STANDARD DRAWINGS, MANUALS, GUIDELINES, AND M.U.T.C.D., LATEST EDITIONS, UNLESS OTHERWISE NOTED IN THESE PLANS.

### CONTROL OF WORK

THE CONTRACTOR SHALL CONDUCT HIS OPERATIONS AND COOPERATE WITH OTHER CONTRACTORS, E.G. PUBLIC UTILITY COMPANIES, SO THAT INTERFERENCE WITH SUCH OTHER WORK WILL BE REDUCED TO A MINIMUM.

160 N.G.S. (U.S.G.S.) BENCH MARKS

DO NOT DISTURB N.G.S. (U.S.G.S.) BENCH MARKS IN ANY MANNER UNLESS DIRECTED BY THE ENGINEER.

165 BEFORE YOU DIG

THE CONTRACTOR IS INSTRUCTED TO CALL 1-800-752-6007 TO REACH KY 811, THE ONE-CALL SYSTEM FOR INFORMATION ON THE LOCATION OF EXISTING UNDERGROUND UTILITIES. THE CALL IS TO BE PLACED A MINIMUM OF TWO (2) AND NO MORE THAN TEN (10) BUSINESS DAYS PRIOR TO EXCAVATION. THE CONTRACTOR SHOULD BE AWARE THAT OWNERS OF UNDERGROUND FACILITIES ARE NOT REQUIRED TO BE MEMBERS OF THE KY 811 ONE-CALL BEFORE-U-DIG (BU-D) SERVICE. THE CONTRACTOR MUST COORDINATE EXCAVATION WITH THE UTILITY OWNERS, INCLUDING THOSE WHOM DO NOT SUBSCRIBE TO KY 811. IT MAY BE NECESSARY FOR THE CONTRACTOR TO CONTACT THE COUNTY COURT CLERK TO DETERMINE WHAT UTILITY COMPANIES HAVE FACILITIES IN THE AREA.

190 DEPARTMENT OF THE ARMY PERMIT AND WATER QUALITY CERTIFICATION APPROVALS

A DEPARTMENT OF THE ARMY (DA) PERMIT, WHICH MAY REQUIRE APPROVAL OF A STATE WATER QUALITY CERTIFICATION FROM THE KENTUCKY DIVISION OF WATER, REGULATES THIS PROJECT AT ONE OR MORE LOCATIONS. PERFORM ALL APPLICABLE WORK IN COMPLIANCE WITH THE CONDITIONS STATED IN THE DA PERMIT AND THE APPROVED WATER QUALITY CERTIFICATION. POST A COPY OF THE DA PERMIT AND THE WATER QUALITY CERTIFICATION IN A CONSPICUOUS PLACE AT THE PROJECT SITE. IF A DA PERMIT OR WATER QUALITY CERTIFICATION APPROVAL IS PENDING, DO NOT WORK IN OR DISTURB THE DESIGNATED AREAS) UNTIL OBTAINING THE APPROPRIATE APPROVAL(S). REFER TO NOTICE(S) CONTAINED IN THE CONTRACT BID PROPOSAL FOR DESIGNATED AREAS) WHERE WORK IS PROHIBITED BY THE ABSENCE OF APPROVAL.

429 WINTER CLOSEDOWN

ANY ASPHALT CONCRETE BASE AND/OR SURFACE COURSE USED AS A RIDING SURFACE EXPOSED TO TRAFFIC DURING WINTER CLOSEDOWN PERIODS SHALL CONTAIN NATURAL, CONGLOMERATE, CRUSHED SLAG, CRUSHED GRANITE OR CRUSH SANDSTONE SAND IN THE PROPORTION OF NO LESS THAN 25% OF THE TOTAL COMBINED COARSE AND FINE AGGREGATE.

444 ASPHALT PAVEMENT RIDE QUALITY

PAVEMENT RIDEABILITY REQUIREMENTS, IN ACCORDANCE WITH SECTION 410 OF THE STANDARD SPECIFICATIONS, SHALL APPLY ON THIS PROJECT. CATEGORY B SHALL APPLY.

447 COMPACTION OF ASPHALT MIXTURES

WILL ACCEPT THE COMPACTION OF ASPHALT MIXTURES FURNISHED FOR DRIVING LANES AND RAMPS AT ONE INCH (25 MM) OR GREATER ON THIS PROJECT BY OPTION A ACCORDING TO SUBSECTIONS 402 AND 403 OF THE CURRENT STANDARD SPECIFICATIONS. USE JOINT CORES AS DESCRIBED IN SUBSECTION 402.03.02 FOR SURFACE MIXTURES ONLY. WILL ACCEPT THE COMPACTION OF ALL OTHER ASPHALT MIXTURES BY OPTION B.

## GENERAL PROVISIONS (cont.)

455 EDGE KEY

THIS WORK INCLUDES CUTTING OUT THE EXISTING ASPHALT SURFACE TO A MINIMUM DEPTH AND WIDTH AS DETAILED ELSEWHERE IN THE PLANS SO THAT THE NEW SURFACE MAY HEEL INTO THE EXISTING SURFACE. THE CONTRACT UNIT PRICE BID LINEAR FOOT FOR "EDGE KEY" INCLUDES ALL NECESSARY MATERIALS, LABOR AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND DISPOSE OF THE REMOVED ASPHALT MATERIAL.

650 STANDARD DRAWINGS

STANDARD DRAWINGS ARE NOT ATTACHED TO THESE PLANS. A STANDARD DRAWING BOOK AND THE HEADWALL SUPPLEMENTAL BOOK MAY BE OBTAINED FROM THE POLICY SUPPORT BRANCH OF THE DEPARTMENT OF ADMINISTRATIVE SERVICES IN FRANKFORT, KY. AT (502) 564-4610

730 EXISTING LANDSCAPE MATERIAL

DO NOT DISTURB LANDSCAPE PLANTS UNLESS ABSOLUTELY NECESSARY. DO NOT TO DISTURB ANY PLANTS WITHOUT PRIOR APPROVAL OF THE PROJECT ENGINEER. THE PROJECT ENGINEER SHALL NOTIFY THE DISTRICT AGRONOMIST FOR POSSIBLE DEPARTMENT SALVAGE OF ANY PLANTS NEEDING REMOVAL.

## PROJECT SPECIFIC NOTES

### PARCEL 11 DOUBLE BURIAL SITE

DUE TO THE PRESENCE OF A DOUBLE BURIAL, A TWENTY FOOT (20-FT) BUFFER SHALL BE ESTABLISHED AROUND THE EXTANT DOUBLE HEADSTONE LOCATED IN A FORMER SIDE YARD ON PARCEL 11, SOUTHWEST OF KY 727 (5TH STREET ROAD). THE HEADSTONE IS LOCATED AT LATITUDE 36.9103947 AND LONGITUDE -84.152664. NO PROJECT ACTIVITIES SHALL OCCUR WITHIN THIS BUFFER, INCLUDING, BUT NOT LIMITED TO: GROUND DISTURBANCE, EQUIPMENT STAGING, EQUIPMENT MOVEMENT, OR EXCAVATION.

IF PROJECT PLANS CHANGE AND THIS AREA IS TO BE IMPACTED, THE CONTRACTOR SHALL CONTACT JOSHUA HIGGINS, DISTRICT ENVIRONMENTAL COORDINATOR AT 606-598-2145. IN THIS SITUATION, THE BURIALS MAY HAVE TO BE RELOCATED IN ACCORDANCE WITH KYTC HUMAN REMAINS RELOCATION PROCEDURES (ROW 403-4; AUTHORIZED BY 600 KAR 3:020 AND 901 KAR 5:090). THE RELOCATION PROCESS TAKES A MINIMUM OF 60 DAYS TO ACCOMPLISH.

### EXISTING DRAINAGE

EXISTING PIPES AND DRAINAGE STRUCTURES THAT ARE NOT TO BE UTILIZED ARE MARKED FOR REMOVAL. IF THESE ITEMS ARE LOCATED WITHIN THE DISTURBED LIMITS, THEIR REMOVAL SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. IF THESE ITEMS ARE LOCATED OUTSIDE THE DISTURBED LIMITS, THEIR REMOVAL SHALL BE PAID AS QUANTIFIED ON THESE PLAN SHEETS.

### SUBGRADE DRAINAGE

SEE PERFORATED PIPE UNDERDRAIN SYSTEM SUMMARY FOR UNDERDRAIN SYSTEM PIPE SIZES AND TYPE.

### PROPOSED STORM SEWER SYSTEM

FOR PROPOSED DRAINAGE STRUCTURE ELEVATIONS, SEE THE STORM SEWER PROFILE SHEETS.

### TEMPORARY DRAINAGE

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DRAINAGE FOR TEMPORARY ROADWAYS INCLUDING DIVERSIONS AND FRONTAGE ROADS. IF A TEMPORARY PIPE IS NOT SPECIFIED, A MINIMUM OPENING OF AT LEAST 15" DIAMETER SHALL BE UTILIZED.

### EXISTING UTILITIES

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UNDERGROUND UTILITY SERVICE LINES. NO DIRECT PAYMENT WILL BE MADE FOR REPAIR OR REPLACEMENT OF SERVICE LINES. IF A UTILITY LINE IS IN CONFLICT WITH CONSTRUCTION AND CANNOT BE AVOIDED, THE OWNER SHALL BE CONTACTED IMMEDIATELY.

COUNTY OF	ITEM NO.	SHEET NO.
WHITLEY	11-186.00	R002W

REVISED 09-20-22

## PROJECT SPECIFIC NOTES (CONT.)

### PIPE REMOVAL / SAFELOADING

REMOVE ALL PIPE THAT ARE ABANDONED, OR NO LONGER IN USE DUE TO THE PROJECT, IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 203 WHETHER THEY ARE IDENTIFIED SPECIFICALLY ON THE PLAN OR NOT. CONTRARY TO SECTION 701, THIS WORK WILL NOT BE MEASURED FOR PAYMENT BUT WILL BE INCIDENTAL TO THE PROJECT, UNLESS SPECIFICALLY CALLED OUT FOR PAYMENT. THE CONTRACTOR MAY ELECT TO SAFELOAD ANY PIPE THAT IS TO BE REMOVED WITH PRIOR WRITTEN APPROVAL FROM THE ENGINEER FOR EACH SPECIFIC LOCATION. SAFELOADING OF PIPE SHALL BE INCIDENTAL TO THE PROJECT UNLESS SPECIFICALLY CALLED OUT FOR PAYMENT IN THE PLANS OR DIRECTED BY THE ENGINEER. IF THE ENGINEER DEEMS IT NECESSARY TO SAFELOAD A PIPE, IN LIEU OF REMOVAL, DUE TO IMPACTS TO TRAFFIC OR FOR OTHER LOCATION SPECIFIC REASONS, THIS WORK SHALL BE PAID AT THE UNIT BID PRICE FOR SAFELOADING.

### TREE REMOVAL

NO CLEARING OF TREES 5 INCHES OR GREATER (DIAMETER BREAST HEIGHT) FROM JUNE 1 THROUGH JULY 31. SEE SPECIAL NOTE FOR TREE REMOVAL

### GRADING BEHIND RETAINING WALLS

THE CONTRACTOR SHALL BE RESPONSIBLE FOR GRADING ALL AREAS BEHIND RETAINING WALLS TO DRAIN TO AVOID TRAPPING WATER BEHIND THE WALL.

### STRIPING REMOVAL

ALL LANE MARKING REMOVAL SHALL BE PERFORMED BY WATERBLASTING IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 713 AND 714, UNLESS SPECIFICALLY CALLED OUT. STRIPING REMOVAL WILL NOT BE MEASURED FOR PAYMENT BUT WILL BE INCIDENTAL TO OTHER ITEMS IN THE CONTRACT.

### PAVEMENT REMOVAL

THIS ITEM SHALL CONSIST OF REMOVING EXISTING PAVEMENT AND BASE COURSES TO A DEPTH OF 12" MINIMUM AND RESHAPING GROUND TO THE ACCEPTANCE OF THE ENGINEER. THIS ITEM SHALL INCLUDE ALL MATERIALS, LABOR AND EQUIPMENT NECESSARY TO COMPLETE PAVEMENT AND BASE REMOVAL & RESHAPE TO THE SATISFACTION OF THE ENGINEER. NO ADDITIONAL PAYMENT WILL BE MADE FOR ANY ITEMS NECESSARY TO COMPLETE THIS WORK. AREAS ARE INCLUDED IN THE "SEEDING AND PROTECTION" QUANTITY.

### GUARDRAIL

CONTRACTOR SHALL INSPECT GUARDRAIL TO BE INSTALLED AT STORM PIPES FOR CONFLICTS.

### GUARDRAIL REMOVAL

SALVAGE EXISTING MATERIAL AS PER SECTION 719.03.07. EXCEPT THAT THE CONTRACTOR SHALL DELIVER EXISTING SALVAGED GUARDRAIL SYSTEM MATERIALS TO THE CENTRAL SIGN SHOP AND RECYCLE CENTER AT 1224 WILKINSON BLVD IN FRANKFORT, KY. CONTACT SECTION SUPERVISOR AT (502)564-8187 TO SCHEDULE THE DELIVERY OF MATERIAL. DELIVER THE MATERIAL BETWEEN THE HOURS OF 8:00 AM AND 3:00 PM, MONDAY THROUGH FRIDAY. REMOVE ANY EXISTING GUARDRAIL WITH A LANE CLOSURE IN PLACE. DO NOT LEAVE UNPROTECTED. AFTER THE GUARDRAIL IS REMOVED, A SHOULDER CLOSURE SHALL REMAIN IN PLACE UNTIL THE GUARDRAIL IS REPLACED IN THAT AREA.

### MATERIAL TRANSFER VEHICLE

A MATERIAL TRANSFER VEHICLE (MTV) SHALL BE REQUIRED FOR ALL PAVING ON THIS JOB IN ACCORDANCE WITH SECTION 403.02.10 AND 403.03.05 OF STANDARD SPECIFICATION, CURRENT EDITION.

### TOPSOIL

STOCKPILE AND SPREAD TOPSOIL FOR USE IN THE MEDIAN AREAS IN ACCORDANCE WITH STANDARD SPECIFICATION 204.03, 212.03.02 B) AND 212.04.03. ADDITIONALLY, IN THE MEDIAN AREAS DESIGNATED FOR TOPSOIL, DO NOT PLACE ANY STONE OR MASONRY FRAGMENT, NOR ANY QUANTITIES OF QUARRIES GRAVEL OR ROCK, WHETHER THEY ARE WITHIN 1 FOOT OF SUBGRADE OR NOT. THE CONTRACTOR MAY STOCKPILE CLEAN SOIL FROM EXCAVATION FOR THIS PURPOSE ONCE ALL TOPSOILS DEEMED TO MEET SECTION 827.10 HAVE BEEN EXHAUSTED, AS DETERMINED BY THE ENGINEER. TOPSOIL MATERIALS MAY BE PLACED DIRECTLY FROM THE EXCAVATION BUT WILL NOT BE MEASURED FOR SEPARATE PAYMENT UNLESS STOCKPILED IN A DESIGNATED AREA FOR MEASUREMENT.

GENERAL NOTES  
US 25W RECONSTRUCTION

SCALE: 1"=N/A

FILE NAME: G:\1483\WHIT-US25W\PHASE 2\SHEETS\GENERAL NOTES\R0020WN.DGN

DATE PLOTTED: September 20, 2022

USER: jsungantz

F-SHEET NAME:

MicroStation v8.11.7.443