



Matthew G. Bevin
Governor

**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Greg Thomas
Secretary

July 15, 2019

CALL NO. 102
CONTRACT ID NO. 191227
ADDENDUM # 1

Subject: MCCRACKEN COUNTY, STP 3015 (028)
Letting July 26, 2019

- (1) Revised - General Summary - Page 20 of 190
- (2) Revised - Paving Summary - Page 23 of 190
- (3) Revised - Proposal Bid Items - Pages 189-190 of 190

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

GENERAL SUMMARY							
US 45 - MCCRACKEN COUNTY - ITEM NO. 1-20019.00							
BID CODE	ITEM	UNIT	NOTE	QUANTITIES			
				US 45			
00001	DGA	TON		1,221			
00190	LEVELING AND WEDGING PG64-22	TON		94			
00214	CL3 ASPH BASE 1.00D PG64-22	TON		1,076			
00324	CL3 ASPH SURF 0.50B PG64-22	TON		1,473			
00358	ASPHALT CURING SEAL	TON		6.5			
01791	ADJUST MANHOLE LID TO GRADE	EACH		4			
01810	STANDARD CURB AND GUTTER	LF		4,163			
01812	REMOVE CURB AND GUTTER	LF	7	4,163			
02014	BARRICADE-TYPE III	EACH		7			
02058	REMOVE PCC PAVEMENT	SY	2	243			
02091	REMOVE PAVEMENT	SY	6	475			
02101	CEM CONC ENT PAVEMENT - 8 IN	SY		475			
02200	ROADWAY EXCAVATION	CUYD	10	1,557			
02542	CEMENT	TON		186.7			
02562	TEMPORARY SIGNS	SF	3	500			
02569	DEMOBILIZATION	LS		1			
02585	EDGE KEY	LF		167			
02650	MAINTAIN AND CONTROL TRAFFIC	LS		1			
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	3	8			
02676	MOBILIZATION FOR MILL & TEXT	LS		1			
02677	ASPHALT MILLING & TEXTURING	TON	12	1,642			
02702	SAND FOR BLOTTER	TON		16.3			
02721	REMOVE CONCRETE SIDEWALK	SY	8	72			
02726	STAKING	LS		1			
02775	ARROW PANEL	EACH	3	2			
04953	TEMP RELOCATION OF SIGNAL HEAD	EACH	3	8			
05990	SODDING	SY		4,696			
06406	SBM ALUM SHEET SIGNS .080 IN	SF	9	18			
06410	STEEL POST TYPE 1	LF	9	60			
06510	PAVE STRIPING - TEMP PAINT - 4 IN	LF	3	7,260			
06549	PAVE STRIPING-TEMP REM TAPE-B	LF	3	500			
06550	PAVE STRIPING-TEMP REM TAPE-W	LF	3	4,840			
06551	PAVE STRIPING-TEMP REM TAPE-Y	LF	3	4,840			
06566	PAVE MARKING - THERMO X-WALK - 12 IN	LF		293			
06568	PAVE MARKING - THERMO STOP BAR - 24 IN	LF		234			
06574	PAVE MARKING - THERMO CURV ARROW	EACH		24			
06575	PAVE MARKING - THERMO COMB ARROW	EACH		4			
20071EC	JOINT ADHESIVE	LF		7,245			

PAVING SUMMARY							
US 45 - MCCracken County - Item No. 1-20019.00							
ITEM CODE	ITEM	NOTES	UNIT	US 45			
00001	DGA	1	TON	1,221			
00190	LEVELING AND WEDGING PG64-22	2,8	TON	94			
00214	CL3 ASPH BASE 1.00D PG64-22	2	TON	1,076			
00324	CL3 ASPH SURF 0.50B PG64-22	2	TON	1,473			
00358	ASPHALT CURING SEAL	3	TON	6.5			
02101	CEM CONC ENT PAVEMENT - 8 INCH		SY	475			
02542	CEMENT	4	TON	186.7			
02677	ASPHALT MILLING AND TEXTURING		TON	1,642			
02702	SAND FOR BLOTTER	6	TON	16.3			
20071EC	JOINT ADHESIVE		LF	7,245			
24781EC	INTELLIGENT COMPACTION FOR ASPHALT	2	TON	2,549			
24785EC	FIBER REINFORCEMENT FOR HMA	2	TON	2,549			
24891EC	PAVE MOUNTED INFRARED TEMP EQUIPMENT		SF	179,216			
24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	5	TON	2.7			
24936EC	FULL DEPTH RECLAMATION WITH CEMENT		SY	6,522			

NOTES:

1. Estimated at 115 lbs. per sq. yd. per inch of depth.
2. Estimated at 110 lbs. per sq. yd. per inch of depth.
3. Estimated at 2 lbs per sq. yd.
4. Estimated at 6% by weight, using an average dry density of 106lbs/Cubic foot.
5. Estimated at 0.84 lbs. per sq. yd.
6. Estimated at 5 lbs. per sq. yd.
7. Quantities are carried over and included in General Summary.
8. For areas that experience scabbing after pavement is milled, and for any settlement of pavement failure repairs.

PROPOSAL BID ITEMS

191227

Page 1 of 2

Report Date 7/15/19

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	1,221.00	TON		\$	
0020	00190		LEVELING & WEDGING PG64-22	94.00	TON		\$	
0030	00214		CL3 ASPH BASE 1.00D PG64-22	1,076.00	TON		\$	
0040	00324		CL3 ASPH SURF 0.50B PG64-22	1,473.00	TON		\$	
0050	00358		ASPHALT CURING SEAL	6.50	TON		\$	
0060	02101		CEM CONC ENT PAVEMENT-8 IN	475.00	SQYD		\$	
0070	02542		CEMENT (REVISED: 7-15-19)	186.70	TON		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	1,642.00	TON		\$	
0090	02702		SAND FOR BLOTTER	16.30	TON		\$	
0100	20071EC		JOINT ADHESIVE	7,245.00	LF		\$	
0110	24781EC		INTELLIGENT COMPACTION FOR ASPHALT	2,549.00	TON		\$	
0120	24785EC		FIBER REINFORCEMENT FOR HMA	2,549.00	TON		\$	
0130	24891EC		PAVE MOUNT INFRARED TEMP EQUIPMENT	179,216.00	SF		\$	
0140	24936EC		FULL DEPTH RECLAMATION WITH CEMENT	6,522.00	SQYD		\$	
0150	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	2.70	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0160	01791		ADJUST MANHOLE FRAME TO GRADE	4.00	EACH		\$	
0170	01810		STANDARD CURB AND GUTTER	4,163.00	LF		\$	
0180	01812		REMOVE CURB AND GUTTER	4,163.00	LF		\$	
0190	02014		BARRICADE-TYPE III	7.00	EACH		\$	
0200	02058		REMOVE PCC PAVEMENT	243.00	SQYD		\$	
0210	02091		REMOVE PAVEMENT	475.00	SQYD		\$	
0220	02200		ROADWAY EXCAVATION	1,557.00	CUYD		\$	
0230	02562		TEMPORARY SIGNS	500.00	SQFT		\$	
0240	02585		EDGE KEY	167.00	LF		\$	
0250	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0260	02671		PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH		\$	
0270	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0280	02721		REMOVE CONCRETE SIDEWALK	72.00	SQYD		\$	
0290	02726		STAKING	1.00	LS		\$	
0300	02775		ARROW PANEL	2.00	EACH		\$	
0310	04953		TEMP RELOCATION OF SIGNAL HEAD	8.00	EACH		\$	
0320	05990		SODDING	4,696.00	SQYD		\$	
0330	06406		SBM ALUM SHEET SIGNS .080 IN	18.00	SQFT		\$	
0340	06410		STEEL POST TYPE 1	60.00	LF		\$	
0350	06510		PAVE STRIPING-TEMP PAINT-4 IN	7,260.00	LF		\$	
0360	06549		PAVE STRIPING-TEMP REM TAPE-B	500.00	LF		\$	
0370	06550		PAVE STRIPING-TEMP REM TAPE-W	4,840.00	LF		\$	
0380	06551		PAVE STRIPING-TEMP REM TAPE-Y	4,840.00	LF		\$	
0390	06566		PAVE MARKING-THERMO X-WALK-12 IN	293.00	LF		\$	
0400	06568		PAVE MARKING-THERMO STOP BAR-24IN	234.00	LF		\$	

PROPOSAL BID ITEMS

191227

Page 2 of 2

Report Date 7/15/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0410	06574		PAVE MARKING-THERMO CURV ARROW	24.00	EACH		\$	
0420	06575		PAVE MARKING-THERMO COMB ARROW	4.00	EACH		\$	
0430	20099ES842		PAVE MARK TEMP PAINT STOP BAR	33.00	LF		\$	
0440	20194ED		REMOVE & RESET TRAFFIC SIGN	25.00	EACH		\$	
0450	20430ED		SAW CUT	627.00	LF		\$	
0460	20757ED		PAVEMENT REPAIR	42.00	SQYD		\$	
0470	20782NS714		PAVE MARKING THERMO-BIKE	36.00	EACH		\$	
0480	20870ND		REMOVE AND RESET HISTORIC MARKERS	1.00	EACH		\$	
0490	20904ED		RECONSTRUCT CURB BOX INLET	13.00	EACH		\$	
0500	24386EC		PAVE MARKING THERMO-BIKE LANE ARROW	36.00	EACH		\$	
0510	24489EC		INLAID PAVEMENT MARKER	101.00	EACH		\$	
0520	24631EC		BARCODE SIGN INVENTORY	6.00	EACH		\$	
0530	24986EC		HMA ELECTRONIC DELIVERY MGMT SYSTEM	1.00	L S		\$	
0540	24995EC		PAVE STRIPING-SPRAY THERMO-6 IN W	4,557.00	LF		\$	
0550	24996EC		PAVE STRIPING-SPRAY THERMO-6 IN Y	4,980.00	LF		\$	

Section: 0003 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0560	04792		CONDUIT-1 IN	10.00	LF		\$	
0570	04811		ELECTRICAL JUNCTION BOX TYPE B	2.00	EACH		\$	
0580	04820		TRENCHING AND BACKFILLING	30.00	LF		\$	
0590	04830		LOOP WIRE	1,320.00	LF		\$	
0600	04850		CABLE-NO. 14/1 PAIR	100.00	LF		\$	
0610	04895		LOOP SAW SLOT AND FILL	516.00	LF		\$	
0620	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	30.00	LF		\$	
0630	24963ED		LOOP TEST	4.00	EACH		\$	

Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0640	02569		DEMOBILIZATION	1.00	LS		\$	