



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

February 5, 2013

CALL NO. 102
CONTRACT ID NO. 131008
ADDENDUM # 1

Subject: Shelby County, NH 0642 (184)
Letting February 22, 2015

- (1) Revised - Plan Sheet - R2D
- (2) Revised - Bid Items - Pages 81-84 of 84

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

GENERAL SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
SHELBY	5-65.25	R2d

PREPARED BY _____ DATE _____
 CHECKED BY _____ DATE _____
 APPROVED BY _____ DATE _____

ITEM	DESCRIPTION	UNIT	KY 1848	RAMP 1	RAMP 3	RAMP 5	RAMP 7											PROJECT TOTALS
2230	EMBANKMENT IN PLACE ③	CU. YD.																29326
2223	GRANULAR EMBANKMENT ⑥	CU. YD.	14479															14479
2545	CLEARING AND GRUBBING ①	LS																1
2726	STAKING	LS																1
23143ED	K.P.D.E.S. PERMIT AND TEMP. EROSION CONTROL	LS																1
2599	FABRIC - GEOTEXTILE TYPE IV ⑦	SQ. YD.	32294															32294
5950	EROSION CONTROL BLANKET ②	SQ. YD.	2330	5800		7412	578											16120
5966	TOPDRESSING FERTILIZER	TON	1.1	0.3	0.4	0.4	0.4											2.6
5985	SEEDING AND PROTECTION	SQ. YD.	21989	6114	7734	6993	7613											50443
1310	REMOVE PIPE ④	LF	8	4		4												16
2625	REMOVE HEADWALL ④	EACH	2	1		1												4
2265	REMOVE FENCE	LF				814												814
2381	REMOVE GUARDRAIL	LF	1405	337.5		250												1992.5
2091	REMOVE PAVEMENT	SQ. YD.	167															167
2429	RIGHT OF WAY MONUMENT	LF	7															7
2262	FENCE - WOVEN WIRE TYPE 1	LF	621			814												1435
2483	CHANNEL LINING CLASS II	TON	1555		328	365												2248
2484	CHANNEL LINING CLASS III	TON		1018														1018
2562	SIGNS	SQ. FT.	330															330
2775	ARROW PANEL ⑤	EACH	2															2
2650	MAINTAIN & CONTROL TRAFFIC	LS																1
2671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2															2
2676	MOBILIZATION FOR MILL & TEXT	LS	1															1
2677	ASPHALT PAVE MILLING & TEXTURING	TON	60															60
2585	EDGE KEY	LF	78	25	25	25	25											178
6417	FLEXIBLE DELINEATOR POSTS - W	EACH		8	13	8	14											43
6418	FLEXIBLE DELINEATOR POSTS - Y	EACH		11	12	8	2											33
2351	GUARDRAIL - STEEL 'W' BEAM - SINGLE FACE	LF	1619	685	96	262.5	225											2887.5
1982	DELINEATOR FOR GUARDRAIL - MW	EACH	16				3											19
1983	DELINEATOR FOR GUARDRAIL - MY	EACH		4		5												9
2367	GUARDRAIL END TREATMENT TYPE 1	EACH	1	1														2
2363	GUARDRAIL TO BRIDGE CONNECTION TYPE A	EACH	2															2
2369	GUARDRAIL END TREATMENT TYPE 2A	EACH			1		1											2
2360	GUARDRAIL TERMINAL SECTION NO. 1	EACH	5															5
2391	GUARDRAIL END TREATMENT TYPE 4A ②	EACH				1												1
2014	BARRICADE TYPE III ⑤	EACH	4															4
1917	STANDARD BARRIER MEDIAN TYPE 2	SQ. YD.	586															586
1937	MOUNTABLE MEDIAN TYPE 2	SQ. YD.	235															235
2696	MILLED RUMBLE STRIPS	LF	5306	1590	1635	1294	1658											11483
21370ED	LONGITUDINAL SAW CUT	LF	820	740	760	1240	755											4315
23131ER70I	PIPELINE VIDEO INSPECTION	LF	250															250
265I	DIVERSION - KY 1848	L.S.																1
1002ONS	FUEL ADJUSTMENT	DOLLAR																18593
1003ONS	ASPHALT ADJUSTMENT	DOLLAR																30339
2568	MOBILIZATION	LS																1
2569	DEMOBILIZATION	LS																1

NOTES:

- ① APPROX. 10.4 ACRES
- ② INCLUDES 14,453 S.Y. FOR SLOPES 3:1 OR GREATER
- ③ INCLUDES 5,287 C.Y. FOR EMB BCH.
- ④ QUANTITIES CARRIED OVER FROM PIPE SUMMARY SHEET
- ⑤ TO BE USED AS DIRECTED BY THE ENGINEER
- ⑥ FOR ROCK ROADBED CONSTRUCTION
- ⑦ FOR WRAPPING ROCK ROADBED

EARTHWORK BALANCE TOTAL PROJECT

COM -	16766 C.Y.
DT. LT. -	2093 C.Y.
DT. RT. -	999 C.Y.
EMB BCH. -	5287 C.Y.
TOTAL EXC.	25145 C.Y.
EMB -	20527 C.Y.
EMB (ENTR.& APPR.) -	3512 C.Y.
EMB BCH. -	5287 C.Y.
GRAN EMB -	14479 C.Y.
TOTAL EMB.	43805 C.Y.

FOR SIGNAL QUANTITIES SEE SIGNAL PLANS

FOR SIGNING QUANTITIES SEE SIGNING SHEETS

FOR LIGHTING QUANTITIES SEE LIGHTING PLANS

FOR PAVING QUANTITIES - SEE PAVING SUMMARY SHEET

FOR PIPE DRAINAGE QUANTITIES - SEE PIPE DRAINAGE SUMMARY SHEETS

GENERAL SUMMARY

GENERAL SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
SHELBY	5-65.25	R2d

PREPARED BY _____ DATE _____
 CHECKED BY _____ DATE _____
 APPROVED BY _____ DATE _____

ITEM	DESCRIPTION	UNIT	KY 1848	RAMP 1	RAMP 3	RAMP 5	RAMP 7											PROJECT TOTALS
2230	EMBANKMENT IN PLACE ③	CU. YD.																29326
2223	GRANULAR EMBANKMENT ⑥	CU. YD.	14479															14479
2545	CLEARING AND GRUBBING ①	LS																1
2726	STAKING	LS																1
23143ED	K.P.D.E.S. PERMIT AND TEMP. EROSION CONTROL	LS																1
2599	FABRIC - GEOTEXTILE TYPE IV ⑦	SQ. YD.	32294															32294
5950	EROSION CONTROL BLANKET ②	SQ. YD.	2330	5800		7412	578											16120
5966	TOPDRESSING FERTILIZER	TON	1.1	0.3	0.4	0.4	0.4											2.6
5985	SEEDING AND PROTECTION	SQ. YD.	21989	6114	7734	6993	7613											50443
1310	REMOVE PIPE ④	LF	8	4		4												16
2625	REMOVE HEADWALL ④	EACH	2	1		1												4
2265	REMOVE FENCE	LF				814												814
2381	REMOVE GUARDRAIL	LF	1405	337.5		250												1992.5
2091	REMOVE PAVEMENT	SQ. YD.	167															167
2429	RIGHT OF WAY MONUMENT	LF	7															7
2262	FENCE - WOVEN WIRE TYPE 1	LF	621			814												1435
2483	CHANNEL LINING CLASS II	TON	1555		328	365												2248
2484	CHANNEL LINING CLASS III	TON		1018														1018
2562	SIGNS	SQ. FT.	330															330
2775	ARROW PANEL ⑤	EACH	2															2
2650	MAINTAIN & CONTROL TRAFFIC	LS																1
2671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2															2
2676	MOBILIZATION FOR MILL & TEXT	LS	1															1
2677	ASPHALT PAVE MILLING & TEXTURING	TON	60															60
2585	EDGE KEY	LF	78	25	25	25	25											178
6417	FLEXIBLE DELINEATOR POSTS - W	EACH		8	13	8	14											43
6418	FLEXIBLE DELINEATOR POSTS - Y	EACH		11	12	8	2											33
2351	GUARDRAIL - STEEL 'W' BEAM - SINGLE FACE	LF	1619	685	96	262.5	225											2887.5
1982	DELINEATOR FOR GUARDRAIL - MW	EACH	16				3											19
1983	DELINEATOR FOR GUARDRAIL - MY	EACH		4		5												9
2367	GUARDRAIL END TREATMENT TYPE 1	EACH	1	1														2
2363	GUARDRAIL TO BRIDGE CONNECTION TYPE A	EACH	2															2
2369	GUARDRAIL END TREATMENT TYPE 2A	EACH			1		1											2
2360	GUARDRAIL TERMINAL SECTION NO. 1	EACH	5															5
2391	GUARDRAIL END TREATMENT TYPE 4A ②	EACH				1												1
2014	BARRICADE TYPE III ⑤	EACH	4															4
1917	STANDARD BARRIER MEDIAN TYPE 2	SQ. YD.	586															586
1937	MOUNTABLE MEDIAN TYPE 2	SQ. YD.	235															235
2696	MILLED RUMBLE STRIPS	LF	5306	1590	1635	1294	1658											11483
2137OED	LONGITUDINAL SAW CUT	LF	820	740	760	1240	755											4315
23131ER70I	PIPELINE VIDEO INSPECTION	LF	250															250
265I	DIVERSION - KY 1848	L.S.																1
1002ONS	FUEL ADJUSTMENT	DOLLAR																18593
1003ONS	ASPHALT ADJUSTMENT	DOLLAR																30339
2568	MOBILIZATION	LS																1
2569	DEMOBILIZATION	LS																1

NOTES:

▲ REVISED 2-4-13

- ① APPROX. 10.4 ACRES
- ② INCLUDES 14,453 S.Y. FOR SLOPES 3:1 OR GREATER
- ③ INCLUDES 5,287 C.Y. FOR EMB BCH.
- ④ QUANTITIES CARRIED OVER FROM PIPE SUMMARY SHEET
- ⑤ TO BE USED AS DIRECTED BY THE ENGINEER
- ⑥ FOR ROCK ROADBED CONSTRUCTION
- ⑦ FOR WRAPPING ROCK ROADBED

EARTHWORK BALANCE TOTAL PROJECT

COM - 16766 C.Y.
 DT. LT. - 2093 C.Y.
 DT. RT. - 999 C.Y.
 EMB BCH. - 5287 C.Y.
 TOTAL EXC. 25145 C.Y.

 EMB - 20527 C.Y.
 EMB (ENTR.& APPR.) - 3512 C.Y.
 EMB BCH. - 5287 C.Y.
 GRAN EMB - 14479 C.Y.
 TOTAL EMB. 43805 C.Y.

FOR SIGNAL QUANTITIES SEE SIGNAL PLANS

FOR SIGNING QUANTITIES SEE SIGNING SHEETS

FOR LIGHTING QUANTITIES SEE LIGHTING PLANS

FOR PAVING QUANTITIES - SEE PAVING SUMMARY SHEET

FOR PIPE DRAINAGE QUANTITIES - SEE PIPE DRAINAGE SUMMARY SHEETS

GENERAL SUMMARY

PROPOSAL BID ITEMS

Report Date 2/5/13

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0010	00001		DGA BASE	12,181.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	83.10	TON		\$	
0030	00103		ASPHALT SEAL COAT	10.00	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	913.00	TON		\$	
0050	00214		CL3 ASPH BASE 1.00D PG64-22	8,155.00	TON		\$	
0060	00217		CL4 ASPH BASE 1.00D PG64-22	4,969.00	TON		\$	
0070	00339		CL3 ASPH SURF 0.38D PG64-22	1,753.00	TON		\$	
0080	00342		CL4 ASPH SURF 0.38A PG76-22	1,065.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0090	01917		STANDARD BARRIER MEDIAN TYPE 2	586.00	SQYD		\$	
0100	01937		MOUNTABLE MEDIAN TYPE 2	235.00	SQYD		\$	
0110	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	19.00	EACH		\$	
0120	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	9.00	EACH		\$	
0130	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0140	02091		REMOVE PAVEMENT	167.00	SQYD		\$	
0150	02223		GRANULAR EMBANKMENT	14,479.00	CUYD		\$	
0160	02230		EMBANKMENT IN PLACE	29,326.00	CUYD		\$	
0170	02262		FENCE-WOVEN WIRE TYPE 1	1,435.00	LF		\$	
0180	02265		REMOVE FENCE	814.00	LF		\$	
0190	02351		GUARDRAIL-STEEL W BEAM-S FACE	2,887.50	LF		\$	
0200	02360		GUARDRAIL TERMINAL SECTION NO 1	5.00	EACH		\$	
0210	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	2.00	EACH		\$	
0220	02367		GUARDRAIL END TREATMENT TYPE 1	2.00	EACH		\$	
0230	02369		GUARDRAIL END TREATMENT TYPE 2A	2.00	EACH		\$	
0240	02381		REMOVE GUARDRAIL	1,992.50	LF		\$	
0250	02391		GUARDRAIL END TREATMENT TYPE 4A	1.00	EACH		\$	
0260	02429		RIGHT-OF-WAY MONUMENT TYPE 1	7.00	EACH		\$	
0270	02483		CHANNEL LINING CLASS II	2,248.00	TON		\$	
0280	02484		CHANNEL LINING CLASS III	1,018.00	TON		\$	
0290	02545		CLEARING AND GRUBBING 10.4 ACRES	1.00	LS		\$	
0300	02562		SIGNS	330.00	SQFT		\$	
0310	02585		EDGE KEY	178.00	LF		\$	
0320	02599		FABRIC-GEOTEXTILE TYPE IV	32,294.00	SQYD		\$	
0330	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0340	02651		DIVERSIONS (BY-PASS DETOURS)	1.00	LS		\$	
0350	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0360	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0370	02677		ASPHALT PAVE MILLING & TEXTURING	60.00	TON		\$	
0380	02696		SHOULDER RUMBLE STRIPS-SAWED	11,483.00	LF		\$	
0390	02726		STAKING	1.00	LS		\$	
0400	02775		ARROW PANEL	2.00	EACH		\$	

PROPOSAL BID ITEMS

Report Date 2/5/13

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0401	05950		EROSION CONTROL BLANKET(ADDED: 2-5-13)	16,120.00	SQYD		\$	
0410	05966		TOPDRESSING FERTILIZER	2.60	TON		\$	
0420	05985		SEEDING AND PROTECTION	50,443.00	SQYD		\$	
0430	06417		FLEXIBLE DELINEATOR POST-W	43.00	EACH		\$	
0440	06418		FLEXIBLE DELINEATOR POST-Y	33.00	EACH		\$	
0450	06510		PAVE STRIPING-TEMP PAINT-4 IN	29,200.00	LF		\$	
0460	06511		PAVE STRIPING-TEMP PAINT-6 IN	3,580.00	LF		\$	
0470	06514		PAVE STRIPING-PERM PAINT-4 IN(REVISED: 2-5-13)	16,305.00	LF		\$	
0480	06515		PAVE STRIPING-PERM PAINT-6 IN	9,030.00	LF		\$	
0490	06516		PAVE STRIPING-PERM PAINT-8 IN	280.00	LF		\$	
0500	06550		PAVE STRIPING-TEMP REM TAPE-W	1,040.00	LF		\$	
0510	06551		PAVE STRIPING-TEMP REM TAPE-Y	1,040.00	LF		\$	
0520	06568		PAVE MARKING-THERMO STOP BAR-24IN	372.00	LF		\$	
0530	06570		PAVE MARKING-PAINT CROSS-HATCH	17,448.00	SQFT		\$	
0540	06572		PAVE MARKING-DOTTED LANE EXTEN	435.00	LF		\$	
0550	06573		PAVE MARKING-THERMO STR ARROW	1.00	EACH		\$	
0560	06574		PAVE MARKING-THERMO CURV ARROW	75.00	EACH		\$	
0570	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0580	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0590	06592		PAVEMENT MARKER TYPE V-B W/R	24.00	EACH		\$	
0600	06593		PAVEMENT MARKER TYPE V-B Y/R	70.00	EACH		\$	
0610	10020NS		FUEL ADJUSTMENT(REVISED: 2-5-13)	18,593.00	DOLL	\$1.00	\$	\$18,593.00
0620	10030NS		ASPHALT ADJUSTMENT	30,339.00	DOLL	\$1.00	\$	\$30,339.00
0630	21370ED		LONGITUDINAL SAW CUT- 6 IN	4,315.00	LF		\$	
0640	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	30.00	LF		\$	
0650	23131ER701		PIPELINE VIDEO INSPECTION	250.00	LF		\$	
0660	23143ED		KPDES PERMIT AND TEMP EROSION CONTROL	1.00	LS		\$	
0670	23607EC		PAVE MARK THERMO-LANE REDUCTION ARROW	4.00	EACH		\$	
0680	23791EC		PAVE STRIPING-CHEVRON MARKINGS	23,880.00	SQFT		\$	

PROPOSAL BID ITEMS

Report Date 2/5/13

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0690	00462		CULVERT PIPE-18 IN	26.00	LF		\$	
0700	00464		CULVERT PIPE-24 IN	451.00	LF		\$	
0710	00468		CULVERT PIPE-36 IN	20.00	LF		\$	
0720	01208		PIPE CULVERT HEADWALL-24 IN	3.00	EACH		\$	
0730	01212		PIPE CULVERT HEADWALL-36 IN	1.00	EACH		\$	
0740	01310		REMOVE PIPE	16.00	LF		\$	
0750	01434		SLOPED BOX OUTLET TYPE 1-24 IN	3.00	EACH		\$	
0760	01450		S & F BOX INLET-OUTLET-18 IN	1.00	EACH		\$	
0770	01451		S & F BOX INLET-OUTLET-24 IN	4.00	EACH		\$	
0780	01642		JUNCTION BOX-18 IN	1.00	EACH		\$	
0790	01643		JUNCTION BOX-24 IN	2.00	EACH		\$	
0800	01645		JUNCTION BOX-36 IN	1.00	EACH		\$	
0810	02625		REMOVE HEADWALL	4.00	EACH		\$	

Section: 0004 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0820	06400		GMSS GALV STEEL TYPE A	743.00	LB		\$	
0830	06406		SBM ALUM SHEET SIGNS .080 IN(REVISED: 2-5-13)	260.00	SQFT		\$	
0840	06407		SBM ALUM SHEET SIGNS .125 IN(REVISED: 2-5-13)	428.00	SQFT		\$	
0850	06410		STEEL POST TYPE 1(REVISED: 2-5-13)	1,071.00	LF		\$	
0860	06412		STEEL POST MILE MARKERS(REVISED: 2-5-13)	2.00	EACH		\$	
0870	06441		GMSS GALV STEEL TYPE C(REVISED: 2-5-13)	686.00	LB		\$	
0880	06490		CLASS A CONCRETE FOR SIGNS(REVISED: 2-5-13)	4.90	CUYD		\$	
0890	06491		STEEL REINFORCEMENT FOR SIGNS (REVISED: 2-5-13)	228.00	LB		\$	
0900	20418ED		REMOVE & RELOCATE SIGNS	3.00	EACH		\$	
0910	20419ND		ROADWAY CROSS SECTION(REVISED: 2-5-13)	3.00	EACH		\$	
0920	21596ND		GMSS TYPE D(REVISED: 2-5-13)	3.00	EACH		\$	

PROPOSAL BID ITEMS

Report Date 2/5/13

Section: 0005 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0930	04792		CONDUIT-1 IN	175.00	LF		\$	
0940	04793		CONDUIT-1 1/4 IN	1,265.00	LF		\$	
0950	04795		CONDUIT-2 IN	615.00	LF		\$	
0960	04811		ELECTRICAL JUNCTION BOX TYPE B	17.00	EACH		\$	
0970	04820		TRENCHING AND BACKFILLING	1,685.00	LF		\$	
0980	04830		LOOP WIRE	9,203.00	LF		\$	
0990	04844		CABLE-NO. 14/5C	4,450.00	LF		\$	
1000	04850		CABLE-NO. 14/1 PAIR	10,255.00	LF		\$	
1010	04885		MESSENGER-10800 LB	430.00	LF		\$	
1020	04886		MESSENGER-15400 LB	975.00	LF		\$	
1030	04895		LOOP SAW SLOT AND FILL	3,400.00	LF		\$	
1040	04931		INSTALL CONTROLLER TYPE 170	3.00	EACH		\$	
1050	04932		INSTALL STEEL STRAIN POLE	11.00	EACH		\$	
1060	20188NS835		INSTALL LED SIGNAL-3 SECTION	32.00	EACH		\$	
1070	20266ES835		INSTALL LED SIGNAL- 4 SECTION	4.00	EACH		\$	
1080	23157EN		TRAFFIC SIGNAL POLE BASE	56.00	CUYD		\$	
1090	23982EC		INSTALL ANTENNA	3.00	EACH		\$	

Section: 0006 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1100	04714		POLE 120 FT MTG HT HIGH MAST	3.00	EACH		\$	
1110	04773		HPS LUMINAIRE HIGH MAST	16.00	EACH		\$	
1120	04797		CONDUIT-3 IN	530.00	LF		\$	
1130	04800		MARKER	4.00	EACH		\$	
1140	04820		TRENCHING AND BACKFILLING	1,795.00	LF		\$	
1150	04860		CABLE-NO. 8/3C DUCTED	630.00	LF		\$	
1160	04861		CABLE-NO. 6/3C DUCTED	1,600.00	LF		\$	
1170	04862		CABLE-NO. 4/3C DUCTED	1,500.00	LF		\$	
1171	04940		REMOVE LIGHTING(ADDED: 2-5-13)	1.00	LS		\$	
1180	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	6.00	EACH		\$	
1190	21543EN		BORE AND JACK CONDUIT	530.00	LF		\$	
1200	23161EN		POLE BASE-HIGH MAST	31.00	CUYD		\$	

Section: 0007 - MOB AND DEMOB

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1210	02568		MOBILIZATION	1.00	LS		\$	
1220	02569		DEMOBILIZATION	1.00	LS		\$	