



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

February 18, 2013

CALL NO. 102
CONTRACT ID NO. 131008
ADDENDUM # 2

Subject: Shelby County, NH 0642 (184)
Letting February 22, 2013

(1) Revised - Special Notes - Pages 20-23(e) of 84

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

GENERAL PROJECT NOTE ON UTILITY PROTECTION

Utility coordination efforts determined that no significant utility relocation work is required to complete the project. Any work pertaining to these utility facilities is defined in the bid package and is to be carried out as instructed by the Kentucky Transportation Cabinet. The contractor will be responsible for any coordination or adjustments that are discussed or quantified in the proposal.

NOTE: DO NOT DISTURB THE FOLLOWING UTILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS

AT&T LEGACY—has a buried fiber optic line in an easement immediately north of the Right-of-Way along the Westbound I-64. This fiber optic line follows the Right-of-Way along Ramp 7 then proceeds northward out of Right-of-Way and crosses KY 1848 immediately north of the project limits. This fiber optic line then runs southward in an easement adjacent to the existing Right-of-Way. This line then proceeds eastward adjacent to the existing Right-of-Way along Ramp 1 and the Westbound I-64. **This facility is not to be disturbed and will remain in place.**

AT&T KY—has an underground (copper) crossing KY-1848 at approximate STA 43+25; this crossing starts on the east side of KY-1848 and runs to the west side of the route. The buried line then follows alongside the Right-of-Way of Ramp 7 inside of an easement. On the east side of KY-1848 there is an overhead (copper) route approaching from the north. This route transitions to underground at the utility pole at approximate Lt. Station 43+20 on KY-1848; underground route splits and runs westward and southward at this point. The south leg of this route follows the Right-of-Way for Ramp 1 and proceeds eastward. **All of these facilities are not to be disturbed and will remain in place.**

AT&T KY—has a diagonal overhead fiber optic crossing of KY-1848 at approximate Station 68+60. This overhead crossing feeds a utility pole located at approximate KY-1848 Lt. Station 69+85. A portion of this overhead line remains aerial and continues southward from the utility pole at Lt. station 68+60.

Shelby Energy Cooperative—has an overhead line that runs in an easement adjacent to the Right-of-Way line along Westbound I-64. This line also follows along Ramp 7 and crosses over KY-1848 at approximate Station 45+10. This line then follows along Ramp 1 and proceeds eastward along an easement adjacent to the northern Right-of-Way fence for Westbound I-64. **All of these facilities are not to be disturbed and will remain in place.**

Louisville Gas and Electric (LG&E) gas—has a 4 inch gas main along the west side of KY-1848 and is approximately 40 feet west of the west edge of pavement. This line crosses perpendicular under KY-1848 approximate Station 42+15. **All of these facilities are not to be disturbed and will remain in place.**

West Shelby Water District—has an existing 16 inch water main that runs approximately parallel to KY-1848 along the east side; this main runs southward from US 60. This main is in close proximity to the proposed Right-of-Way and follows along the Right-of-Way to Ramp 1 and then eastward in an easement along the I-64 Right-of-Way. In addition, there is a 10 inch water main that runs parallel to the 16 inch water main. This 10 inch main reduces down to an 8 inch main and then runs eastward in an easement immediately north of the Right-of-Way for Ramp 1. There is also an existing 4 inch asbestos coated water main on the west side of KY-1848. This line runs southward and ends at approximate KY-1848 Rt. Station 42+65. All of these facilities are not to be disturbed and will remain in place. **This utility is not a participant in the KY 811 system. Please contact Steve Eden ((502)722-8944) for locate assistance.**

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

**SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25**

The City of Simpsonville—has a 10 inch sanitary sewer force main along the east side of KY-1848. This force main enters the project from the north side and follows along the Right-of-Way of KY-1848 and turns eastward to follow the Right-of-Way for Ramp 1 and for westbound I-64. This force main is in an easement immediately adjacent to the Right-of-Way throughout the project limits. **All of these facilities are not to be disturbed and will remain in place.**

The Contractor is fully responsible for protection of all utilities listed above

THE FOLLOWING COMPANIES ARE RELOCATING/ADJUSTING THEIR UTILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION

AT&T KY—has a diagonal overhead crossing of KY-1848 at approximate Station 68+60. This overhead crossing feeds a utility pole located at approximate KY-1848 Lt. Station 69+85. An underground fiber run proceeds northward from this pole and turns eastward at approximate KY-1848 Lt. Station 67+35. The underground fiber from approximate KY-1848 Lt. Station 67+35 to approximate KY-1848 Lt. Station 68+35 will be relocated out of the proposed disturb limits. **This work is anticipated to be completed by March 15, 2013.**

West Shelby Water District—will relocate the property service feed to Parcel No. 222; a new meter will be set also. A new fire hydrant on the existing 6 inch PVC water main at the back of the temporary easement for entrance construction at approximate KY-1848 Rt. Station 59+10. The existing 6 inch PVC water line will be cut and capped at approximate KY-1848 Rt. Station 59+10; the inactive portion will be abandoned in place. The property service connection to Parcel No 227 at approximate KY-1848 Station 67+80 will be lowered; the meter will be relocated as well. The property service connection to Parcel No 227 at approximate KY-1848 Station 70+20 will be lowered; the meter will be relocated as well. **This work is anticipated to be completed by March 1, 2013.**

Shelby Energy Cooperative—has an overhead crossing to a utility pole at approximate KY-1848 Lt. Station 66+10. **This pole has been relocated eastward out of the proposed Right-of-Way; the work was completed on January 8, 2013.**

THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE COMPANY OR THE COMPANY'S SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT

LG&E gas-has property service connections underneath KY-1848 that serve the houses on the east side of Ky-1848 between approximate Lt. Station 65+00 and approximate Lt. Station 71+00. These service connections will be lowered immediately prior to the initial ditch excavation on either side of the road. **Note: the gas main serving these customers is located in an easement immediately west of existing KY-1399; this main will remain in place and is not to be disturbed.** Contact Gary Demko with LG&E at least five (5) working days prior to the initial ditch excavation in order to arrange to have these service connections lowered. Please contact Gary at either (502)364-8347 (**office**) or at (502)376-0487 (**cell**) in order to arrange to have these services lowered.

City of Simpsonville Sewer Board—is installing a sanitary sewer crossing underneath I-64 at approximate Station 1191+00; this crossing will be bored and jacked using a 24 inch casing in order to accommodate a 10 inch PVC sanitary sewer pipe. This work is anticipated to be completed during the

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

summer construction season of 2013; work will commence shortly after funds are secured by the City of Simpsonville. This work is being completed under Permit No. 5U-13290-12; contact David Derrick (502)636-9273 or Bryan Romine at (502)722-5634 regarding this work. This work is adjacent to the roadway project and is not expected to impact the roadway work.

West Shelby Water District—is installing a water line crossing underneath I-64 east of KY-1848 at approximate Station 2011+00; this crossing will be bored and jacked using a 24 inch casing in order to accommodate a 16 inch ductile iron water line. The water line will then extend eastward and southward in a private easement immediately adjacent to the Right-of-Way. A second crossing will be installed under KY-1848 at approximate Station 69+50. This crossing will also be bored and jacked using a 24 inch casing in order to accommodate a 16 inch ductile iron water line. This work is also anticipated to be completed during the summer construction season of 2013; work will commence shortly after funds are secured by the City of Simpsonville. This work is being completed under Permit No. 5U-11588-12; contact Steve Eden (502)636-9273 or Chris Jones at (502)722-5634 regarding this work. This work is adjacent to the roadway project and is not expected to impact the roadway work. The crossing under KY-1848 is within the project limits, however, the bore pits and other work will be located in private easement immediately adjacent to the Right-of-Way.

Windstream KDL Inc.—is installing an aerial crossing over I-64 at approximate Station 1989+80 and an overhead line adjacent to the access control fence of Ramp 7 eastward towards KY-1848. This facility will switch to become buried along KY-1848 at approximate Rt. Station 46+20 and will proceed northerly to a hand hole at approximate Rt. Station 40+00. This work is anticipated to be completed prior to April 1, 2013. This work is being completed under Permit No. 5U-0090-12; contact Rita Jones (812)253-2151 or Joey Bowen (912)536-9494 regarding this work.

**THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD
CONTRACTOR AS INCLUDED IN THIS CONTRACT**

Not Applicable..

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

SPECIAL CAUTION NOTE – PROTECTION OF UTILITIES

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. Due to the nature of the work proposed, it is unlikely to conflict with the existing utilities beyond minor facility adjustments. Where conflicts with utility facilities are unavoidable, the contractor will coordinate any necessary relocation work with the facility owner and Resident Engineer. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs.

The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor's responsibility to verify all utilities and their respective locations before excavating.

BEFORE YOU DIG

The contractor is instructed to call 1-800-752-6007 to reach KY 811, the one-call system for information on the location of existing underground utilities. The call is to be placed a minimum of two (2) and no more than ten (10) business days prior to excavation. The contractor should be aware that owners of underground facilities are not required to be members of the KY 811 one-call Before-U-Dig (BUD) service. The contractor must coordinate excavation with the utility owners, including those whom do not subscribe to KY 811. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area.

Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.

SPECIAL NOTES FOR UTILITY CLEARANCE
IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

Utility Owners and Contact Persons
For Shelby County

- 1.** LG&E KU (Electric)
820 West Broadway
Louisville, KY 40202
LG&E Emergency Number (502) 589-1444
LG&E and KU Emergency Number 1-800-331-7370

Greg Geiser
work: (502) 627-3708
Greg.Geiser@LGE-KU.com
- 2.** LG&E (Gas)
820 West Broadway
Louisville, KY 40202
Gas Emergency Number (502) 589-5511
LG&E and KU Emergency Number 1-800-331-7370

Greg Geiser
work: (502) 627-3708
Greg.Geiser@LGE-KU.com
- 3.** AT&T KY
3719 Bardstown Road - 2nd Floor
Louisville, KY 40218

Morgan Herndon
Morgan.Herndon@att.com
(502) 458-7312
- 4.** Shelby Energy Cooperative
P.O. Box 311, 620 Old Finchville Road
Shelbyville, KY 40065
(502) 633-4420

Jason Ginn
Jason@ShelbyEnergy.com
cell: 502-643-2778
Kristi Carter
Kristi@shelbyenergy.com
- 5.** North Shelby Water District
P.O. Box 97 5913 Elmburg Rd.
Bagdad, KY 40003

Pete Hedges
PeteHedges@BellSouth.net
Office: (502) 747-8942

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

6. Atmos Energy
130 Stonecrest Road Suite105
Shelbyville, KY 40065
- OR
- Bernie Anderson
cell: 502-321-8073
(502) 633-2831 ext. 104
Bernie.Anderson@AtmosEnergy.com
- Earl Taylor
Earl.Taylor@AtmosEnergy.com
Cell: 859-583-0306
Office: 859-236-2300
7. Mid - Valley Pipeline Company
4910 Limaburg Road
Burlington, KY 41005
FAX (866) 699-1185
- Todd Calfee
(859) 371-4469x14
(859)630-8271
RTCalfee@SunocoLogistics.com
8. Shelbyville Water & Sewer Commission
1059 Washington Street
Shelbyville, KY 40065
(502) 633-2840
- Tom Doyle
TGDoyle@BellSouth.net
9. Insight Communications Company
4701 Commerce Crossings Dr.
Louisville, KY 40229
- Deno Barbour
Cell: (502) 664-7395
Office(502) 357-4376
Dwight.Barbour@TWCable.com
10. U.S. 60 Water District
P.O. Box 97
Bagdad, KY 40003
- Engineer: Sandy Broughman
- Pete Hedges
PeteHedges@BellSouth.net
NSWUS60@BellSouth.net(old)
(502)747-8942
(859) 271-1778

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

- | | |
|---|--|
| 11. West Shelby Water District
P.O. Box 39
Simpsonville, KY 40067 | Steve Eden
SEden@WestShelbyWater.org
(502) 722-8944
Engineer: Kenvirons-Chris Jones
CJones@Kenvirons.com
(502)695-4357 |
| 12. City of Simpsonville Sewer Board
P.O. Box 378
Simpsonville, KY 40067
(502) 722-5634 | Bryan Romine (Plant)
Office: 502-722-5634
Cell: 442-5608
BRomine1@gmail.com
Engineer: Derrick Engineering
(Walter Elmes)
(502) 636-9273
DerrickInc@BellSouth.net |
| 13. Kentucky Data Link (KDL now Windstream)
Project Manager-Construction
3701 Communications Way
Evansville, IN 47715 | Michael D. Prather
Michael.D.Prather@windstream.com
office (859)357-6255
cell (859)550-3918
Timothy Gibson (Fiber location/relocation)
Timothy.Gibson@Windstream.com
(812) 454-6756
Lezlie Allison |
| 14. AT&T Legacy
4500 Johnston Pkwy.
Cleveland, OH 44128 | Mike Diederich
MD4145@att.com
(216)-587-6267
(216)-212-8556

Don Garr
DRGarr@Hughes.net
Cell: (502) 741-8374 |

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

- 15.** City of Taylorsville Sewer & Water
70 Taylorsville Rd., P O Box 279
Taylorsville, KY 40071
Contact: Harold Compton
HCompton@TaylorsvilleWater.org
(502) 477-3235
Fax: (502) 477-1310
- 16.** East Kentucky Power Coop
4775 Lexington Road
Winchester, KY 40391
OR
P O Box 707
Winchester, KY 40391
OR
Garry Harvey
Garry.Harvey@EKPC.coop
(859)745-9601
Jason Witt
Jason.Witt@EKPC.coop
Cell: (859) 749-9110
Office (859) 745-9596
Barry Warner
Barry.Warner@EKPC.coop
(859) 745-9304
- Include Garry on facility map requests.
Garry Harvey
Garry.Harvey@EKPC.coop
Office: 859-745-9601
- 17.** Marathon Pipeline, LLC
539 S Main St, Rm 7642
Findlay, OH 45840
David Wisner
DSWisner@MarathonPetroleum.com
(419) 421-2211

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

SHELBY COUNTY, NH 0642 (184)
FD52 106 76140 01U
RECONSTRUCT I-64/KY 1848 INTERCHANGE TO IMPROVE
ACCESS CONTROL
SYP ITEM NO. 5-65.25

- 18.** Crown Castle Network Operations
10170 Linn Station Road
Suite 525
Louisville, KY 40223
(builds cell towers and leases space on them)
- Brian Watkins
Brian.Watkins@CrownCastle.com
(502)318-1323
Brandy Bowling (Brian's supervisor)
Brandy.Bowling@CrownCastle.com
(502)318-1322
Cindy Shaffer
Cynthia.Shaffer@CrownCastle.com
(502) 318-1313
Chris Gladstone
Chris.Gladstone@CrownCastle.com
(502)689-2162
Cell: (502) 220-0169
- 19.** TRIMARC
Public Safety & Transportation Systems
901 West Main Street
Louisville, Kentucky 40202
- Todd Hood
Todd.Hodd@ngc.com
Office: (502)587-6624 ext. 2
Cell: (502)307-7456

Railroad Companies

- 1. C.S.X. Transportation, Inc.**
Contacts:
Dave Fette (Ft. Wright) – (859) 344-8137
Milton Holder – crossings – cell (502) 817-2011
John Williams – crossings – cell (502) 376-8745, Office (502) 364-1133
Joe Malandruco (Florida) – signals (904) 245-1160
- 2. R. J. Corman Railroad Corp.**
One Jay St.
Nicholasville, KY 40356
- Mike Lamar
(859) 881-2502
Dispatcher (859) 881-2503