



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

October 17, 2012

CALL NO. 103
CONTRACT ID NO. 121350
ADDENDUM # 1

Subject: Hopkins County, NH 0021 (035)
Letting October 19, 2012

- (1) Revised - Plan Sheet - R2G & R2H
- (2) Revised - Bid Items - Pages 108-113 of 115

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

GENERAL SUMMARY



TRANSPORTATION CABINET
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

COUNTY OF	ITEM NO.	SHEET NO.
HOPKINS	2-8500.00	R2g

REVISED 10-10-12 ▲

NOTES:

- ① Diversion No. 1 Ramp A Sta. 50+00 to Sta. 55+14.68
Earthwork Totals:
Embankment = 5789 CY
Excavation = 34 CY
- ② Diversion No. 2 Ramp B Sta. 63+85.27 to Sta. 67+99.09
Earthwork Totals:
Embankment = 1713 CY
Excavation = 166 CY
- ③ Diversion No. 3 Ramp C Sta. 70+00 to Sta. 75+37.20
Earthwork Totals:
Embankment = 3489 CY
Excavation = 450 CY
- ④ Diversion No. 4 Ramp D Sta. 85+92.77 to Sta. 90+93.04
Earthwork Totals:
Embankment = 38 CY
Excavation = 9242 CY
- ⑤ The area for Clearing and Grubbing was calculated to include all property within the existing and proposed control of access lines plus additional disturbed areas outside the existing and proposed control of access lines. It is intended that this entire area be Cleared and Grubbed except for areas specifically designated by the Engineer to remain undisturbed. Approximately 72 Acres
- ⑥ 156 Tons Added from Pipe Sheets
- ⑦ From Pipe Sheets
- ⑧ Remove all perforated pipe edge drains as directed by the engineer. Any perforated pipe edge drains that are designated to remain by the Engineer and are subsequently damaged as a result of removing the adjacent perforated pipe edge drains shall be repaired or replaced. Fill the void created by the removal of the perforated pipe edge drain to the subgrade line in accordance with Section 207.03 of the Standard Specifications. The Department will measure the quantity of Remove Perf. Pipe in the linear feet and payment for this item will include all casts associated with removing the perforated pipe, back filling the void to the subgrade line and maintaining the integrity of the adjacent perforated pipe.
- ⑨ 61 L.F. Added from Pipe Drainage Sheet
- ⑩ 62 S.Y. Added from Pipe Drainage Sheet
- ⑪ Used for Dust Control Caused by Maintenance of Traffic
- ⑫ From Perforated Pipe Drainage Summary

ITEM	DESCRIPTION	UNIT	I-69 SB	I-69 NB	KY 109	RAMP A	RAMP B	RAMP C	RAMP D	MOT, EROSION & DIVERSIONS	TOTAL							
00078	CRUSHED AGGREGATE SIZE NO 2	TON	19	16					2		42	⑫						
01000	PERF. PIPE 4 IN	LF	2412	1454		142	137	146	91		4382	⑫						
01005	PERF. PIPE EDGE DRAIN-4 IN	LF	3068	3131							6199	⑫						
01010	NON-PERFORATED PIPE-4 IN	LF	511	438		65	56	145	63		1278	⑫						
01015	INSP & CERT EDGE DRAIN SYS	LP SUM									1							
01020	PERF PIPE HEADWALL TY 1-4 IN	EACH	15	12							27	⑫						
01028	PERF PIPE HEADWALL TY 3-4 IN	EACH	2			2	1	1	2		8	⑫						
01032	PERF PIPE HEADWALL TY 4-4 IN	EACH	2	4			1				7	⑫						
01310	REMOVE PIPE (PERFORATED)	LF									3996	⑧ ⑫						
01310	REMOVE PIPE	LF	56				47	48			212	⑨						
01314	PLUG PIPE	EACH				1			1		2							
01982	DELINEATOR FOR GUARDRAIL-WHITE	EACH	43	22	11	6	10	0	8		100							
01984	DELINEATOR FOR BARRIER - WHITE	EACH		4							4							
01987	DELINEATOR FOR GUARDRAIL - BI-DIRECTIAL WHITE	EACH			7						7							
01989	CONC MEDIAN BARRIER TYPE 14C2	LF		338							338							
02157	PAVED DITCH TYPE 1	SOYD	187	243					100		592	⑩						
02159	TEMP DITCH	LF								5296	5296							
02242	WATER	MGAL									1247	⑪						
02262	FENCE - WOVEN WIRE TYPE 1	LF	2855	2433		1246	1120	904	891		9449							
02265	REMOVE FENCE	LF	2847	2379		1335	1170	767	856		9354							
02351	GUARDRAIL - STEEL W BEAM - S FACE	LF	2987.5	1637.5	750	500	512.5		525		6912.5							
02360	GUARDRAIL TERMINAL SECTION NO. 1	EACH			1					2	3							
02369	GUARDRAIL END TREATMENT TYPE 2A	EACH	1	2		1			1		5							
02378	GUARDRAIL CONNECTOR TO BRIDGE END TY D	EACH			4						4							
02387	GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	EACH		1							1							
02391	GUARDRAIL END TREATMENT TYPE 4A	EACH	2	2	2		1			5	12							
02381	REMOVE GUARDRAIL	LF	4000	2800	937.5	987.5	375	237.5	612.5		9950							
02397	TEMP GUARDRAIL	LF								937.5	937.5							
02429	RIGHT-OF-WAY MONUMENT TYPE 1	EACH	3	4	2						9							
02432	WITNESS POST	EACH	3	4							7							
02483	CHANNEL LINING CLASS II	TON	735	541			35	283	611		2205							
02484	CHANNEL LINING CLASS III	TON	186	636		336	595	328			2237	⑥						
02545	CLEARING AND GRUBBING	LP SUM									1	⑤						
02562	SIGNS	SOFT								970	970							
02568	MOBILIZATION	LP SUM									1							
02569	DEMOBILIZATION	LP SUM									1							
02600	FABRIC-GEOTEXTILE TYPE IV FOR PIPE	SY									1235	⑦						
02650	MAINTAIN AND CONTROL TRAFFIC	LP SUM									1							
02651	DIVERSION (RAMP A)	LP SUM									1	①						
02651	DIVERSION (RAMP B)	LP SUM									1	②						
02651	DIVERSION (RAMP C)	LP SUM									1	③						
02651	DIVERSION (RAMP D)	LP SUM									1	④						
02653	LANE CLOSURE	EACH								4	4							
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH								4	4							
▲ 2091	REMOVE PAVEMENT	SY				1907	1443	1670	2328		7348							
02690	SAFELOADING	CUYD	14.3								14.3							
02701	TEMP SILT FENCE	LF								5296	5296							
02703	SILT TRAP TYPE A	EACH								106	106							
02704	SILT TRAP TYPE B	EACH								106	106							
02705	SILT TRAP TYPE C	EACH								53	53							
02706	CLEAN SILT TRAP TYPE A	EACH								159	159							
02707	CLEAN SILT TRAP TYPE B	EACH								159	159							
02708	CLEAN SILT TRAP TYPE C	EACH								159	159							
02709	CLEAN TEMP SILT FENCE	LF								5296	5296							

FILE NAME: G:\PWORK\MWILEY\0096225\RO0206SU.DGN
 USER: Mwiley
 DATE PLOTTED: September 17, 2012
 E-SHEET NAME: RO0206SU
 MicroStation v8.11.7.180



An Equal Opportunity Employer M/F/D

GENERAL SUMMARY



TRANSPORTATION CABINET
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

COUNTY OF	ITEM NO.	SHEET NO.
HOPKINS	2-8500.00	R2g

ITEM	DESCRIPTION	UNIT	I-69 SB	I-69 NB	KY 109	RAMP A	RAMP B	RAMP C	RAMP D	MOT, EROSION & DIVERSIONS	TOTAL							
00078	CRUSHED AGGREGATE SIZE NO 2	TON	19	16					2		42	⑫						
01000	PERF. PIPE 4 IN	LF	2412	1454		142	137	146	91		4382	⑫						
01005	PERF. PIPE EDGE DRAIN-4 IN	LF	3068	3131							6199	⑫						
01010	NON-PERFORATED PIPE-4 IN	LF	511	438		65	56	145	63		1278	⑫						
01015	INSP & CERT EDGE DRAIN SYS	LP SUM									1							
01020	PERF PIPE HEADWALL TY 1-4 IN	EACH	15	12							27	⑫						
01028	PERF PIPE HEADWALL TY 3-4 IN	EACH	2			2	1	1	2		8	⑫						
01032	PERF PIPE HEADWALL TY 4-4 IN	EACH	2	4			1				7	⑫						
01310	REMOVE PIPE (PERFORATED)	LF									3996	⑧ ⑫						
01310	REMOVE PIPE	LF	56				47	48			212	⑨						
01314	PLUG PIPE	EACH				1			1		2							
01982	DELINEATOR FOR GUARDRAIL-WHITE	EACH	43	22	11	6	10	0	8		100							
01984	DELINEATOR FOR BARRIER - WHITE	EACH		4							4							
01987	DELINEATOR FOR GUARDRAIL - BI-DIRECTIAL WHITE	EACH			7						7							
01989	CONC MEDIAN BARRIER TYPE 14C2	LF		338							338							
02157	PAVED DITCH TYPE 1	SOYD	187	243					100		592	⑩						
02159	TEMP DITCH	LF								5296	5296							
02242	WATER	MGAL									1247	⑪						
02262	FENCE - WOVEN WIRE TYPE 1	LF	2855	2433		1246	1120	904	891		9449							
02265	REMOVE FENCE	LF	2847	2379		1335	1170	767	856		9354							
02351	GUARDRAIL - STEEL W BEAM - S FACE	LF	2987.5	1637.5	750	500	512.5		525		6912.5							
02360	GUARDRAIL TERMINAL SECTION NO. 1	EACH			1					2	3							
02369	GUARDRAIL END TREATMENT TYPE 2A	EACH	1	2		1			1		5							
02378	GUARDRAIL CONNECTOR TO BRIDGE END TY D	EACH			4						4							
02387	GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	EACH		1							1							
02391	GUARDRAIL END TREATMENT TYPE 4A	EACH	2	2	2		1			5	12							
02381	REMOVE GUARDRAIL	LF	4000	2800	937.5	987.5	375	237.5	612.5		9950							
02397	TEMP GUARDRAIL	LF								937.5	937.5							
02429	RIGHT-OF-WAY MONUMENT TYPE 1	EACH	3	4	2						9							
02432	WITNESS POST	EACH	3	4							7							
02483	CHANNEL LINING CLASS II	TON	735	541			35	283	611		2205							
02484	CHANNEL LINING CLASS III	TON	186	636		336	595	328			2237	⑥						
02545	CLEARING AND GRUBBING	LP SUM									1	⑤						
02562	SIGNS	SOFT								970	970							
02568	MOBILIZATION	LP SUM									1							
02569	DEMOBILIZATION	LP SUM									1							
02600	FABRIC-GEOTEXTILE TYPE IV FOR PIPE	SY									1235	⑦						
02650	MAINTAIN AND CONTROL TRAFFIC	LP SUM									1							
02651	DIVERSION (RAMP A)	LP SUM									1	①						
02651	DIVERSION (RAMP B)	LP SUM									1	②						
02651	DIVERSION (RAMP C)	LP SUM									1	③						
02651	DIVERSION (RAMP D)	LP SUM									1	④						
02653	LANE CLOSURE	EACH								4	4							
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH								4	4							
2091	REMOVE PAVEMENT	SY				1907	1443	1670	2328		7348							
02690	SAFELOADING	CUYD	14.3								14.3							
02701	TEMP SILT FENCE	LF								5296	5296							
02703	SILT TRAP TYPE A	EACH								106	106							
02704	SILT TRAP TYPE B	EACH								106	106							
02705	SILT TRAP TYPE C	EACH								53	53							
02706	CLEAN SILT TRAP TYPE A	EACH								159	159							
02707	CLEAN SILT TRAP TYPE B	EACH								159	159							
02708	CLEAN SILT TRAP TYPE C	EACH								159	159							
02709	CLEAN TEMP SILT FENCE	LF								5296	5296							

- NOTES:**
- ① Diversion No. 1 Ramp A Sta. 50+00 to Sta. 55+14.68
Earthwork Totals:
Embankment = 5789 CY
Excavation = 34 CY
 - ② Diversion No. 2 Ramp B Sta. 63+85.27 to Sta. 67+99.09
Earthwork Totals:
Embankment = 1713 CY
Excavation = 166 CY
 - ③ Diversion No. 3 Ramp C Sta. 70+00 to Sta. 75+37.20
Earthwork Totals:
Embankment = 3489 CY
Excavation = 450 CY
 - ④ Diversion No. 4 Ramp D Sta. 85+92.77 to Sta. 90+93.04
Earthwork Totals:
Embankment = 38 CY
Excavation = 9242 CY
 - ⑤ The area for Clearing and Grubbing was calculated to include all property within the existing and proposed control of access lines plus additional disturbed areas outside the existing and proposed control of access lines. It is intended that this entire area be Cleared and Grubbed except for areas specifically designated by the Engineer to remain undisturbed.
Approximately 72 Acres
 - ⑥ 156 Tons Added from Pipe Sheets
 - ⑦ From Pipe Sheets
 - ⑧ Remove all perforated pipe edge drains as directed by the engineer. Any perforated pipe edge drains that are designated to remain by the Engineer and are subsequently damaged as a result of removing the adjacent perforated pipe edge drains shall be repaired or replaced. Fill the void created by the removal of the perforated pipe edge drain to the subgrade line in accordance with Section 207.03 of the Standard Specifications. The Department will measure the quantity of Remove Perf. Pipe in the linear feet and payment for this item will include all casts associated with removing the perforated pipe, back filling the void to the subgrade line and maintaining the integrity of the adjacent perforated pipe.
 - ⑨ 61 L.F. Added from Pipe Drainage Sheet
 - ⑩ 62 S.Y. Added from Pipe Drainage Sheet
 - ⑪ Used for Dust Control Caused by Maintenance of Traffic
 - ⑫ From Perforated Pipe Drainage Summary

FILE NAME: G:\PWORK\MWILEY\0096225\RO0206SU.DGN
 USER: Mwiley
 DATE PLOTTED: September 17, 2012
 E-SHEET NAME: RO0206SU
 MicroStation v8.1i.7.180



GENERAL SUMMARY



TRANSPORTATION CABINET
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

COUNTY OF	ITEM NO.	SHEET NO.
HOPKINS	2-8500.00	R2h

ITEM	DESCRIPTION	UNIT	I-69 SB	I-69 NB	KY 109	RAMP A	RAMP B	RAMP C	RAMP D	MOT, EROSION & DIVERSIONS	TOTAL							
02726	STAKING	LP SUM									1							
02775	ARROW PANEL	EACH								2	2							
05950	EROSION CONTROL BLANKET	SY	2875	2750	1063	674	283	521	887		9053							
05952	TEMP MULCH	SY								190490	190490							
05953	TEMP SEEDING AND PROTECTION	SY								50000	50000							
05966	TOPDRESSING FERTILIZER	TON									5.2							
05985	SEEDING AND PROTECT	SY									100000							
06510	PAVE STRIPING - TEMP PAINT - 4 IN	LF								82900	82900							
06514	PAVE STRIPING - PERM PAINT - 4 IN	LF			4462						4462							
06515	PAVE STRIPING - PERM PAINT - 6 IN	LF	12016	12378		2903	1914	2185	3582		34978							
06517	PAVE STRIPING - PERM PAINT - 12 IN	LF	738	707							1445							
06569	PAVE MARKING - THERMO CROSS-HATCH	SOFT	3382	3197							6579							
06574	PAVE MARKING - THERMO CURV ARROW	EACH				4		4			8							
06589	PAVEMENT MARKER TYPE V - MW	EACH	67	60							127							
06591	PAVEMENT MARKER TYPE V - BY	EACH			32						32							
06592	PAVEMENT MARKER TYPE V - B W/R	EACH	78	80		3		3			164							
06593	PAVEMENT MARKER TYPE V - B Y/R	EACH		5		35	22	26	45		133							
2313IER701	PIPELINE VIDEO INSPECTION	LF									899							
02230	EMBANKMENT IN PLACE	CY	31212	38412	1007	33794	17069	9697	16542		147733							
10020NS	FUEL ADJUSTMENT	DOLLAR									8056							
10030NS	ASPHALT ADJUSTMENT	DOLLAR									73061							

NOTES:

⑬ Earthwork Calculations
 Common = 84978 CY
 Ditch = 11088 CY
 Benching = 31663 CY
 Refill = 3665 CY
 Trans. Benching = 903 CY
 Ditch Excavation = 49 CY ⑭

Total Excavation = 132349 CY

Embankment = 111500 CY
 Benching = 31663 CY
 Refill = 3665 CY
 Trans. Benching = 903 CY

Total Embankment = 147733 CY

⑭ From Pipe Drainage Summary Sheet

FILE NAME: G:\PWORK\CHARLOTTE_COTTON\00196225\ROO20HSU.DGN
 USER: Charlotte.Cotton
 DATE PLOTTED: September 12, 2012
 E-SHEET NAME: ROO20HSU
 MicroStation v8.11.7.443



GENERAL SUMMARY



COUNTY OF	ITEM NO.	SHEET NO.
HOPKINS	2-8500.00	R2h

△ REVISED 10-12-12

NOTES:

- ⑬ Earthwork Calculations
 Common = 84978 CY
 Ditch = 11088 CY
 Benching = 31663 CY
 Refill = 3665 CY
 Trans. Benching = 903 CY
 Ditch Excavation = 49 CY ⑭
 Total Excavation = 132349 CY
- Embankment = 111500 CY
 Benching = 31663 CY
 Refill = 3665 CY
 Trans. Benching = 903 CY
 Total Embankment = 147733 CY
- ⑭ From Pipe Drainage Summary Sheet

ITEM	DESCRIPTION	UNIT	I-69 SB	I-69 NB	KY 109	RAMP A	RAMP B	RAMP C	RAMP D	MOT, EROSION & DIVERSIONS	TOTAL								
02726	STAKING	LP SUM																	
02775	ARROW PANEL	EACH								2	2								
05950	EROSION CONTROL BLANKET	SY	2875	2750	1063	674	283	521	887		9053								
05952	TEMP MULCH	SY								190490	190490								
05953	TEMP SEEDING AND PROTECTION	SY								50000	50000								
05966	TOPDRESSING FERTILIZER	TON									5.2								
05985	SEEDING AND PROTECT	SY									100000								
06510	PAVE STRIPING - TEMP PAINT - 4 IN	LF								82900	82900								
06514	PAVE STRIPING - PERM PAINT - 4 IN	LF			4462						4462								
06515	PAVE STRIPING - PERM PAINT - 6 IN	LF	12016	12378		2903	1914	2185	3582		34978								
06517	PAVE STRIPING - PERM PAINT - 12 IN	LF	738	707							1445								
06569	PAVE MARKING - THERMO CROSS-HATCH	SOFT	3382	3197							6579								
06574	PAVE MARKING - THERMO CURV ARROW	EACH				4		4			8								
06589	PAVEMENT MARKER TYPE V - MW	EACH	67	60							127								
06591	PAVEMENT MARKER TYPE V - BY	EACH			32						32								
06592	PAVEMENT MARKER TYPE V - B W/R	EACH	78	80		3		3			164								
06593	PAVEMENT MARKER TYPE V - B Y/R	EACH		5		35	22	26	45		133								
2313IER701	PIPELINE VIDEO INSPECTION	LF									899								
02230	EMBANKMENT IN PLACE	CY	31212	38412	1007	33794	17069	9697	16542		147733								
10020NS	FUEL ADJUSTMENT	DOLLAR									8056								
10030NS	ASPHALT ADJUSTMENT	DOLLAR									73061								

Steven L. Beshear
 Governor
 Frankfort, Kentucky 40622
www.transportation.ky.gov/
Michael W. Hancock, P.E.
 Secretary

FILE NAME: G:\PWORK\CHARLOTTE_COTTON.D0196225AR0020HSU.DGN
 USER: Charlotte.Cotton
 DATE PLOTTED: September 12, 2012
 E-SHEET NAME: R0020HSU
 MicroStation v8.11.7.443



PROPOSAL BID ITEMS

Report Date 10/16/12

Page 1 of 6

SECTION: 1 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
0010	00003		CRUSHED STONE BASE	54,159.00	TON		
0020	00078		CRUSHED AGGREGATE SIZE NO 2	500.00	TON		
0030	00100		ASPHALT SEAL AGGREGATE	170.00	TON		
0040	00103		ASPHALT SEAL COAT	20.00	TON		
0050	00190		LEVELING & WEDGING PG64-22	895.00	TON		
0060	00214		CL3 ASPH BASE 1.00D PG64-22	12,800.00	TON		
0070	00330		CL3 ASPH SURF 0.50A PG64-22	5,598.00	TON		
0080	02599		FABRIC-GEOTEXTILE TYPE IV	500.00	SQYD		
0090	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		
0100	02677		ASPHALT PAVE MILLING & TEXTURING	2,670.00	TON		

SECTION: 2 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
0110	00078		CRUSHED AGGREGATE SIZE NO 2	42.00	TON		
0120	01000		PERFORATED PIPE-4 IN	4,382.00	LF		
0130	01005		PERFORATED PIPE EDGE DRAIN-4 IN	6,199.00	LF		
0140	01010		NON-PERFORATED PIPE-4 IN	1,278.00	LF		
0150	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM	1.00	LS		
0160	01020		PERF PIPE HEADWALL TY 1-4 IN	27.00	EACH		
0170	01028		PERF PIPE HEADWALL TY 3-4 IN	8.00	EACH		
0180	01032		PERF PIPE HEADWALL TY 4-4 IN	7.00	EACH		
0190	01310		REMOVE PIPE (PERF. PIPE)	3,996.00	LF		
0200	01310		REMOVE PIPE	212.00	LF		
0210	01314		PLUG PIPE	2.00	EACH		
0220	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	100.00	EACH		
0230	01984		DELINEATOR FOR BARRIER - WHITE	4.00	EACH		
0240	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	7.00	EACH		
0250	01989		CONC MEDIAN BARRIER TYPE 14C2	338.00	LF		
0260	02091		REMOVE PAVEMENT (REVISED: 10-16-12)	7,348.00	SQYD		
0270	02157		PAVED DITCH TYPE 1	592.00	SQYD		
0280	02159		TEMP DITCH	5,296.00	LF		
0290	02230		EMBANKMENT IN PLACE	147,733.00	CUYD		
0300	02242		WATER	1,247.00	MGAL		

PROPOSAL BID ITEMS

Report Date 10/16/12

SECTION: 2 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
0310	02262		FENCE-WOVEN WIRE TYPE 1	9,449.00	LF		
0320	02265		REMOVE FENCE	9,354.00	LF		
0330	02351		GUARDRAIL-STEEL W BEAM-S FACE	6,912.50	LF		
0340	02360		GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH		
0350	02369		GUARDRAIL END TREATMENT TYPE 2A	5.00	EACH		
0360	02378		GUARDRAIL CONNECTOR TO BRIDGE END TY D	4.00	EACH		
0370	02381		REMOVE GUARDRAIL	9,950.00	LF		
0380	02387		GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	1.00	EACH		
0390	02391		GUARDRAIL END TREATMENT TYPE 4A	12.00	EACH		
0400	02397		TEMP GUARDRAIL	937.50	LF		
0410	02429		RIGHT-OF-WAY MONUMENT TYPE 1	9.00	EACH		
0420	02432		WITNESS POST	7.00	EACH		
0430	02483		CHANNEL LINING CLASS II	2,205.00	TON		
0440	02484		CHANNEL LINING CLASS III	2,237.00	TON		
0450	02545		CLEARING AND GRUBBING (72 ACRES)	1.00	LS		
0460	02562		SIGNS	970.00	SQFT		
0470	02600		FABRIC GEOTEXTILE TY IV FOR PIPE	1,235.00	SQYD	\$2.00	\$2,470.00
0480	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		
0490	02651		DIVERSIONS (BY-PASS DETOURS) (RAMP A)	1.00	LS		
0500	02651		DIVERSIONS (BY-PASS DETOURS) (RAMP B)	1.00	LS		
0510	02651		DIVERSIONS (BY-PASS DETOURS) (RAMP C)	1.00	LS		
0520	02651		DIVERSIONS (BY-PASS DETOURS) (RAMP D)	1.00	LS		
0530	02653		LANE CLOSURE	4.00	EACH		
0540	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		
0550	02690		SAFELOADING	14.30	CUYD		
0560	02701		TEMP SILT FENCE	5,296.00	LF		
0570	02703		SILT TRAP TYPE A	106.00	EACH		
0580	02704		SILT TRAP TYPE B	106.00	EACH		
0590	02705		SILT TRAP TYPE C	53.00	EACH		
0600	02706		CLEAN SILT TRAP TYPE A	159.00	EACH		
0610	02707		CLEAN SILT TRAP TYPE B	159.00	EACH		
0620	02708		CLEAN SILT TRAP TYPE C	159.00	EACH		
0630	02709		CLEAN TEMP SILT FENCE	5,296.00	LF		
0640	02726		STAKING	1.00	LS		

PROPOSAL BID ITEMS

Report Date 10/16/12

SECTION: 2 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
0650	02775		ARROW PANEL	2.00	EACH		
0660	03171		CONCRETE BARRIER WALL TYPE 9T	338.00	LF		
0670	05950		EROSION CONTROL BLANKET	9,053.00	SQYD		
0680	05952		TEMP MULCH	190,490.00	SQYD		
0690	05953		TEMP SEEDING AND PROTECTION	50,000.00	SQYD		
0700	05966		TOPDRESSING FERTILIZER	5.20	TON		
0710	05985		SEEDING AND PROTECTION	100,000.00	SQYD		
0720	06510		PAVE STRIPING-TEMP PAINT-4 IN	82,900.00	LF		
0730	06514		PAVE STRIPING-PERM PAINT-4 IN	4,462.00	LF		
0740	06515		PAVE STRIPING-PERM PAINT-6 IN	34,978.00	LF		
0750	06517		PAVE STRIPING-PERM PAINT-12 IN	1,445.00	LF		
0760	06569		PAVE MARKING-THERMO CROSS-HATCH	6,579.00	SQFT		
0770	06574		PAVE MARKING-THERMO CURV ARROW	8.00	EACH		
0780	06589		PAVEMENT MARKER TYPE V-MW	127.00	EACH		
0790	06591		PAVEMENT MARKER TYPE V-BY	32.00	EACH		
0800	06592		PAVEMENT MARKER TYPE V-B W/R	164.00	EACH		
0810	06593		PAVEMENT MARKER TYPE V-B Y/R	133.00	EACH		
0820	10020NS		FUEL ADJUSTMENT	8,056.00	DOLL	\$1.00	\$8,056.00
0830	10030NS		ASPHALT ADJUSTMENT	73,061.00	DOLL	\$1.00	\$73,061.00
0840	23131ER701		PIPELINE VIDEO INSPECTION	899.00	LF		

PROPOSAL BID ITEMS

Report Date 10/16/12

SECTION: 3 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
0850	00461		CULVERT PIPE-15 IN	88.00	LF		
0860	00462		CULVERT PIPE-18 IN	165.00	LF		
0870	00464		CULVERT PIPE-24 IN	102.00	LF		
0880	00470		CULVERT PIPE-48 IN	72.00	LF		
0890	00521		STORM SEWER PIPE-15 IN	558.00	LF		
0900	00522		STORM SEWER PIPE-18 IN	591.00	LF		
0910	00524		STORM SEWER PIPE-24 IN	165.00	LF		
0920	00526		STORM SEWER PIPE-30 IN	58.00	LF		
0930	01432		SLOPED BOX OUTLET TYPE 1-15 IN	1.00	EACH		
0940	01450		S & F BOX INLET-OUTLET-18 IN	4.00	EACH		
0950	01451		S & F BOX INLET-OUTLET-24 IN	2.00	EACH		
0960	01452		S & F BOX INLET-OUTLET-30 IN	2.00	EACH		
0970	01480		CURB BOX INLET TYPE B	2.00	EACH		
0980	01490		DROP BOX INLET TYPE 1	7.00	EACH		
0990	01499		DROP BOX INLET TYPE 4	2.00	EACH		
1000	01767		MANHOLE TYPE C	3.00	EACH		
1010	08100		CONCRETE-CLASS A	8.95	CUYD		
1020	08150		STEEL REINFORCEMENT	541.00	LB		

SECTION: 4 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
1030	06400		GMSS GALV STEEL TYPE A	4,972.00	LB		
1040	06405		SBM ALUMINUM PANEL SIGNS	737.90	SQFT		
1050	06406		SBM ALUM SHEET SIGNS .080 IN	173.90	SQFT		
1060	06407		SBM ALUM SHEET SIGNS .125 IN	242.00	SQFT		
1070	06410		STEEL POST TYPE 1	705.00	LF		
1080	06417		FLEXIBLE DELINEATOR POST-W	107.00	EACH		
1090	06418		FLEXIBLE DELINEATOR POST-Y	39.00	EACH		
1100	06490		CLASS A CONCRETE FOR SIGNS	12.54	CUYD		
1110	06491		STEEL REINFORCEMENT FOR SIGNS	660.00	LB		
1120	20418ED		REMOVE & RELOCATE SIGNS	4.00	EACH		
1130	21373ND		REMOVE SIGN	2.00	EACH		
1140	21596ND		GMSS TYPE D	22.00	EACH		

PROPOSAL BID ITEMS

Report Date 10/16/12

SECTION: 5 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
1150	04714		POLE 120 FT MTG HT HIGH MAST	7.00	EACH		
1160	04761		LIGHTING CONTROL EQUIPMENT	1.00	EACH		
1170	04773		HPS LUMINAIRE HIGH MAST	37.00	EACH		
1180	04797		CONDUIT-3 IN	370.00	LF		
1190	04800		MARKER	15.00	EACH		
1200	04820		TRENCHING AND BACKFILLING	5,655.00	LF		
1210	04860		CABLE-NO. 8/3C DUCTED	3,100.00	LF		
1220	04861		CABLE-NO. 6/3C DUCTED	1,380.00	LF		
1230	04862		CABLE-NO. 4/3C DUCTED	5,450.00	LF		
1240	04940		REMOVE LIGHTING	1.00	LS		
1250	20392NS835		ELECTRICAL JUNCTION BOX TYPE C	6.00	EACH		
1260	21543EN		BORE AND JACK CONDUIT	370.00	LF		
1270	23161EN		POLE BASE-HIGH MAST	68.00	CUYD		

SECTION: 6 - WATERLINE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
1280	01073		STEEL ENCASMENT PIPE-16 IN	325.00	LF		
1290	03360		COPPER PIPE-3/4 IN	40.00	LF		
1300	03387		PVC PIPE-8 IN	1,800.00	LF		
1310	03528		GATE VALVE-8 IN	4.00	EACH		
1320	03546		BEND 22.50 DEG 8 IN	3.00	EACH		
1330	03563		BEND 45 DEG 8 IN	3.00	EACH		
1340	20552NC		TEE AND BLOCK 8 IN X 8 IN X 8 IN	2.00	EACH		
1350	20582ND		PROPOSED WATER METER	2.00	EACH		
1360	20864ND		FIRE HYDRANT ASSEMBLY	1.00	EACH		
1370	21399ED		BORE AND JACK PIPE-16 IN	160.00	LF		
1380	23330EC		WYE CONNECTION	1.00	EACH		

SECTION: 7 - TRAINEES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
1390	02742		TRAINEE PAYMENT REIMBURSEMENT 1 EQUIPMENT OPERATOR GROUP 3	1,400.00	HOUR		

PROPOSAL BID ITEMS

Report Date 10/16/12

SECTION: 8 - MOBILIZATION / DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENDED PRICE
1400	02568		MOBILIZATION	1.00	LS		
1410	02569		DEMOBILIZATION	1.00	LS		