



Matthew G. Bevin
Governor

COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Greg Thomas
Secretary

February 14, 2018

CALL NO. 103
CONTRACT ID NO. 184201
ADDENDUM # 1

Subject: NELSON COUNTY, HSIP 5038 (117)
Letting February 23, 2018

- (1) Revised - Utility Note - Pages 43-45 of 241
- (2) Revised - Proposal Bid Items - Pages 239-241 of 241

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills". The signature is written in a cursive, flowing style.

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

UTILITIES AND RAIL CERTIFICATION NOTE

NELSON COUNTY, HSIP 5038 (117)
FD52 090 0062 020-028
SAFETY IMPROVEMENTS ALONG US 62 FROM MP 20.141-27.006
ITEM NUMBER 4-9004

GENERAL PROJECT NOTE ON UTILITY PROTECTION

Other work not associated with stations 100+00 to 130+00 and stations 501+00 to 506+00 can be completed without disturbing AT&T, Kentucky Utilities and the City of Bloomfield. The anticipated completion dates listed in this note only affects the work that is to be completed between stations 100+00 and 130+00 and between stations 501+00 and 506+00.

NOTE: DO NOT DISTURB THE FOLLOWING UTILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS

AT&T, KENTUCKY UTILITIES, CITY OF BLOOMFIELD

The Contractor is fully responsible for protection of all utilities listed above

THE FOLLOWING COMPANIES ARE RELOCATING/ADJUSTING THEIR UTILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION

N/A

THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE COMPANY OR THE COMPANY’S SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT

AT&T will be relocating/removing telephone facilities and shall be completed by June 1, 2018.
Kentucky Utilities will be relocating/removing electric facilities and shall be completed by June 1, 2018.
The Department will consider submission of a bid as the Contractor’s agreement to not make any claims for additional compensation due to delays or other conditions created by the operations of utility companies listed above. Working days will not be charged for those days on which work on facilities listed above is delayed, as provided in the current edition of the KY Standard Specifications for Road and Bridge Construction. Should a difference of opinion arise as to the rights of the Contractor and others working within the limits of, or adjacent to the project, the KYTC Resident Engineer will decide as to the respective rights of the various parties involved in order to assure the completion of the Department’s work in general harmony and in a satisfactory manner, and his decision shall be final and binding upon the Contractor.

THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD CONTRACTOR AS INCLUDED IN THIS CONTRACT

City of Bloomfield Water and Sewer- The contractor is responsible for water line relocation. See general summary and utility plan sheets.

THE FOLLOWING RAIL COMPANIES HAVE FACILITIES IN CONJUNCTION WITH THIS PROJECT AS NOTED

☒ No Rail Involved ☐ Minimal Rail Involved (See Below) ☐ Rail Involved (See Below)

UTILITIES AND RAIL CERTIFICATION NOTE

NELSON COUNTY, HSIP 5038 (117)
FD52 090 0062 020-028
SAFETY IMPROVEMENTS ALONG US 62 FROM MP 20.141-27.006
ITEM NUMBER 4-9004

UNDERGROUND FACILITY DAMAGE PROTECTION – BEFORE YOU DIG

The contractor shall make every effort to protect underground facilities from damage as prescribed in the Underground Facility Damage Protection Act of 1994, Kentucky Revised Statute KRS 367.4901 to 367.4917. It is the contractor’s responsibility to determine and take steps necessary to be in compliance with federal and state damage prevention directives. The contractor is instructed to contact KY 811 for the location of existing underground utilities. Contact shall be made a minimum of two (2) and no more than ten (10) business days prior to excavation.

The contractor shall submit Excavation Locate Requests to the Kentucky Contact Center (KY 811) via web ticket entry. The submission of this request does not relieve the contractor from the responsibility of contacting non-member facility owners, whom are to be contacted through their individual Protection Notification Center. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area. Non-compliance with these directives can result in the enforcement of penalties.

SPECIAL CAUTION NOTE – PROTECTION OF UTILITIES

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. Due to the nature of the work proposed, it is unlikely to conflict with the existing utilities beyond minor facility adjustments. Where conflicts with utility facilities are unavoidable, the contractor will coordinate any necessary relocation work with the facility owner and Resident Engineer. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs.

The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor’s responsibility to verify all utilities and their respective locations before excavating.

Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.

UTILITIES AND RAIL CERTIFICATION NOTE

NELSON COUNTY, HSIP 5038 (117)
FD52 090 0062 020-028
SAFETY IMPROVEMENTS ALONG US 62 FROM MP 20.141-27.006
ITEM NUMBER 4-9004

AREA UTILITIES CONTACT LIST

<u>Utility Company/Agency</u>	<u>Contact Name</u>	<u>Contact Information</u>
<u>AT&T</u>	<u>SCOTT ROCHE</u>	<u>502-348-4528</u>
<u>KENTUCKY UTILITIES</u>	<u>MICHAEL WHITIS</u>	<u>502-333-6619</u>
<u>CITY OF BLOOMFIELD</u>	<u>RICKY JEWELL</u>	<u>502-252-5746</u>

Report Date 2/14/18

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	4,288.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	62.20	TON		\$	
0030	00103		ASPHALT SEAL COAT	7.50	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	318.00	TON		\$	
0050	00212		CL2 ASPH BASE 1.00D PG64-22	2,981.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	1,794.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0070	00078		CRUSHED AGGREGATE SIZE NO 2	2,618.00	TON		\$	
0080	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	12.00	EACH		\$	
0090	02159		TEMP DITCH	1,800.00	LF		\$	
0100	02160		CLEAN TEMP DITCH	900.00	LF		\$	
0110	02230		EMBANKMENT IN PLACE	8,920.00	CUYD		\$	
0120	02237		DITCHING	415.00	LF		\$	
0130	02351		GUARDRAIL-STEEL W BEAM-S FACE	650.00	LF		\$	
0140	02381		REMOVE GUARDRAIL	625.00	LF		\$	
0150	02429		RIGHT-OF-WAY MONUMENT TYPE 1	14.00	EACH		\$	
0160	02432		WITNESS POST	3.00	EACH		\$	
0170	02483		CHANNEL LINING CLASS II	100.00	TON		\$	
0180	02545		CLEARING AND GRUBBING (APPROX. 1.46 ACRES)	1.00	LS		\$	
0190	02562		TEMPORARY SIGNS	400.00	SQFT		\$	
0200	02585		EDGE KEY	44.00	LF		\$	
0210	02598		FABRIC-GEOTEXTILE TYPE III	4,450.00	SQYD		\$	
0220	02650		MAINTAIN & CONTROL TRAFFIC (NELSON CO. US 62)	1.00	LS		\$	
0230	02653		LANE CLOSURE	2.00	EACH		\$	
0240	02697		EDGE LINE RUMBLE STRIPS	21,343.00	LF		\$	
0250	02701		TEMP SILT FENCE	1,800.00	LF		\$	
0260	02704		SILT TRAP TYPE B	10.00	EACH		\$	
0270	02705		SILT TRAP TYPE C	19.00	EACH		\$	
0280	02707		CLEAN SILT TRAP TYPE B	10.00	EACH		\$	
0290	02708		CLEAN SILT TRAP TYPE C	19.00	EACH		\$	
0300	02726		STAKING (NELSON CO. US 62)	1.00	LS		\$	
0310	03171		CONCRETE BARRIER WALL TYPE 9T	200.00	LF		\$	
0320	04933		TEMP SIGNAL 2 PHASE	1.00	EACH		\$	
0330	05950		EROSION CONTROL BLANKET	8,500.00	SQYD		\$	
0340	05952		TEMP MULCH	4,700.00	SQYD		\$	
0350	05953		TEMP SEEDING AND PROTECTION	3,500.00	SQYD		\$	
0360	05985		SEEDING AND PROTECTION	10,000.00	SQYD		\$	
0370	05989		SPECIAL SEEDING CROWN VETCH	753.00	SQYD		\$	
0380	05990		SODDING	2,000.00	SQYD		\$	
0390	06510		PAVE STRIPING-TEMP PAINT-4 IN	1,000.00	LF		\$	

Report Date 2/14/18

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	06514		PAVE STRIPING-PERM PAINT-4 IN	41,576.00	LF		\$	
0410	08901		CRASH CUSHION TY VI CLASS BT TL2	1.00	EACH		\$	
0420	10020NS		FUEL ADJUSTMENT	7,938.00	DOLL	\$1.00	\$	\$7,938.00
0430	10030NS		ASPHALT ADJUSTMENT	19,939.00	DOLL	\$1.00	\$	\$19,939.00
0440	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
0450	23010EN		PAVE MARK TEMP PAINT STOP BAR-24 IN	22.00	LF		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0460	00440		ENTRANCE PIPE-15 IN	130.00	LF		\$	
0470	00462		CULVERT PIPE-18 IN	264.00	LF		\$	
0480	00464		CULVERT PIPE-24 IN	147.00	LF		\$	
0490	00468		CULVERT PIPE-36 IN	4.00	LF		\$	
0500	00494		CULVERT PIPE-30 IN EQUIV	63.00	LF		\$	
0510	01391		METAL END SECTION TY 3-18 IN	1.00	EACH		\$	
0520	01726		SAFETY BOX INLET-18 IN SDB-1	5.00	EACH		\$	
0530	01728		SAFETY BOX INLET-18 IN DBL SDB-5	2.00	EACH		\$	
0540	01729		SAFETY BOX INLET-24 IN DBL SDB-5	3.00	EACH		\$	
0550	02625		REMOVE HEADWALL	5.00	EACH		\$	
0560	24575ES610		HEADWALL (SLOPED & MITERED CONCRETE - FOR 18 INCH PIPE)	5.00	EACH		\$	
0570	24575ES610		HEADWALL (SLOPED & MITERED CONCRETE - FOR 24 INCH PIPE)	3.00	EACH		\$	
0580	24575ES610		HEADWALL (SLOPED & MITERED CONCRETE - FOR 2'X3' EQUIV. PIPE)	3.00	EACH		\$	
0590	24575ES610		HEADWALL (SLOPED & MITERED CONCRETE - FOR 36" PIPE)	1.00	EACH		\$	
0600	24814EC		PIPELINE INSPECTION	535.00	LF		\$	

Section: 0004 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0610	02220		FLOWABLE FILL (5'x3.3' RCBC EXTENSION STA 123+34)	26.00	CUYD		\$	
0620	02403		REMOVE CONCRETE MASONRY	.80	CUYD		\$	
0630	02625		REMOVE HEADWALL (Exist. 2.5'x2.5' RCBC)	2.00	EACH		\$	
0640	02731		REMOVE STRUCTURE (STA 117+01.95)	1.00	LS		\$	
0650	08002		STRUCTURE EXCAV-SOLID ROCK	56.00	CUYD		\$	
0660	08003		FOUNDATION PREPARATION (16' x 4' RCBC STA 117+01.95)	1.00	LS		\$	
0670	08003		FOUNDATION PREPARATION (2.5' x 2.5' EXTENSIONS MP 22.42)	1.00	LS		\$	
0680	08003		FOUNDATION PREPARATION (5'x3.3' RCBC EXTENSION STA 123+34)	1.00	LS		\$	

Report Date 2/14/18

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0690	08100		CONCRETE-CLASS A	115.90	CUYD		\$	
0700	08150		STEEL REINFORCEMENT	11,554.00	LB		\$	
0710	20598NC		BAR SPLICE-PHASE CONSTRUCTION	32.00	EACH		\$	
0720	24694ED		BOX CULVERT	16.00	LF		\$	
0730	24695ED		BOX CULVERT HEADWALL	2.00	EACH		\$	

Section: 0005 - WATERLINE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0740	14102		W VALVE 02 INCH	1.00	EACH		\$	
0750	14503		W CAP EXISTING MAIN INST	2.00	EACH		\$	
0760	14510		W FIRE HYDRANT ASSEMBLY INST	1.00	EACH		\$	
0770	14516		W METER 2 INCH INST	1.00	EACH		\$	
0780	14547		W PIPE PVC 08 INCH INST	2,265.00	LF		\$	
0790	14570		W SERV PE/PLST SHORT SIDE 2 IN INST	1.00	EACH		\$	
0800	14575		W TIE-IN 02 INCH INST	1.00	EACH		\$	
0810	14579		W TIE-IN 08 INCH INST	2.00	EACH		\$	
0820	14590		W VALVE 08 INCH INST	2.00	EACH		\$	
0830	23667EC		WATER MAIN CREEK CROSSING	30.00	LF		\$	
0840	23675EC		WIRE-NO. 12-INSTALL (REVISED: 2-14-18)	2,265.00	LF		\$	
0850	24445EC		STONE FILL NO. 9	550.00	TON		\$	

Section: 0006 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0860	02569		DEMOBILIZATION	1.00	LS		\$	