



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

July 3, 2014

CALL NO. 104
CONTRACT ID NO. 141240
ADDENDUM # 1

Subject: Hancock County, STP 0602 (010)
Letting July 11, 2014

- (1) Revised - Special Note - Pages 60-61 of 187
- (2) Revised - Bid Items - Pages 186-187 of 187

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Diana Castle Radcliffe".

Diana Castle Radcliffe
Director
Division of Construction Procurement

DR:ks
Enclosures



An Equal Opportunity Employer M/F/D

US 60 PAVEMENT REHABILITATION
HANCOCK COUNTY
ITEM NO 2-2068.00

PAVEMENT SUMMARY										
ITEM CODE	ITEM	UNIT	US 60	KY 69 (MADISON ST)	KY 1389 (MADISON ST)	CIRCLE CT	KY 2181 (PELLVILLE ST)	DAVIES DR	FROM SIDEWALK AND ENTRANCE SUMMARY	TOTAL
3	CRUSHED STONE BASE (1)	TON	14,682	151	101	38	44	15	12	15,043
100	ASPHALT SEAL AGGREGATE (2)	TON	48							48
103	ASPHALT SEAL COAT (3)	TON	6							6
212	CL2 ASPH BASE 1.00D PG64-22 (4)	TON	432							432
2015	CEMENT CONCRETE ISLAND (5)	SQ YD	1,467							1,467
2025	JPC PAVEMENT-11 IN/24 (8)	SQ YD	657		440		193	67		1,357
2058	REMOVE PCC PAVEMENT (6)	SQ YD	34,281	450	419	166	193	67	54	35,630
2071	JPC PAVEMENT-11 IN	SQ YD	35,455			166				35,621
2072	JPC PAVEMENT-11 IN SHLD	SQ YD	14,957							14,957
2091	REMOVE PAVEMENT	SQ YD	17,283	228	90					17,601
2695	RUMBLE STRIPS TYPE 3 (7)	LF	1,052							1,052

- (1) Estimated at 115 pounds per square yard per inch depth and/or at 2.07 tons per cubic yard.
- (2) Estimated at 20 pounds per square yard per application with two applications required.
- (3) Estimated at 2.4 pounds per square yard per application with two applications required.
- (4) Estimated at 110 pounds per square yard per inch depth.
- (5) Concrete thickness shall be four inches.
- (6) Removal of curb and gutter and saw cutting shall be incidental to Remove PCC Pavement.
- (7) For outside shoulders when they are no longer needed for MOT.
- (8) Includes shoulder pavement.

US 60 PAVEMENT REHABILITATION
HANCOCK COUNTY
ITEM NO 2-2068.00

PAVEMENT AREAS									
ITEM	US 60	KY 69 (MADISON ST)	KY 1389 (MADISON ST)	CIRCLE CT	KY 2181 (PELLVILLE ST)	DAVIES DR	TOTAL	(SQUARE YARDS)	
CRUSHED STONE BASE (SHOULDER WEDGE) (1)	1,532						1,532		
4" CRUSHED STONE BASE (2)	796						796		
4" CRUSHED STONE BASE	49,252	657	439	166	193	67	50,774		
ASPHALT SEAL AGGREGATE (5)	2,411						2,411		
ASPHALT SEAL COAT (5)	2,411						2,411		
4" CL2 ASPH BASE 1.00D PG64-22 (2)(3)	1,962						1,962		
CEMENT CONCRETE ISLAND	1,467						1,467		
REMOVE PCC PAVEMENT (4)	34,281	450	419	166	193	67	35,576		
JPC PAVEMENT-11 IN/24		657	440		193	67	1,357		
JPC PAVEMENT-11 IN	35,455			166			35,621		
JPC PAVEMENT-11 IN SHLD	14,957						14,957		
REMOVE PAVEMENT (2)	845						845		
REMOVE PAVEMENT	16,438	228	90				16,756		

- (1) This quantity reported in cubic yards.
- (2) Pavement for maintenance of traffic purposes. See MOT plans.
- (3) Removal of temporary asphalt pavement to construct raised traffic islands will be incidental to Item 2015 Cement Concrete Island.
- (4) Includes removal of all granular materials and sub-grade below the exist pavement to the depth required to install the new pavement.
Saw cutting shall be incidental to this bid item.

PROPOSAL BID ITEMS

141240

Page 1 of 2

Report Date 7/3/14

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	15,043.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	48.00	TON		\$	
0030	00103		ASPHALT SEAL COAT	6.00	TON		\$	
0040	00212		CL2 ASPH BASE 1.00D PG64-22	432.00	TON		\$	
0050	02015		CEMENT CONCRETE ISLAND	1,467.00	SQYD		\$	
0060	02058		REMOVE PCC PAVEMENT	35,630.00	SQYD		\$	
0061	02025		JPC PAVEMENT-11 IN/24 ADDED: 7-3-14	1,357.00	SQYD		\$	
0070	02071		JPC PAVEMENT-11 IN REVISED: 7-3-14	35,621.00	SQYD		\$	
0080	02072		JPC PAVEMENT-11 IN SHLD REVISED: 7-3-14	14,957.00	SQYD		\$	
0090	02091		REMOVE PAVEMENT	17,601.00	SQYD		\$	
0100	02695		RUMBLE STRIPS TYPE 3	1,052.00	LF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0110	01830		STANDARD INTEGRAL CURB	570.60	LF		\$	
0120	01840		LIP INTEGRAL CURB	2,689.90	LF		\$	
0130	01985		DELINEATOR FOR BARRIER - YELLOW	88.00	EACH		\$	
0140	02014		BARRICADE-TYPE III	10.00	EACH		\$	
0150	02101		CEM CONC ENT PAVEMENT-8 IN	53.70	SQYD		\$	
0160	02562		TEMPORARY SIGNS	500.00	SQFT		\$	
0170	02575		DITCHING AND SHOULDERING	5,912.00	LF		\$	
0180	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0190	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0200	02720		SIDEWALK-4 IN CONCRETE	121.40	SQYD		\$	
0210	02721		REMOVE CONCRETE SIDEWALK	121.40	SQYD		\$	
0220	02726		STAKING	1.00	LS		\$	
0230	02775		ARROW PANEL	4.00	EACH		\$	
0240	05950		EROSION CONTROL BLANKET	12,000.00	SQYD		\$	
0250	05990		SODDING	206.00	SQYD		\$	
0260	06510		PAVE STRIPING-TEMP PAINT-4 IN	55,000.00	LF		\$	
0270	06550		PAVE STRIPING-TEMP REM TAPE-W	5,000.00	LF		\$	
0280	06551		PAVE STRIPING-TEMP REM TAPE-Y	5,000.00	LF		\$	
0290	06554		PAVE STRIPING-DUR TY 1-4 IN W	15,450.00	LF		\$	
0300	06555		PAVE STRIPING-DUR TY 1-4 IN Y	13,900.00	LF		\$	
0310	06560		PAVE STRIPING-DUR TY 1-12 IN W	230.00	LF		\$	
0320	06589		PAVEMENT MARKER TYPE V-MW	113.00	EACH		\$	
0330	06591		PAVEMENT MARKER TYPE V-BY	40.00	EACH		\$	
0340	06592		PAVEMENT MARKER TYPE V-B W/R	23.00	EACH		\$	
0350	10020NS		FUEL ADJUSTMENT	4,446.00	DOLL	\$1.00	\$	\$4,446.00
0360	22664EN		WATER BLASTING EXISTING STRIPE	55,000.00	LF		\$	
0370	23143ED		KPDES PERMIT AND TEMP EROSION CONTROL	1.00	LS		\$	
0380	23158ES505		DETECTABLE WARNINGS	89.00	SQFT		\$	

PROPOSAL BID ITEMS

141240

Page 2 of 2

Report Date 7/3/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0390	23265ES717		PAVE MARK TY 1 TAPE STOP BAR-24 IN	100.00	LF		\$	
0400	23270ES717		PAVE MARK TY 1 TAPE-CURV ARROW	6.00	EACH		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0410	00466		CULVERT PIPE-30 IN	24.00	LF		\$	
0420	00522		STORM SEWER PIPE-18 IN	16.00	LF		\$	
0430	01000		PERFORATED PIPE-4 IN	1,845.00	LF		\$	
0440	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM	1.00	LS		\$	
0450	01310		REMOVE PIPE	32.00	LF		\$	
0460	01433		SLOPED BOX OUTLET TYPE 1-18 IN	1.00	EACH		\$	
0470	01452		S & F BOX INLET-OUTLET-30 IN	2.00	EACH		\$	
0480	01458		CURB BOX INLET TYPE A T	2.00	EACH		\$	
0490	01642		JUNCTION BOX-18 IN	1.00	EACH		\$	
0500	01719		ADJUST INLET	2.00	EACH		\$	
0510	01740		CORED HOLE DRAINAGE BOX CON-4 IN	6.00	EACH		\$	
0520	02484		CHANNEL LINING CLASS III	1,600.00	TON		\$	
0530	02625		REMOVE HEADWALL	3.00	EACH		\$	
0540	20366NN		REPLACE GRATE	3.00	EACH		\$	

Section: 0004 - TRAFFIC LOOPS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0550	04792		CONDUIT-1 IN	20.00	LF		\$	
0560	04793		CONDUIT-1 1/4 IN	60.00	LF		\$	
0570	04811		ELECTRICAL JUNCTION BOX TYPE B	2.00	EACH		\$	
0580	04820		TRENCHING AND BACKFILLING	60.00	LF		\$	
0590	04850		CABLE-NO. 14/1 PAIR	384.00	LF		\$	
0600	04894		PREFORMED LOOP/LEAD-IN	60.00	LF		\$	
0610	04895		LOOP SAW SLOT AND FILL	289.00	LF		\$	
0620	20453ES835		PREFORMED QUADRAPOLE LOOPS	204.00	LF		\$	

Section: 0005 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0630	02568		MOBILIZATION	1.00	LS		\$	
0640	02569		DEMOBILIZATION	1.00	LS		\$	