



**COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET**  
Frankfort, Kentucky 40622  
[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

**Matthew G. Bevin**  
Governor

**Greg Thomas**  
Secretary

March 22, 2017

CALL NO. 104  
CONTRACT ID NO. 171205  
ADDENDUM # 3

Subject: Hardin County, STP BRO 5038 (112)  
Letting March 24, 2017

- (1) Revised - Plan Sheet - R2A
- (2) Revised - Bid Items - Pages 97-98 of 98

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:ks  
Enclosures



An Equal Opportunity Employer M/F/D

# GENERAL SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
Hardin	4-1077.00	R2A

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE	TAXES	TOTAL PROJECT
2200	Roadway Excavation (1)	CU. YD.	488				488
2726	Staking	LP SUM	1				1
2242	Water	M GAL	4				4
2545	Clearing and Grubbing (2)	LP SUM	1				1
2569	Demobilization	LP SUM	1				1
2585	Edge Key	L.F.	40				40
2650	Maintain and Control Traffic	LP SUM	1				1
21415ND	Erosion Control (3)	LP SUM	1				1
2351	Guardrail Steel-W Beam-S Face	L.F.	475				475
2367	Guardrail End Treatment Ty 1	EACH	4				4
20191ED	Object Marker Ty 3	EACH	4				4
1987	Delineators for Guardrail-Bi-Directional White	EACH	9				9
6514	Pave Striping-Perm Paint 4 in	L.F.	1676				1676
6510	Pave Striping-Temp Paint 4 in	L.F.	1701				1701
2562	Temporary Signs	SQ. YD.	100				100
2696	Shoulder Rumble Strips	L.F.	783				783
2731	Remove Structure (Culvert) (4)	LP SUM	1				1
1992	Install Temp Concrete Median Barrier (5)	L.F.	120				40
2653	Lane Closures	EACH	2				2
4933	Temp Signal 2 Phase (6)	EACH	1				1
6568	Pave Marking-Thermo Stop Bar-24 in	L.F.	40				40

**NOTES:**

- (1) Earthwork Quantities  
(As derived from cross sections)

312 C.Y Embankment  
488 C.Y Excavation
- (2) Includes 0.16 acres for clearing and grubbing
  - (3) See Special Note for items included in Erosion Control Lump Sum
  - (4) Remove Existing 3-Barrel Box Culvert Sta 100+16.25
  - (5) Wall is located at the abandoned Hardin County Rest Area at northbound MP 82. Any and all work required to access these sites and prepare them for receiving the wall shall be incidental to the bid item. Site accessibility shall be returned to pre-existing conditions upon completion and shall also be incidental to the bid item. Relocation of barrier wall shall also be incidental to the bid item.
  - (6) Includes both signals for each end of bridge

FILE NAME: G:\PWORK\GARY.WALTERS\00559970\R0020A05.DGN

USER: gary.walters  
DATE PLOTTED: March 22, 2017

E-SHEET NAME:

MicroStation v8.11.7.443



### PROPOSAL BID ITEMS

171205

Page 1 of 2

Report Date 3/22/17

#### Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	693.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	3.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE (2 APPLICATIONS)	9.20	TON		\$	
0040	00103		ASPHALT SEAL COAT (2 APPLICATIONS)	1.10	TON		\$	
0050	00190		LEVELING & WEDGING PG64-22	6.00	TON		\$	
0060	00212		CL2 ASPH BASE 1.00D PG64-22	732.00	TON		\$	
0070	00301		CL2 ASPH SURF 0.38D PG64-22	90.00	TON		\$	

#### Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	9.00	EACH		\$	
0090	01992		INSTALL TEMP CONC MED BARR (REVISED: 3-16-17)	120.00	LF		\$	
0100	02200		ROADWAY EXCAVATION	488.00	CUYD		\$	
0110	02242		WATER	4.00	MGAL		\$	
0120	02351		GUARDRAIL-STEEL W BEAM-S FACE	475.00	LF		\$	
0130	02367		GUARDRAIL END TREATMENT TYPE 1	4.00	EACH		\$	
0140	02545		CLEARING AND GRUBBING (APPROXIMATELY 0.16 ACRES)	1.00	LS		\$	
0150	02562		TEMPORARY SIGNS	100.00	SQFT		\$	
0160	02585		EDGE KEY	40.00	LF		\$	
0170	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0180	02653		LANE CLOSURE	2.00	EACH		\$	
0190	02696		SHOULDER RUMBLE STRIPS	783.00	LF		\$	
0200	02726		STAKING	1.00	LS		\$	
0210	02731		REMOVE STRUCTURE (3 BARREL BOX CULVERT AT STA. 100+16.25)	1.00	LS		\$	
0230	04933		TEMP SIGNAL 2 PHASE	1.00	EACH		\$	
0240	06510		PAVE STRIPING-TEMP PAINT-4 IN	1,701.00	LF		\$	
0250	06514		PAVE STRIPING-PERM PAINT-4 IN	1,676.00	LF		\$	
0260	06568		PAVE MARKING-THERMO STOP BAR-24IN	40.00	LF		\$	
0270	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
0280	21415ND		EROSION CONTROL	1.00	LS		\$	

#### Section: 0003 - BRIDGE - STA. 100+61.25 - DWG. 27601

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0290	02231		STRUCTURE GRANULAR BACKFILL	178.00	CUYD		\$	
0300	02355		GUARDRAIL-STEEL W BEAM-S FACE A	100.00	LF		\$	
0310	02998		MASONRY COATING	89.00	SQYD		\$	
0320	03299		ARMORED EDGE FOR CONCRETE	72.00	LF		\$	
0330	08001		STRUCTURE EXCAVATION-COMMON	103.00	CUYD		\$	

**PROPOSAL BID ITEMS**

171205

Report Date 3/22/17

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0340	08019		CYCLOPEAN STONE RIP RAP	260.00	TON		\$	
0350	08033		TEST PILES	40.00	LF		\$	
0360	08039		PRE-DRILLING FOR PILES	187.00	LF		\$	
0370	08046		PILES-STEEL HP12X53	234.00	LF		\$	
0380	08100		CONCRETE-CLASS A	71.40	CUYD		\$	
0390	08104		CONCRETE-CLASS AA	27.00	CUYD		\$	
0400	08151		STEEL REINFORCEMENT-EPOXY COATED	8,190.00	LB		\$	
0410	08661		PRECAST PC BOX BEAM CB12-48	306.00	LF		\$	
0420	08801		GUARDRAIL-STEEL W BEAM-S FACE BR	57.00	LF		\$	
0430	20598NC		BAR SPLICE-PHASE CONSTRUCTION	72.00	EACH		\$	

**Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0440	02569		DEMOBILIZATION	1.00	LS		\$	