



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

January 23, 2024

CALL NO. 105
CONTRACT ID NO. 245333
ADDENDUM # 1

Subject: SCOTT COUNTY STP BRZ 9030 (404)
Letting January 25, 2024

(1) Revised - Proposal Bid Items p. 144 of 144

Proposal revisions are available at
<http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mw
Enclosures

PROPOSAL BID ITEMS

245333

Page 1 of 1

Report Date 1/23/24

Section: 0001 - BRIDGE - 105C00112N

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	162.00	TON		\$	
0020	00212		CL2 ASPH BASE 1.00D PG64-22	120.00	TON		\$	
0030	00301		CL2 ASPH SURF 0.38D PG64-22	30.00	TON		\$	
0040	01691		FLUME INLET TYPE 2	1.00	EACH		\$	
0050	01811		STANDARD CURB AND GUTTER MOD	198.00	LF		\$	
0060	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	12.00	EACH		\$	
0070	02001		CURB TO BARRIER WALL TRANS	2.00	EACH		\$	
0080	02223		GRANULAR EMBANKMENT	40.00	CUYD		\$	
0090	02351		GUARDRAIL-STEEL W BEAM-S FACE	87.50	LF		\$	
0100	02371		GUARDRAIL END TREATMENT TYPE 7	2.00	EACH		\$	
0110	02381		REMOVE GUARDRAIL	148.00	LF		\$	
0120	02399		EXTRA LENGTH GUARDRAIL POST	16.00	EACH		\$	
0130	02483		CHANNEL LINING CLASS II	8.00	TON		\$	
0140	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
0150	02585		EDGE KEY	44.00	LF		\$	
0160	02602		FABRIC-GEOTEXTILE CLASS 1	12.00	SQYD		\$	
0170	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0180	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0190	02726		STAKING	1.00	LS		\$	
0200	03299		ARMORED EDGE FOR CONCRETE	52.00	LF		\$	
0210	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0220	08100		CONCRETE-CLASS A	157.30	CUYD		\$	
0230	08104		CONCRETE-CLASS AA	62.00	CUYD		\$	
0240	08150		STEEL REINFORCEMENT	15,290.00	LB		\$	
0250	08151		STEEL REINFORCEMENT-EPOXY COATED	8,587.00	LB		\$	
0260	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
0270	08661		PRECAST PC BOX BEAM CB12-48	294.00	LF		\$	
0280	08664		PRECAST PC BOX BEAM CB27-48	476.00	LF		\$	
0290	08714		BRIDGE CHAIN LINK FENCE-10 FT	222.00	LF		\$	
0300	21415ND		EROSION CONTROL	1.00	LS		\$	
0310	23378EC		CONCRETE SEALING	6,520.00	SQFT		\$	
0315	24665EX		RAILROAD COORDINATION (ADDED 1-23-24)	1.00	LS		\$	
0320	24982EC		CONCRETE COATING APPROX 4859 SF	1.00	LS		\$	
0330	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	222.00	LF		\$	
0340	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	2.00	EACH		\$	
0350	26141EC		GALVANIC ANODE	204.00	EACH		\$	

Section: 0002 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	02568		MOBILIZATION	1.00	LS		\$	
0370	02569		DEMOBILIZATION	1.00	LS		\$	