



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

March 21, 2017

CALL NO. 105
CONTRACT ID NO. 171010
ADDENDUM # 2

Subject: Spencer County, STP BRZ 0503 (249)
Letting March 24, 2017

(1) Revised - Bid Items - Pages 103-104 of 104

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D

PROPOSAL BID ITEMS

Report Date 3/21/17

Page 1 of 2

Section: 0001 - PAVING

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|-----------------------------|----------|------|-----------|----|--------|
| 0010 | 00003 | | CRUSHED STONE BASE | 346.00 | TON | | \$ | |
| 0020 | 00100 | | ASPHALT SEAL AGGREGATE | 4.20 | TON | | \$ | |
| 0030 | 00103 | | ASPHALT SEAL COAT | .50 | TON | | \$ | |
| 0040 | 00221 | | CL2 ASPH BASE 0.75D PG64-22 | 218.00 | TON | | \$ | |
| 0050 | 00301 | | CL2 ASPH SURF 0.38D PG64-22 | 44.00 | TON | | \$ | |

Section: 0002 - ROADWAY

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|---|----------|------|-----------|----|--------|
| 0060 | 00078 | | CRUSHED AGGREGATE SIZE NO 2 | 910.00 | TON | | \$ | |
| 0070 | 01891 | | ISLAND HEADER CURB TYPE 2 | 95.00 | LF | | \$ | |
| 0080 | 01987 | | DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE | 10.00 | EACH | | \$ | |
| 0090 | 01990 | | DELINEATOR FOR BARRIER WALL-B/W | 4.00 | EACH | | \$ | |
| 0100 | 02014 | | BARRICADE-TYPE III | 4.00 | EACH | | \$ | |
| 0110 | 02159 | | TEMP DITCH | 207.00 | LF | | \$ | |
| 0120 | 02160 | | CLEAN TEMP DITCH | 104.00 | LF | | \$ | |
| 0130 | 02203 | | STRUCTURE EXCAV-UNCLASSIFIED | 194.00 | CUYD | | \$ | |
| 0140 | 02230 | | EMBANKMENT IN PLACE | 469.00 | CUYD | | \$ | |
| 0150 | 02242 | | WATER | 39.00 | MGAL | | \$ | |
| 0160 | 02351 | | GUARDRAIL-STEEL W BEAM-S FACE | 191.00 | LF | | \$ | |
| 0170 | 02360 | | GUARDRAIL TERMINAL SECTION NO 1 | 1.00 | EACH | | \$ | |
| 0180 | 02363 | | GUARDRAIL CONNECTOR TO BRIDGE END TY A | 4.00 | EACH | | \$ | |
| 0190 | 02371 | | GUARDRAIL END TREATMENT TYPE 7 | 3.00 | EACH | | \$ | |
| 0200 | 02381 | | REMOVE GUARDRAIL | 282.00 | LF | | \$ | |
| 0210 | 02429 | | RIGHT-OF-WAY MONUMENT TYPE 1 | 6.00 | EACH | | \$ | |
| 0220 | 02431 | | WITNESS R/W MONUMENT TYPE 2 | 2.00 | EACH | | \$ | |
| 0230 | 02432 | | WITNESS POST | 3.00 | EACH | | \$ | |
| 0240 | 02483 | | CHANNEL LINING CLASS II | 13.00 | TON | | \$ | |
| 0250 | 02545 | | CLEARING AND GRUBBING 0.5 ACRES | 1.00 | LS | | \$ | |
| 0260 | 02555 | | CONCRETE-CLASS B | 99.00 | CUYD | | \$ | |
| 0270 | 02562 | | TEMPORARY SIGNS | 332.00 | SQFT | | \$ | |
| 0280 | 02565 | | OBJECT MARKER TYPE 2 | 4.00 | EACH | | \$ | |
| 0290 | 02585 | | EDGE KEY | 40.00 | LF | | \$ | |
| 0300 | 02596 | | FABRIC-GEOTEXTILE TYPE I | 29.00 | SQYD | | \$ | |
| 0310 | 02599 | | FABRIC-GEOTEXTILE TYPE IV | 1,022.00 | SQYD | | \$ | |
| 0320 | 02650 | | MAINTAIN & CONTROL TRAFFIC | 1.00 | LS | | \$ | |
| 0330 | 02671 | | PORTABLE CHANGEABLE MESSAGE SIGN | 2.00 | EACH | | \$ | |
| 0340 | 02701 | | TEMP SILT FENCE | 340.00 | LF | | \$ | |
| 0350 | 02704 | | SILT TRAP TYPE B | 3.00 | EACH | | \$ | |
| 0360 | 02705 | | SILT TRAP TYPE C | 1.00 | EACH | | \$ | |
| 0370 | 02707 | | CLEAN SILT TRAP TYPE B | 3.00 | EACH | | \$ | |
| 0380 | 02708 | | CLEAN SILT TRAP TYPE C | 1.00 | EACH | | \$ | |
| 0390 | 02726 | | STAKING | 1.00 | LS | | \$ | |

PROPOSAL BID ITEMS

171010

Page 2 of 2

Report Date 3/21/17

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|--------------------------------------|----------|------|-----------|----|--------|
| 0395 | 02731 | | REMOVE STRUCTURE (ADDED: 3-21-17) | 1.00 | LS | | \$ | |
| 0400 | 05950 | | EROSION CONTROL BLANKET | 1,050.00 | SQYD | | \$ | |
| 0410 | 05952 | | TEMP MULCH | 1,367.00 | SQYD | | \$ | |
| 0420 | 05953 | | TEMP SEEDING AND PROTECTION | 1,025.00 | SQYD | | \$ | |
| 0430 | 05963 | | INITIAL FERTILIZER | .10 | TON | | \$ | |
| 0440 | 05964 | | 20-10-10 FERTILIZER | .10 | TON | | \$ | |
| 0450 | 05985 | | SEEDING AND PROTECTION | 1,000.00 | SQYD | | \$ | |
| 0460 | 05992 | | AGRICULTURAL LIMESTONE | 1.30 | TON | | \$ | |
| 0470 | 06514 | | PAVE STRIPING-PERM PAINT-4 IN | 574.00 | LF | | \$ | |
| 0480 | 20418ED | | REMOVE & RELOCATE SIGNS | 1.00 | EACH | | \$ | |
| 0490 | 24540 | | R/W MONUMENT TYPE 3 | 3.00 | EACH | | \$ | |

Section: 0003 - DRAINAGE

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|----------------------------------|----------|------|-----------|----|---------|
| 0500 | 00461 | | CULVERT PIPE-15 IN | 36.00 | LF | | \$ | |
| 0510 | 01000 | | PERFORATED PIPE-4 IN | 22.00 | LF | | \$ | |
| 0520 | 01010 | | NON-PERFORATED PIPE-4 IN | 6.00 | LF | | \$ | |
| 0530 | 01020 | | PERF PIPE HEADWALL TY 1-4 IN | 1.00 | EACH | | \$ | |
| 0540 | 01202 | | PIPE CULVERT HEADWALL-15 IN | 1.00 | EACH | | \$ | |
| 0550 | 01577 | | DROP BOX INLET TYPE 14 | 1.00 | EACH | | \$ | |
| 0560 | 02600 | | FABRIC GEOTEXTILE TY IV FOR PIPE | 46.00 | SQYD | \$2.00 | \$ | \$92.00 |

Section: 0004 - BRIDGE

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|----------------------------------|-----------|------|-----------|----|--------|
| 0570 | 02231 | | STRUCTURE GRANULAR BACKFILL | 259.00 | CUYD | | \$ | |
| 0580 | 02998 | | MASONRY COATING | 354.00 | SQYD | | \$ | |
| 0590 | 03299 | | ARMORED EDGE FOR CONCRETE | 46.00 | LF | | \$ | |
| 0600 | 08001 | | STRUCTURE EXCAVATION-COMMON | 357.00 | CUYD | | \$ | |
| 0610 | 08019 | | CYCLOPEAN STONE RIP RAP | 860.00 | TON | | \$ | |
| 0620 | 08033 | | TEST PILES | 35.00 | LF | | \$ | |
| 0630 | 08039 | | PRE-DRILLING FOR PILES | 152.00 | LF | | \$ | |
| 0640 | 08046 | | PILES-STEEL HP12X53 | 138.00 | LF | | \$ | |
| 0650 | 08094 | | PILE POINTS-12 IN | 10.00 | EACH | | \$ | |
| 0660 | 08100 | | CONCRETE-CLASS A | 60.90 | CUYD | | \$ | |
| 0670 | 08104 | | CONCRETE-CLASS AA | 102.90 | CUYD | | \$ | |
| 0680 | 08151 | | STEEL REINFORCEMENT-EPOXY COATED | 25,209.00 | LB | | \$ | |
| 0690 | 21532ED | | RAIL SYSTEM TYPE III | 174.00 | LF | | \$ | |
| 0700 | 23981EC | | PPC I-BEAM TYPE HN 42-49 | 256.50 | LF | | \$ | |

Section: 0005 - DEMOBILIZATION &/OR MOBILIZATION

| LINE | BID CODE | ALT | DESCRIPTION | QUANTITY | UNIT | UNIT PRIC | FP | AMOUNT |
|------|----------|-----|----------------|----------|------|-----------|----|--------|
| 0710 | 02569 | | DEMOBILIZATION | 1.00 | LS | | \$ | |