



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET

[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

February 15, 2021

CALL NO. 106  
CONTRACT ID NO. 215166  
ADDENDUM # 1

Subject: JEFFERSON COUNTY, STP BRZ 9030 (243)  
Letting February 19, 2021

- (1) Revised - Utilities and Rail Certification Note - Pages 82-86 of 168
- (2) Revised - CAP Notes - Page 126 of 168

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

## UTILITIES AND RAIL CERTIFICATION NOTE

**Jefferson County**  
**Mile point: 16.353 TO 16.361**  
**ADDRESS DEFICIENCIES OF US 31E BRIDGE OVER S FK BEARGRASS CREEK. (056B00137N)**  
**ITEM NUMBER: 05-10018.00**

### PROJECT NOTES ON UTILITIES

For all projects under 2000 Linear feet which require a normal excavation locate request pursuant to KRS 367.4901-4917, the awarded contractor shall field mark the proposed excavation or construction boundaries of the project (also called white lining) using the procedure set forth in KRS 367.4909(9)(k). For all projects over 2000 linear feet, which are defined as a "Large Project" in KRS 367.4903(18), the awarded contractor shall initially mark the first 2000 linear feet minimally of proposed excavation or construction boundaries of the project to be worked using the procedure set forth in KRS 367.4909(9)(k). This temporary field locating of the project excavation boundary shall take place prior to submitting an excavation location request to the underground utility protection Kentucky Contact Center. For large projects, the awarded contractor shall work with the impacted utilities to determine when additional white lining of the remainder of the project site will take place. This provision shall not alter or relieve the awarded contractor from complying with requirements of KRS 367.4905 to 367.4917 in their entirety.

Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. Due to the nature of the work proposed, it is unlikely to conflict with the existing utilities beyond minor facility adjustments. Where conflicts with utility facilities are unavoidable, the contractor will coordinate any necessary relocation work with the facility owner and Resident Engineer. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs. The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor's responsibility to verify all utilities and their respective locations before excavating.

The contractor shall make every effort to protect underground facilities from damage as prescribed in the Underground Facility Damage Protection Act of 1994, Kentucky Revised Statute KRS 367.4901 to 367.4917. It is the contractor's responsibility to determine and take steps necessary to be in compliance with federal and state damage prevention directives. The contractor is instructed to contact KY 811 for the location of existing underground utilities. Contact shall be made a minimum of two (2) and no more than ten (10) business days prior to excavation. The contractor shall submit Excavation Locate Requests to the Kentucky Contact Center (KY 811) via web ticket entry. The submission of this request does not relieve the contractor from the responsibility of contacting non-member facility owners, whom

## UTILITIES AND RAIL CERTIFICATION NOTE

**Jefferson County**  
**Mile point: 16.353 TO 16.361**  
**ADDRESS DEFICIENCIES OF US 31E BRIDGE OVER S FK BEARGRASS CREEK. (056B00137N)**  
**ITEM NUMBER: 05-10018.00**

are to be contacted through their individual Protection Notification Center. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area. Non-compliance with these directives can result in the enforcement of penalties.

**NOTE: DO NOT DISTURB THE FOLLOWING FACILITIES LOCATED WITHIN THE PROJECT AREA**

AT&T (Telephone)

Kentucky Wired - Communication

Zayo - CATV

CenturyLink - Communication

Metropolitan Sewer District - Sewer

Windstream dba Kentucky Data Link (KDL) - Communication

Louisville Jefferson County Metro Government - Communication

LG&E KU - Electric, Natural Gas

Spectrum Communications - Communications

Crown Castle Network Operations - Communications

Louisville Water Company - Water

**\*The Contractor is fully responsible for protection of all utilities listed above\***

**THE FOLLOWING FACILITY OWNERS ARE RELOCATING/ADJUSTING THEIR FACILITIES WITHIN THE PROJECT AREA AND WILL BE COMPLETE PRIOR TO CONSTRUCTION**

Spectrum Communications (Communications) will relocate their existing aerial communication lines from the existing utility pole in the sidewalk on the northeast side of US 31E by October 31, 2019.

AT&T (Telephone) will remove the existing utility pole in the sidewalk on the northeast side of US 31E after Spectrum relocates their aerial communication lines by November 15, 2019.

Crown Castle Network Operations (Communication) will remove their existing utility pole anchor in the sidewalk near the southeast corner of the bridge by October 31, 2019.

Louisville Metro Government, Public Works (Traffic Signal) will relocate their existing aerial traffic signal line from the existing utility pole in the sidewalk on the northeast side of US 31E by October 31, 2019.

## UTILITIES AND RAIL CERTIFICATION NOTE

**Jefferson County**  
**Mile point: 16.353 TO 16.361**  
**ADDRESS DEFICIENCIES OF US 31E BRIDGE OVER S FK BEARGRASS CREEK. (056B00137N)**  
**ITEM NUMBER: 05-10018.00**

**THE FOLLOWING FACILITY OWNERS HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE OWNER OR THEIR SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT**

LG&E/KU (Natural Gas) has a 4-inch gas main in the roadway on the southwest side of US 31E that will be adjusted or relocated.

**THE FOLLOWING FACILITY OWNERS HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD CONTRACTOR AS INCLUDED IN THIS CONTRACT**

Louisville Water Company (Water) has an existing 16-inch water line in the roadway along the northwest side of US 31E that will be relocated by the Contractor as part of the bridge replacement project, as indicated in the drawings.

AT&T (Telephone) has two ducts in the roadway along the southwest side of US 31E that shall be protected and maintained with additional support.

Crown Castle Network Operations (Communication) has three ducts in the roadway on the northeast side of US 31E that shall be protected and maintained with additional support.

**RAIL COMPANIES HAVE FACILITIES IN CONJUNCTION WITH THIS PROJECT AS NOTED**

**No Rail Involvement**    **Rail Involved**    **Rail Adjacent**

### AREA FACILITY OWNER CONTACT LIST

Facility Owner	Address	Contact Name	Phone	Email
AT&T - Telephone	1350 E John Rowan Blvd., Bardstown, KY 40004	Scott Roche	(502) 348-4528	sr8832@att.com
CenturyLink - Communication	100 W 5th St #315 Tulsa, OK 74103	Renoy Thomas	(918) 235-6848	renoy.thomas@centurylink.com

## UTILITIES AND RAIL CERTIFICATION NOTE

**Jefferson County**  
**Mile point: 16.353 TO 16.361**  
**ADDRESS DEFICIENCIES OF US 31E BRIDGE OVER S FK BEARGRASS CREEK. (056B00137N)**  
**ITEM NUMBER: 05-10018.00**

Spectrum Communications - Communication	10168 Linn Station Road, Suite 120 Louisville, KY 40223	Kevin Mercer	(502) 817-5055	Kevin.Mercer@charter.com
Crown Castle Network Operations - Communication	10300 Ormsby Park Place, Louisville, KY 40223	Patrick Massie	(502) 604-5268	Patrick.Massie@crowncastle.com
Kentucky Wired - Communication	Ledcor Lexington, KY 40511	Alvin Barksdale	(859) 286-8146	Alvin.Barksdale@ledcor.com
LG&E KU - Electric	10300 Ballardsville Rd., Louisville, KY 40241	Caroline Justice	(502) 627-3708	Caroline.Justice@lge-ku.com
LG&E/KU - Natural Gas	10300 Ballardsville Rd., Louisville, KY 40241	Caroline Justice	(502) 627-3708	Caroline.Justice@lge-ku.com
Louisville Jefferson County Metro Government - Communication	410 S 2nd Street Louisville, KY 40202	Jeremy Cissell	(502) 574-1525	Jeremy.Cissell@louisvilleky.gov
Louisville Water Company - Water	550 South Third Street, Louisville, KY 40202	Daniel Tegene	(502) 569-3649	dtegene@lwcky.com
Metropolitan Sewer District - Sewer	700 West Liberty Street, Louisville, KY 40203	Brandon Flaherty	(502) 540-6632	brandon.flaherty@louisvillemsd.org
Windstream dba Kentucky Data Link (KDL) - Communication	111 S. Main St. Elizabethtown, KY 42701	James Galvin	(270) 765-1818	james.galvin@windstream.net
Zayo - CATV	9209 Castlegate Dr. Indianapolis, IN 46256	Jared Rogers	(812) 661-6690	jared.rogers@zayo.com

## UTILITIES AND RAIL CERTIFICATION NOTE

Jefferson County  
Mile point: 16.353 TO 16.361  
**ADDRESS DEFICIENCIES OF US 31E BRIDGE OVER S FK BEARGRASS CREEK. (056B00137N)**  
ITEM NUMBER: 05-10018.00

Louisville Jefferson County Metro Government - Public Works	601 W. Jefferson St. Louisville, KY 40202	Pat Johnson	(502) 574- 3930	Pat.Johnson@louisvilleky.gov
--	--	-------------	--------------------	------------------------------

**The Contractor shall contact CenturyLink at least 48 hours prior to any pre-construction meeting or prior to any work near CenturyLink facilities.**

**The Contractor shall contact AT&T at least 2 weeks prior to any removal work to coordinate the protection and support of their underground ducts.**

**The Contractor shall contact LG&E/KU (Natural Gas) at least 4 weeks prior to any removal work to coordinate their gas main work.**

**The Contractor shall contact Crown Castle Network Operations (Communications) at least 2 weeks prior to any excavation work to coordinate the protection and support of their buried fiber optic lines.**

**The Contractor shall contact Pat Johnson at Louisville/Jefferson Co. Metro Government, at least 2 weeks prior to a lane closures or road closure to coordinate the traffic control and detour.**

## CAP Notes

The following notes are required to be fulfilled as part of the Contract

1. The contract must comply with the construction commitments provided to the Kentucky State Historic Preservation Office (SHPO) that were used to make their finding of No Adverse Effect to the historic bridge. The commitments are provided as Special Notes, which are listed below and included in full with this submittal:
  - Special Note for Bridge Cleaning
  - Special Note for Dutchman Repairs
  - Special Note for Masonry Crack Repairs
  - Special Note for Masonry Repairs
  - Special Note for Stone Replacement
2. LG&E estimates the gas main related work can be completed in 3 weeks. This work is weather dependent and must begin after April 1, 2021. The Contractor shall coordinate with LG&E about the gas main work a minimum of 4 weeks before beginning any removal work on the road or bridge.