



Matthew G. Bevin
Governor

COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Greg Thomas
Secretary

October 24, 2019

CALL NO. 110
CONTRACT ID NO. 195149
ADDENDUM # 1

Subject: HENRY COUNTY, STP BRZ 9030 (144)
Letting October 25, 2019

(1) Revised - Proposal Bid Items - Page 158 of 158

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

PROPOSAL BID ITEMS

Report Date 10/24/19

Section: 0001 - BRIDGE - 052B00064N

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	8.00	EACH		\$	
0020	02223		GRANULAR EMBANKMENT	75.00	CUYD		\$	
0030	02351		GUARDRAIL-STEEL W BEAM-S FACE	87.50	LF		\$	
0040	02360		GUARDRAIL TERMINAL SECTION NO 1	2.00	EACH		\$	
0050	02371		GUARDRAIL END TREATMENT TYPE 7	2.00	EACH		\$	
0060	02399		EXTRA LENGTH GUARDRAIL POST	16.00	EACH		\$	
0070	02545		CLEARING AND GRUBBING Less than 1 acre	1.00	LS		\$	
0080	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0090	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0100	02726		STAKING	1.00	LS		\$	
0110	02731		REMOVE STRUCTURE	1.00	LS		\$	
0120	03299		ARMORED EDGE FOR CONCRETE	40.00	LF		\$	
0130	03304		BRIDGE OVERLAY APPROACH PAVEMENT	329.00	SQYD		\$	
0140	08002		STRUCTURE EXCAV-SOLID ROCK	125.00	CUYD		\$	
0150	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0160	08019		CYCLOPEAN STONE RIP RAP	280.00	TON		\$	
0170	08033		TEST PILES	18.00	LF		\$	
0180	08046		PILES-STEEL HP12X53	48.00	LF		\$	
0190	08094		PILE POINTS-12 IN	4.00	EACH		\$	
0200	08100		CONCRETE-CLASS A	243.10	CUYD		\$	
0210	08104		CONCRETE-CLASS AA	34.00	CUYD		\$	
0220	08150		STEEL REINFORCEMENT	26,300.00	LB		\$	
0230	08151		STEEL REINFORCEMENT-EPOXY COATED	8,086.00	LB		\$	
0240	08662		PRECAST PC BOX BEAM CB17-48	540.00	LF		\$	
0245	20629NS719		THRIE BEAM TO W BEAM CONNECTOR (ADDED: 10-24-19)	4.00	EACH		\$	
0250	21415ND		EROSION CONTROL	1.00	LS		\$	
0260	23378EC		CONCRETE SEALING	1,911.00	SQFT		\$	
0270	24982EC		CONCRETE COATING Approx 5347 SF	1.00	LS		\$	
0280	25024ED		CLASSIC BRIDGE RAIL	216.00	LF		\$	

Section: 0002 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0300	02568		MOBILIZATION	1.00	LS		\$	
0310	02569		DEMOBILIZATION	1.00	LS		\$	