



COMMONWEALTH OF KENTUCKY

Matthew G. Bevin
Governor

March 15, 2016

CALL NO. 111
CONTRACT ID NO. 164300
ADDENDUM # 1

Subject: Christian County, HSIP 9010 (210)
Letting March 25, 2016

(1) Revised - Guardrail Summary - Page 27 of 95

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D

Bid Summary

I-24 (CHRISTIAN CO.) MP 69.830 - 93.373											
REMOVE GUARDRAIL						INSTALL GUARDRAIL					
LANE	TREAT.	BEGIN MILEPOINT	MILEPOINT	TREAT.	REMARKS	LANE	END TREAT.	MILEPOINT	MILEPOINT	TREAT.	REMARKS
EB	BCT	70.436	70.521	BEC-A	449	EB	4A	70.436	70.521	BEC-A	449
EB	BCT	72.454	72.604	2A	792	EB	4A	72.454	72.604	2A	792
EB	BCT	72.604	72.691	BEC-A	459	EB	4A	72.604	72.691	BEC-A	459
EB	BCT	73.116	73.171	2A	290	EB	4A	73.116	73.171	2A	290
EB	BCT	74.755	74.856	2A	533	EB	4A	74.755	74.856	2A	533
WB	BCT	74.872	74.797	2A	396	WB	4A	74.872	74.797	2A	396
WB	BCT	73.211	73.161	2A	264	WB	1	73.211	73.161	2A	264
WB	BCT	72.790	72.725	BEC-A	343	WB	4A	72.790	72.725	BEC-A	343
WB	BCT	72.398	72.348	2A	264	WB	4A	72.398	72.348	2A	264

US-41 (CHRISTIAN CO.) MP 9.212 - 12.438											
REMOVE GUARDRAIL						INSTALL GUARDRAIL					
LANE	TREAT.	BEGIN MILEPOINT	MILEPOINT	TREAT.	REMARKS	LANE	END TREAT.	MILEPOINT	MILEPOINT	TREAT.	REMARKS
NB	7	10.362	10.406	2A	232	NB	4A	10.362	10.406	2A	232
NB	7	11.350	11.376	BEC-A	137	NB	4A	11.350	11.376	BEC-A	137
SB	7	11.411	11.396	BEC-A	79	SB	1	11.411	11.396	BEC-A	79
SB	7	10.422	10.377	2A	238	SB	4A	10.422	10.377	2A	238

US-68B (CHRISTIAN CO.) MP 0.000 - 11.026											
REMOVE GUARDRAIL						INSTALL GUARDRAIL					
LANE	TREAT.	BEGIN MILEPOINT	MILEPOINT	TREAT.	REMARKS	LANE	END TREAT.	MILEPOINT	MILEPOINT	TREAT.	REMARKS
EB	BCT	4.303	4.408	2A	554	EB	4A	4.303	4.408	2A	554
EB	BCT	5.285	5.337	2A	275	EB	4A	5.285	5.337	2A	275
EB	BCT	6.046	6.080	BEC-A	180	EB	1	6.046	6.080	BEC-A	180
EB	BCT	6.590	6.756	2A	876	EB	4A	6.590	6.756	2A	876
WB	BCT	6.746	6.614	2A	697	WB	1	6.746	6.614	2A	697
WB	BCT	7.874	7.790	2A	444	WB	4A	7.874	7.790	2A	444

***NOTICE:**

Begin/End Milepoints are estimated to include the entire length of the rail AND the End Treatments. The Engineer may adjust the termini to ensure proper installation of the guardrail system.

County	Route	Remove Guardrail	W-Beam	ET TY 1	ET TY 2A	ET TY 4A	BEC TY A
Christian	I-24	3791	3791	1	6	8	3
Christian	US-41	686	686	1	2	3	2
Christian	US-68B	3025	3025	2	5	4	1
Total:		7503	7503	4	13	15	6