



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

October 25, 2016

CALL NO. 113
CONTRACT ID NO. 161049
ADDENDUM # 2

Subject: Carter County, STP BRZ 0903 (201)
Letting October 28, 2016

- (1) Revised - Plan Sheet - U1
- (2) Revised - Bid Items - Pages 163-165 of 165

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D

WATERLINE UTILITY SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
CARTER	9-1081.00	U1

ITEM	DESCRIPTION	UNIT	\$														TOTALS
14057	NEW 3" CL. 250 PVC W/L	L.F.	150														150
14012	NEW 6" STL. SCH. 40 OPEN CUT CASING	L.F.	30														30
14092	CONNECT NEW 3" PVC W/L TO EXISTING 3" W/L. FURNISH INSTALLATION OF 3" x 3" M.J. TEE. W/GRIP RINGS.	EA.	1														1
14103	NEW 3" M.J. GATE VALVE WITH GRIP RINGS BOX/LID, CONCRETE COLLAR, FURNISH AND INSTALL, COMPLETE	EA.	2														2
14023	NEW 3" BLOWOFF ASSEMBLY W/3"x3" M.J. TEE, 10 L.F. 3" CL. 250 PVC W/L & NEW 3" M.J. GATE VALVE (ALL W/ GRIP RINGS)	EA.	1														1
14003	CUT, CAP AND ABANDON EXISTING 3" W/L W/M.J. PLUG W/GRIP RINGS	EA.	1														1
*	NEW 3" M.J. 90° M.J. BENDS W/GRIP RINGS	EA.	1*														1
*	NEW 3" M.J. 45° BENDS W/GRIP RINGS	EA.	1*														1
14005	ENCASEMENT CONCRETE (CREEK OR DITCH CROSSING)	L.F.	10														10
14080	W SERV PE/PLST LONG SIDE 3/4 IN	EA.	1														1
14081	EXISTING WATER SERVICE RE-CONNECT	EA.	1														1
	*NOTE: NO SEPARATE PAYMENT FOR FITTINGS. TO BE INCLUDED IN PRICE BID FOR WATER PIPE PER KYTC.																

NOTES:

MicroStation v8.11.7.443
E-SHEET NAME:
USER: DATE PLOTTED: January 6, 2016
FILE NAME: \\NAS145\PROJECTS\RAFILESNAKE_RIDGE_WATER_DISTRICT\KY\474\CADD\KYTC_U1_474_GENERAL_SUMMARY.DWG

GENERAL SUMMARY

WATERLINE UTILITY SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
CARTER	9-1081.00	U1

REVISED 10-25-16

ITEM	DESCRIPTION	UNIT	\$														TOTALS
14057	NEW 3" CL. 250 PVC W/L	L.F.	150														150
14012	NEW 6" STL. SCH. 40 OPEN CUT CASING	L.F.	30														30
14092	CONNECT NEW 3" PVC W/L TO EXISTING 3" W/L. FURNISH INSTALLATION OF 3" x 3" M.J. TEE. W/GRIP RINGS.	EA.	1														1
14103	NEW 3" M.J. GATE VALVE WITH GRIP RINGS BOX/LID, CONCRETE COLLAR, FURNISH AND INSTALL, COMPLETE	EA.	2														2
14023	NEW 3" BLOWOFF ASSEMBLY W/3"x3" M.J. TEE, 10 L.F. 3" CL. 250 PVC W/L & NEW 3" M.J. GATE VALVE (ALL W/ GRIP RINGS)	EA.	1														1
14003	CUT, CAP AND ABANDON EXISTING 3" W/L W/M.J. PLUG W/GRIP RINGS	EA.	1														1
*	NEW 3" M.J. 90° M.J. BENDS W/GRIP RINGS	EA.	1*														1
*	NEW 3" M.J. 45° BENDS W/GRIP RINGS	EA.	1*														1
14005	ENCASEMENT CONCRETE (CREEK OR DITCH CROSSING)	L.F.	10														10
14080	W SERV PE/PLST LONG SIDE 3/4 IN	EA.	1														1
14081	EXISTING WATER SERVICE RE-CONNECT	EA.	1														1
	*NOTE: NO SEPARATE PAYMENT FOR FITTINGS. TO BE INCLUDED IN PRICE BID FOR WATER PIPE PER KYTC.																

NOTES:

FILE NAME: \\ASSTVS\PROJECTS\RA\FILES\NAKE_RIDGE_WATER_DISTRICT\KY\474\CADD\KYTC_U1_474_GENERAL_SUMMARY.DWG

USER: DATE PLOTTED: January 6, 2016

E-SHEET NAME:

MicroStation v8.11.7.443

GENERAL SUMMARY

PROPOSAL BID ITEMS

161049

Page 1 of 3

Report Date 10/25/16

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	1,710.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	40.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE	13.00	TON		\$	
0040	00103		ASPHALT SEAL COAT	2.00	TON		\$	
0050	00221		CL2 ASPH BASE 0.75D PG64-22	1,234.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	259.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0070	00078		CRUSHED AGGREGATE SIZE NO 2	400.00	TON		\$	
0080	01891		ISLAND HEADER CURB TYPE 2	100.00	LF		\$	
0090	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	49.00	EACH		\$	
0100	01984		DELINEATOR FOR BARRIER - WHITE	4.00	EACH		\$	
0110	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0120	02159		TEMP DITCH	328.00	LF		\$	
0130	02160		CLEAN TEMP DITCH	164.00	LF		\$	
0140	02200		ROADWAY EXCAVATION	4,243.00	CUYD		\$	
0150	02242		WATER	62.00	MGAL		\$	
0160	02351		GUARDRAIL-STEEL W BEAM-S FACE	625.00	LF		\$	
0170	02360		GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH		\$	
0180	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH		\$	
0190	02371		GUARDRAIL END TREATMENT TYPE 7	4.00	EACH		\$	
0200	02391		GUARDRAIL END TREATMENT TYPE 4A	1.00	EACH		\$	
0210	02397		TEMP GUARDRAIL	437.50	LF		\$	
0220	02429		RIGHT-OF-WAY MONUMENT TYPE 1	25.00	EACH		\$	
0230	02432		WITNESS POST	3.00	EACH		\$	
0240	02483		CHANNEL LINING CLASS II	119.00	TON		\$	
0250	02545		CLEARING AND GRUBBING 1.922 ACRES	1.00	LS		\$	
0260	02562		TEMPORARY SIGNS	109.00	SQFT		\$	
0270	02585		EDGE KEY	57.00	LF		\$	
0280	02599		FABRIC-GEOTEXTILE TYPE IV	1,385.00	SQYD		\$	
0290	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0300	02651		DIVERSIONS (BY-PASS DETOURS) INCLUDES TEMPORARY STRUCTURE FOR SMITH CREEK	1.00	LS		\$	
0310	02701		TEMP SILT FENCE	328.00	LF		\$	
0320	02703		SILT TRAP TYPE A	2.00	EACH		\$	
0330	02704		SILT TRAP TYPE B	2.00	EACH		\$	
0340	02705		SILT TRAP TYPE C	2.00	EACH		\$	
0350	02706		CLEAN SILT TRAP TYPE A	2.00	EACH		\$	
0360	02707		CLEAN SILT TRAP TYPE B	2.00	EACH		\$	
0370	02708		CLEAN SILT TRAP TYPE C	2.00	EACH		\$	
0380	02726		STAKING	1.00	LS		\$	
0390	02731		REMOVE STRUCTURE	1.00	LS		\$	

PROPOSAL BID ITEMS

161049

Page 2 of 3

Report Date 10/25/16

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	05950		EROSION CONTROL BLANKET	229.00	SQYD		\$	
0410	05952		TEMP MULCH	6,201.00	SQYD		\$	
0420	05953		TEMP SEEDING AND PROTECTION	4,651.00	SQYD		\$	
0430	05963		INITIAL FERTILIZER	.50	TON		\$	
0440	05964		20-10-10 FERTILIZER	.50	TON		\$	
0450	05985		SEEDING AND PROTECTION	5,473.00	SQYD		\$	
0460	05992		AGRICULTURAL LIMESTONE	5.76	TON		\$	
0470	06407		SBM ALUM SHEET SIGNS .125 IN FOR STOP SIGN	6.25	SQFT		\$	
0480	06410		STEEL POST TYPE 1 FOR STOP SIGN	15.00	LF		\$	
0490	06510		PAVE STRIPING-TEMP PAINT-4 IN	4,162.00	LF		\$	
0500	06514		PAVE STRIPING-PERM PAINT-4 IN	2,620.00	LF		\$	
0510	06568		PAVE MARKING-THERMO STOP BAR-24IN	9.00	LF		\$	
0520	06588		PAVEMENT MARKER TY IVA-BY TEMP	27.00	EACH		\$	
0530	24631EC		BARCODE SIGN INVENTORY	1.00	EACH		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0540	00464		CULVERT PIPE-24 IN	30.00	LF		\$	
0550	01208		PIPE CULVERT HEADWALL-24 IN	2.00	EACH		\$	
0560	02484		CHANNEL LINING CLASS III	1,301.00	TON		\$	
0570	02596		FABRIC-GEOTEXTILE TYPE I	1,682.00	SQYD		\$	

Section: 0004 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0580	02231		STRUCTURE GRANULAR BACKFILL SPAN = 74', WIDTH = 31'	74.30	CUYD		\$	
0590	02998		MASONRY COATING	396.00	SQYD		\$	
0600	03299		ARMORED EDGE FOR CONCRETE	79.20	LF		\$	
0610	08001		STRUCTURE EXCAVATION-COMMON	783.00	CUYD		\$	
0620	08002		STRUCTURE EXCAV-SOLID ROCK	82.00	CUYD		\$	
0630	08019		CYCLOPEAN STONE RIP RAP	219.00	TON		\$	
0640	08033		TEST PILES	15.00	LF		\$	
0650	08039		PRE-DRILLING FOR PILES	70.00	LF		\$	
0660	08046		PILES-STEEL HP12X53	72.00	LF		\$	
0670	08100		CONCRETE-CLASS A	169.30	CUYD		\$	
0680	08104		CONCRETE-CLASS AA	91.20	CUYD		\$	
0690	08130		MECHANICAL REINF COUPLER #5	49.00	EACH		\$	
0700	08131		MECHANICAL REINF COUPLER #6	5.00	EACH		\$	
0710	08150		STEEL REINFORCEMENT	14,831.00	LB		\$	
0720	08151		STEEL REINFORCEMENT-EPOXY COATED	19,819.00	LB		\$	
0730	08671		PRECAST PC BOX BEAM SB33	314.00	LF		\$	
0740	21532ED		RAIL SYSTEM TYPE III	161.10	LF		\$	
0750	23813EC		DECK DRAIN	4.00	EACH		\$	

PROPOSAL BID ITEMS

161049

Page 3 of 3

Report Date 10/25/16

Section: 0005 - WATERLINE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0760	14003		W CAP EXISTING MAIN	1.00	EACH		\$	
0770	14005		W ENCASEMENT CONCRETE	10.00	LF		\$	
0780	14012		W ENCASEMENT STEEL OPEN CUT RANGE 1	30.00	LF		\$	
0790	14023		W FLUSHING ASSEMBLY	1.00	EACH		\$	
0800	14057		W PIPE PVC 03 INCH (REVISED: 10-25-16)	150.00	LF		\$	
0810	14080		W SERV PE/PLST LONG SIDE 3/4 IN (REVISED:10-25-16)	1.00	EACH		\$	
0820	14081		W SERVICE RELOCATE	1.00	EACH		\$	
0830	14092		W TIE-IN 03 INCH	1.00	EACH		\$	
0840	14103		W VALVE 03 INCH	2.00	EACH		\$	

Section: 0006 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0850	02569		DEMOBILIZATION	1.00	LS		\$	